AD 2. AERODROMES

VEAT AD 2.1 AERODROME LOCATION INDICATOR AND NAME

VEAT - AGARTALA AIRPORT, AGARTALA

VEAT AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome reference point coordinates and its site	235326N 0911421E M. Brg.198.75 DEG/796 M from physical extremity of RWY 18.	
2	Direction and distance of aerodrome reference point from the centre of the city or town which the aerodrome serves	334 DEG/10.5KM from Agartala	
3	Aerodrome elevation and reference temperature	56 FT / 33.0 DEG C	
4	Magnetic variation, date of information and annual change	0.50 DEG W (2010) /0.00	
5	Name of aerodrome operator, address, telephone, telefax, e-mail address, AFS address, website (if available)	The Airport Director Airports Authority of India, Agartala Airport, Agartala - 799009	
		Telephone:	(91) 3812342224 (91) 9436123556
		Fax:	(91) 381 2342085
		AFS:	VEATYHYX
		Email:	apdagartala@AAI.AERO
6	Types of traffic permitted (IFR/VFR)	IFR/VFR	
7	Remarks	Vertical Datum: EGM08	

VEAT AD 2.3 OPERATIONAL HOURS

1	Aerodrome Operator	MON-FRI 0400-1230 UTC (0930-1800 IST) SAT, SUN+ HOL: Nil	
2	Custom and immigration	As ATS	
3	Health and sanitation	First Aid Facility within ATS hours	
4	AIS briefing office	AS ATS	
5	ATS reporting office (ARO)	As ATS	
6	MET Briefing office	As ATS	
7	Air Traffic Service	Consult NOTAMs for current ATS HR.	
8	Fuelling	As ATS	
9	Handling	As ATS	
10	Security	As ATS	
11	De-icing	NIL	
12	Remarks	Outside of ATS hours service available O/R with one-hour PN to The Airport Director. Consult NOTAMs for current ATS hours. Early watch on 24HR PN.	
		ATS approved hourly runway traffic handling capacity	Maximum number of arrival and departure- 12 (The Minimum Spacing BTN two successive ARR shall be more than 5 Min) Maximum number of arrival only – 06 Maximum number of departure only -10

VEAT AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo-handling facilities	Manual

2	Fuel and Oil types	JET A1
3	Fuelling facilities and capacity	IOCL -3 Bowsers (11+11+10) KL underground tank capacity 280 KL (70 KL X 4 tank) BPCL: 3 Bowsers (15+15+27) KL
4	De-icing facilities	NIL
5	Hangar space for visiting aircraft	i. Location: End of Taxiway C ii. Surface: Concrete iii. PCN: 43/R/A/W/T iv. Suitability: Up to A 321-200 type of aircraft.
6	Repair facilities for visiting aircraft	NIL
7	Remarks	NIL

VEAT AD 2.5 PASSENGER FACILITIES

1	Hotel(s) at or in the vicinity of aerodrome	In the city.
2	Restaurant(s) at or in the vicinity of aerodrome	At AD and in the city
3	Transportation possibilities	Buses, and Autos from AD.
4	Medical Facilities	First aid at AD. Hospital in the city.
5	Bank and post office at or in the vicinity of aerodrome	Banks: ATM Post office: 1 KM from Airport.
6	Tourist office	Available at Aerodrome and in the city.
7	Remarks	NIL

VEAT AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	Within ATS HR: CAT-7
2	Rescue equipment	AVBL. as per category
3	Capability for removal of disabled aircraft	1. The critical aircraft for the airport is -A321. 2. Primary responsibility for removal of disabled aircraft rests with the concerned airline. 3. The airlines may contact 'Aerodrome Coordinator for Disabled Aircraft Removal Operations' for coordinating with the agencies having Disabled Aircraft Recovery Kit. 4. Contact Details of Aerodrome Coordinator for Disabled Aircraft Removal Operations: Aerodrome coordinator - Airport Director. Email: apdagartala@aai.aero Contact No: 9436123556 / 0381- 2342224 / FAX-0381-2342085
4	Remarks	NIL

VEAT AD 2.7 SEASONAL AVAILABILITY CLEARING

1	Type(s) of clearing equipment	NIL
2	Clearance priorities	NIL
3	Remarks	NIL

VEAT AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Designation, surface and strength of aprons	Refer Aircraft Parking/Docking Chart.
2	Designation, width, surface and strength of taxiways	Refer Aircraft Parking/Docking Chart.
3	Location and elevation of altimeter checkpoints	NIL
4	Location of VOR checkpoints	TWY B: 235336.44N 0911432.43E/ ELEV: 55FT TWY D: 235331.50N 0911432.00E/ ELEV: 56FT TWY F: 235312.94N 0911430.73E/ ELEV: 51FT TWY G: 235305.65N 0911430.14E/ ELEV: 51FT Gravity Model: EGM 08
5	Position of INS checkpoints	Not Established
6	Remarks	**1. Coordinates of RWY Holding Position** **TWY — Coordinates — Elevation(Ft)** TWY A — 235342.91N 0911437.94E — 57 TWY B — 235336.77N 0911431.87E — 55 TWY C — 235338.05N 0911425.87E — 54 TWY D — 235331.51N 0911431.82E — 56 TWY E — 235328.26N 0911431.56E — 55 **2. Coordinates of RWY and TWY Intersection** **TWY — Coordinates — Elevation(Ft)** TWY B — 235338.38N 0911429.12E — 55 TWY C — 235340.79N 0911429.32E — 55 TWY D — 235331.74N 0911428.58E — 54 TWY E — 235328.49N 0911428.31E — 55 3.Apron Dimension: 297X233 FT, 272X252 FT, 512X233 FT. 4. Apron PCN: 65/R/D/X/T. 5. Isolation Bays: Refer Aircraft Parking/Docking Chart 6. Distance of TWY B, TWY D and TWY E are 264M, 591M and 691M respectively from beginning of RWY18. 7. Length of TWY D and TWY E: 78.5M. 8. Shoulder of TWY D and TWY E: 3.5M. 9. Shoulder of TWY A, TWY B and TWY C: 7.5M. 10. Operations on parking stand nos. 4 and 5 restricted to daytime only due to insufficient lighting in the apron. 11. **NEW APRON:** i. Critical Aircraft: A321 in Power In Push back configuration. ii. New Apron is connected to Fire Station and New Terminal Building. iii. Taxiway connected to RWY & New Apron – TWY ‘F’ & TWY ‘G’. iv. Surface and Strength: Concrete, 60/R/A/W/T

VEAT AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand identification signs, taxiway guidelines and visual docking/parking guidance system at aircraft stands	Taxiing guidance provided on R/T Guidelines and Edge lights AVBL at Apron. AVDGS available on stand No. 07, 08, 09 and 10.
2	Runway and taxiway markings and lights	RWY Markings: Designation, THR, TDZ, Centreline, Fixed distance, side strips, END RWY Lights: THR, Edge, End TWY Marking: Centre-line, Holding Point, Side stripe, Transverse Stripe TWY Lights: Edge TWY Guidance Signs: Intersection of TWY and RWY and Holding Points
3	Stop bars (if any)	NIL
4	Remarks	Runway guard lights provided at all holding points on Taxiways A, B, C, D, E, F, G AND H

VEAT AD 2.10 AERODROME OBSTACLES

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
36/TKOF 18/APCH	OTHER	235352.9N 0911430.3E	55 FT	NO	Approach Light
36/TKOF 18/APCH	FENCE	235353.3N 0911435.5E	59 FT	NO	Airport Boundary Wall with Fencing on Top
36/TKOF 18/APCH	FENCE	235353.8N 0911434.8E	60 FT	NO	Airport Boundary Wall with Fencing on Top
36/TKOF 18/APCH	BUILDING	235355.4N 0911434.6E	64 FT	NO	Building
36/TKOF 18/APCH	BUILDING	235354.9N 0911426.8E	64 FT	NO	Security Hut
36/TKOF 18/APCH	OTHER	235353.1N 0911435.4E	62 FT	NO	Mobile Road Traffic (Road Elev.14.0 M +Traffic Ht.5.0 M)
36/TKOF 18/APCH	TREE	235407.1N 0911436.2E	91 FT	NO	Group of Tree
36/TKOF 18/APCH	BUILDING	235355.2N 0911433.7E	72 FT	NO	Security Hut
36/TKOF 18/APCH	TREE	235409.8N 0911437.0E	106 FT	NO	Tree
36/TKOF 18/APCH	TREE	235405.6N 0911435.4E	98 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235408.6N 0911436.7E	106 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235412.7N 0911438.2E	115 FT	NO	Tree
36/TKOF 18/APCH	TREE	235406.4N 0911437.1E	103 FT	NO	Tree
36/TKOF 18/APCH	TREE	235359.5N 0911435.8E	94 FT	NO	Tree
36/TKOF 18/APCH	TREE	235400.3N 0911434.5E	96 FT	NO	Group of Tree

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
36/TKOF 18/APCH	TREE	235356.3N 0911434.2E	90 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235406.8N 0911438.1E	115 FT	NO	Tree
36/TKOF 18/APCH	TREE	235401.7N 0911435.6E	105 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235403.2N 0911435.6E	108 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235401.1N 0911434.6E	106 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235354.1N 0911434.9E	93 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235353.6N 0911435.1E	93 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235403.8N 0911435.5E	115 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235358.2N 0911435.6E	110 FT	NO	Tree
36/TKOF 18/APCH	TREE	235357.3N 0911436.1E	114 FT	NO	Group of Tree
36/TKOF 18/APCH	TREE	235356.0N 0911436.1E	121 FT	NO	Group of Tree
36/APCH 18/TKOF	GATE	235229.7N 0911427.7E	67 FT	NO	Gate Top
36/APCH 18/TKOF	OTHER	235228.1N 0911419.2E	71 FT	NO	Flood Light
36/APCH 18/TKOF	BUILDING	235226.3N 0911427.1E	74 FT	NO	Security Hut
36/APCH 18/TKOF	POLE	235225.2N 0911427.0E	76 FT	NO	Electric Pole
36/APCH 18/TKOF	TREE	235224.6N 0911425.8E	78 FT	NO	Group of Tree
36/APCH 18/TKOF	OTHER	235234.9N 0911423.9E	58 FT	NO	Approach Light
36/APCH 18/TKOF	TREE	235217.0N 0911420.7E	95 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235212.4N 0911416.5E	105 FT	NO	Group of Tree
36/APCH 18/TKOF	POLE	235230.5N 0911427.4E	67 FT	NO	Light Pole
36/APCH 18/TKOF	TREE	235214.1N 0911423.0E	101 FT	NO	Group of Tree
36/APCH 18/TKOF	OTHER	235231.8N 0911420.6E	66 FT	NO	Mobile Road Traffic (Road Elev.15.2 M + Traffic Ht.5.0 M.)
36/APCH 18/TKOF	POLE	235231.4N 0911427.4E	67 FT	NO	Light Pole
36/APCH 18/TKOF	BUILDING	235231.3N 0911428.5E	67 FT	NO	Building
36/APCH 18/TKOF	POLE	235226.6N 0911427.5E	77 FT	NO	Electric Pole

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
36/APCH 18/TKOF	TREE	235217.7N 0911424.9E	95 FT	NO	Group of Tree
36/APCH 18/TKOF	FENCE	235232.5N 0911427.8E	66 FT	NO	Airport Boundary Wall with Fencing on Top
36/APCH 18/TKOF	TREE	235213.7N 0911425.2E	104 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235215.4N 0911418.9E	101 FT	NO	Group of Tree
36/APCH 18/TKOF	POLE	235232.4N 0911427.5E	66 FT	NO	Light Pole
36/APCH 18/TKOF	TREE	235229.1N 0911419.9E	75 FT	NO	Group of Tree
36/APCH 18/TKOF	FENCE	235233.6N 0911428.9E	65 FT	NO	Airport Boundary Wall with Fencing on Top
36/APCH 18/TKOF	POLE	235227.6N 0911427.8E	77 FT	NO	Electric Pole
36/APCH 18/TKOF	TREE	235217.6N 0911419.9E	99 FT	NO	Group of Tree
36/APCH 18/TKOF	POLE	235234.0N 0911428.0E	65 FT	NO	Light Pole
36/APCH 18/TKOF	BUILDING	235234.1N 0911419.8E	66 FT	NO	Building
36/APCH 18/TKOF	TREE	235224.9N 0911420.2E	86 FT	NO	Group of Tree
36/APCH 18/TKOF	POLE	235234.4N 0911427.5E	67 FT	NO	Light Pole
36/APCH 18/TKOF	POLE	235228.7N 0911428.2E	78 FT	NO	Electric Pole
36/APCH 18/TKOF	TREE	235216.9N 0911426.4E	102 FT	NO	Group of Tree
36/APCH 18/TKOF	OTHER	235233.8N 0911428.9E	68 FT	NO	Mobile Road Traffic (Road Elev.15.8 M +Traffic Ht.5.0 M)
36/APCH 18/TKOF	TREE	235216.2N 0911426.5E	104 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235225.7N 0911420.9E	86 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235215.5N 0911421.3E	107 FT	NO	Group of Tree
36/APCH 18/TKOF	POLE	235229.8N 0911428.3E	78 FT	NO	Electric Pole
36/APCH 18/TKOF	TREE	235220.5N 0911425.2E	98 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235216.5N 0911421.5E	106 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235215.9N 0911423.4E	107 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235214.9N 0911416.0E	110 FT	NO	Group of Tree
36/APCH 18/TKOF	POLE	235230.7N 0911428.3E	78 FT	NO	Electric Pole

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
36/APCH 18/TKOF	TREE	235219.8N 0911427.2E	100 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235221.7N 0911425.5E	97 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235226.0N 0911426.3E	88 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235223.6N 0911426.3E	93 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235228.2N 0911427.8E	86 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235225.5N 0911427.5E	93 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235214.5N 0911417.3E	117 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235221.3N 0911425.4E	104 FT	NO	Group of Tree
36/APCH 18/TKOF	BUILDING	235233.7N 0911428.1E	80 FT	NO	Security Hut
36/APCH 18/TKOF	TREE	235221.2N 0911427.5E	107 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235225.2N 0911428.7E	100 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235224.8N 0911428.7E	103 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235227.1N 0911428.0E	98 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235224.0N 0911427.9E	105 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235234.6N 0911420.1E	87 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235227.8N 0911428.1E	100 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235228.2N 0911429.3E	101 FT	NO	Group of Tree
36/APCH 18/TKOF	TREE	235232.8N 0911428.6E	98 FT	NO	Group of Tree
In circling area and at AD	OTHER	235356.2N 0911433.8E	62 FT	NO	Mobile Road Traffic(Road Elev.13.9 M + Traffic Ht.5.0 M.)
In circling area and at AD	SIGN	235339.8N 0911430.7E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235339.5N 0911430.7E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235338.7N 0911425.4E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235341.9N 0911427.9E	57 FT	NO	Sign Board
In circling area and at AD	SIGN	235341.5N 0911431.5E	58 FT	NO	Sign Board
In circling area and at AD	SIGN	235343.7N 0911431.0E	58 FT	NO	Sign Board

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	SIGN	235337.5N 0911432.4E	58 FT	NO	Sign Board
In circling area and at AD	BUILDING	235342.6N 0911425.8E	60 FT	NO	Hut
In circling area and at AD	OTHER	235339.0N 0911434.0E	61 FT	NO	Electric Box
In circling area and at AD	POLE	235342.2N 0911425.2E	61 FT	NO	Light Pole
In circling area and at AD	POLE	235341.4N 0911424.4E	61 FT	NO	Light Pole
In circling area and at AD	POLE	235342.9N 0911425.9E	62 FT	NO	Light Pole
In circling area and at AD	POLE	235343.9N 0911426.1E	63 FT	NO	Light Pole
In circling area and at AD	POLE	235350.7N 0911426.6E	62 FT	NO	Light Pole
In circling area and at AD	POLE	235345.8N 0911426.2E	63 FT	NO	Light Pole
In circling area and at AD	POLE	235344.8N 0911426.2E	64 FT	NO	Light Pole
In circling area and at AD	POLE	235347.7N 0911426.3E	64 FT	NO	Light Pole
In circling area and at AD	BUILDING	235339.3N 0911433.5E	67 FT	NO	GP Hut (Old)
In circling area and at AD	BUILDING	235340.4N 0911433.8E	67 FT	NO	GP Hut (New)
In circling area and at AD	OTHER	235340.5N 0911433.7E	108 FT	LGTD	New GP Main Antenna with Lightning Arrester Top
In circling area and at AD	OTHER	235340.5N 0911433.8E	76 FT	LGTD	New GP DME Antenna with Lightning Arrester Top
In circling area and at AD	OTHER	235342.7N 0911433.8E	73 FT	LGTD	New GP Monitor Antenna with Lightning Arrester Top
In circling area and at AD	OTHER	235342.3N 0911433.8E	72 FT	LGTD	OLD GP Monitor Antenna
In circling area and at AD	OTHER	235339.6N 0911433.6E	101 FT	LGTD	OLD GP Main Antenna
In circling area and at AD	OTHER	235353.1N 0911426.7E	67 FT	NO	Mobile Road Traffic (Road Elev.15.4 M. + Traffic Ht.5.0 M.)
In circling area and at AD	OTHER	235338.8N 0911433.5E	91 FT	NO	Arrester on MET Antenna
In circling area and at AD	OTHER	235339.6N 0911433.6E	104 FT	NO	Arrester on GP Main Antenna
In circling area and at AD	OTHER	235247.3N 0911423.6E	55 FT	NO	PAPI Light
In circling area and at AD	POLE	235242.9N 0911421.1E	59 FT	NO	Light Pole

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	POLE	235243.9N 0911421.2E	59 FT	NO	Light Pole
In circling area and at AD	POLE	235237.1N 0911421.0E	61 FT	NO	Light Pole
In circling area and at AD	FENCE	235235.1N 0911420.5E	63 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	GATE	235235.5N 0911420.5E	63 FT	NO	Gate
In circling area and at AD	FENCE	235235.5N 0911419.5E	64 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	FENCE	235242.5N 0911420.7E	62 FT	NO	Airport Boundary Wall
In circling area and at AD	FENCE	235240.0N 0911420.5E	63 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	FENCE	235235.3N 0911420.3E	64 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	FENCE	235241.9N 0911420.6E	63 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	FENCE	235244.5N 0911420.8E	64 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	POLE	235235.3N 0911427.6E	66 FT	NO	Light Pole
In circling area and at AD	POLE	235236.3N 0911427.6E	66 FT	NO	Light Pole
In circling area and at AD	OTHER	235235.1N 0911420.7E	67 FT	NO	Mobile Road Traffic (Road Elev.15.3 M +Traffic Ht.5.0 M)
In circling area and at AD	BUILDING	235243.5N 0911428.3E	65 FT	NO	Security Hut
In circling area and at AD	TREE	235237.3N 0911428.0E	70 FT	NO	Group of Tree
In circling area and at AD	BUILDING	235235.6N 0911419.5E	77 FT	NO	Security Hut
In circling area and at AD	TREE	235235.6N 0911428.4E	78 FT	NO	Group of Tree
In circling area and at AD	SIGN	235330.4N 0911429.9E	55 FT	NO	Sign Board
In circling area and at AD	SIGN	235329.6N 0911429.9E	55 FT	NO	Sign Board
In circling area and at AD	SIGN	235313.9N 0911429.2E	55 FT	NO	Sign Board
In circling area and at AD	SIGN	235312.2N 0911429.1E	55 FT	NO	Sign Board
In circling area and at AD	SIGN	235306.6N 0911428.6E	55 FT	NO	Sign Board
In circling area and at AD	SIGN	235333.7N 0911430.2E	55 FT	NO	Sign Board

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	235325.2N 0911432.9E	56 FT	NO	Electric Box
In circling area and at AD	SIGN	235315.7N 0911428.6E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235303.2N 0911427.6E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235335.8N 0911430.4E	56 FT	NO	Sign Board
In circling area and at AD	OTHER	235325.8N 0911431.5E	56 FT	NO	Electric Box
In circling area and at AD	SIGN	235308.4N 0911428.0E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235337.4N 0911426.4E	56 FT	NO	Sign Board
In circling area and at AD	SIGN	235335.9N 0911431.7E	57 FT	NO	Sign Board
In circling area and at AD	OTHER	235326.1N 0911431.2E	57 FT	NO	Landing T
In circling area and at AD	POLE	235304.3N 0911429.4E	57 FT	NO	Pole
In circling area and at AD	POLE	235258.5N 0911428.9E	58 FT	NO	Pole
In circling area and at AD	SIGN	235330.2N 0911431.7E	58 FT	NO	Sign Board
In circling area and at AD	OTHER	235329.9N 0911431.6E	58 FT	NO	Flood Light Mast
In circling area and at AD	POLE	235318.9N 0911430.6E	59 FT	NO	Light Pole
In circling area and at AD	POLE	235316.9N 0911430.4E	59 FT	NO	Light Pole
In circling area and at AD	OTHER	235335.1N 0911432.4E	59 FT	NO	Flood Light Mast
In circling area and at AD	OTHER	235333.4N 0911431.9E	59 FT	NO	Flood Light Mast
In circling area and at AD	POLE	235306.2N 0911423.2E	59 FT	NO	Light Pole
In circling area and at AD	SIGN	235325.7N 0911432.1E	59 FT	NO	Sign Board
In circling area and at AD	SIGN	235325.1N 0911431.4E	59 FT	NO	Sign Board
In circling area and at AD	OTHER	235334.0N 0911432.0E	59 FT	NO	Flood Light Mast
In circling area and at AD	POLE	235315.9N 0911430.3E	60 FT	NO	Light Pole
In circling area and at AD	POLE	235315.0N 0911430.3E	60 FT	NO	Light Pole
In circling area and at AD	POLE	235310.1N 0911429.8E	60 FT	NO	Pole
In circling area and at AD	BUILDING	235308.1N 0911422.7E	60 FT	NO	Birds Chaser Hut
In circling area and at AD	POLE	235257.5N 0911422.4E	61 FT	NO	Light Pole

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	FENCE	235253.4N 0911421.7E	62 FT	NO	Airport Boundary Wall with Fencing on Top
In circling area and at AD	POLE	235253.5N 0911420.8E	62 FT	NO	Light Pole
In circling area and at AD	POLE	235317.9N 0911430.5E	62 FT	NO	Light Pole
In circling area and at AD	BUILDING	235254.7N 0911429.2E	63 FT	NO	Birds Chaser Hut
In circling area and at AD	POLE	235254.6N 0911422.2E	63 FT	NO	Light Pole
In circling area and at AD	POLE	235316.0N 0911424.0E	63 FT	NO	Light Pole
In circling area and at AD	POLE	235253.6N 0911422.1E	63 FT	NO	Light Pole
In circling area and at AD	POLE	235316.9N 0911423.8E	65 FT	NO	Light Pole
In circling area and at AD	BUILDING	235318.9N 0911431.3E	66 FT	NO	Security Hut
In circling area and at AD	BUILDING	235316.7N 0911423.5E	67 FT	NO	Security Hut
In circling area and at AD	TREE	235251.2N 0911429.3E	73 FT	NO	Group of Tree
In circling area and at AD	TREE	235316.5N 0911423.4E	76 FT	NO	Tree
In circling area and at AD	OTHER	235326.0N 0911431.5E	76 FT	NO	Obstacle Light on Windsock
In circling area and at AD	OTHER	235339.6N 0911433.6E	77 FT	NO	DME (Co-located with Glide Path) Antenna
In circling area and at AD	ANTENNA	235339.3N 0911433.4E	83 FT	NO	Antenna
In circling area and at AD	OTHER	235337.6N 0911434.4E	60 FT	NO	Flood Light Mast
In circling area and at AD	BUILDING	235353.4N 0911435.8E	65 FT	NO	Building
In circling area and at AD	OTHER	235337.4N 0911434.0E	60 FT	NO	Flood Light Mast
In circling area and at AD	TREE	235351.8N 0911437.6E	94 FT	NO	Group of Tree
In circling area and at AD	TREE	235351.0N 0911421.8E	107 FT	NO	Group of Tree
In circling area and at AD	TREE	235354.0N 0911439.8E	120 FT	NO	Group of Tree
In circling area and at AD	TREE	235352.8N 0911422.6E	102 FT	NO	Group of Tree
In circling area and at AD	TREE	235352.7N 0911436.5E	88 FT	NO	Group of Tree
In circling area and at AD	TREE	235352.7N 0911438.5E	116 FT	NO	Group of Tree
In circling area and at AD	TREE	235354.9N 0911437.5E	107 FT	NO	Group of Tree

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	TREE	235342.4N 0911424.4E	85 FT	NO	Group of Tree
In circling area and at AD	TREE	235400.0N 0911437.9E	110 FT	NO	Group of Tree
In circling area and at AD	TREE	235358.1N 0911437.5E	109 FT	NO	Tree
In circling area and at AD	TREE	235355.0N 0911436.3E	100 FT	NO	Group of Tree
In circling area and at AD	TREE	235357.7N 0911423.3E	122 FT	NO	Group of Tree
In circling area and at AD	POLE	235246.7N 0911431.5E	76 FT	NO	Electric Pole
In circling area and at AD	TREE	235239.0N 0911416.3E	99 FT	NO	Group of Trees
In circling area and at AD	TREE	235245.9N 0911431.5E	83 FT	NO	Group of Tree
In circling area and at AD	TREE	235225.3N 0911415.2E	102 FT	NO	Group of Tree
In circling area and at AD	POLE	235233.6N 0911418.0E	75 FT	NO	Electric Pole
In circling area and at AD	BUILDING	235233.9N 0911418.5E	69 FT	NO	Building
In circling area and at AD	POLE	235231.7N 0911417.9E	77 FT	NO	Electric Pole
In circling area and at AD	TREE	235240.8N 0911415.5E	121 FT	NO	Group of Tree
In circling area and at AD	TREE	235246.8N 0911417.7E	103 FT	NO	Group of Tree
In circling area and at AD	OTHER	235231.2N 0911417.9E	86 FT	NO	Flood Light (Border)
In circling area and at AD	TREE	235224.0N 0911415.5E	112 FT	NO	Group of Tree
In circling area and at AD	TREE	235245.3N 0911417.9E	101 FT	NO	Group of Tree
In circling area and at AD	TREE	235231.0N 0911416.8E	103 FT	NO	Group of Tree
In circling area and at AD	TREE	235233.4N 0911429.7E	95 FT	NO	Group of Tree
In circling area and at AD	POLE	235235.6N 0911417.4E	105 FT	NO	Electric Pole
In circling area and at AD	TREE	235239.9N 0911417.7E	107 FT	NO	Group of Tree
In circling area and at AD	TREE	235247.0N 0911431.5E	112 FT	NO	Group of Tree
In circling area and at AD	TREE	235230.3N 0911429.3E	108 FT	NO	Group of Tree
In circling area and at AD	TREE	235234.7N 0911418.5E	103 FT	NO	Group of Tree
In circling area and at AD	TREE	235229.2N 0911429.6E	118 FT	NO	Group of Tree
In circling area and at AD	TREE	235257.5N 0911434.4E	104 FT	NO	Group of Tree

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	235328.5N 0911439.2E	135 FT	NO	Arrester on New ATC
In circling area and at AD	POLE	235247.9N 0911431.5E	76 FT	NO	Electric Pole
In circling area and at AD	OTHER	235317.1N 0911422.2E	60 FT	NO	Electric Panel
In circling area and at AD	TREE	235325.9N 0911437.0E	109 FT	NO	Tree
In circling area and at AD	POLE	235319.9N 0911432.8E	61 FT	NO	Light Pole
In circling area and at AD	BUILDING	235321.3N 0911422.1E	68 FT	NO	Old DVOR Hut Disused
In circling area and at AD	BUILDING	235315.6N 0911433.2E	71 FT	NO	Temple
In circling area and at AD	OTHER	235325.2N 0911436.3E	103 FT	NO	Antenna on Fire Station
In circling area and at AD	BUILDING	235331.3N 0911437.3E	110 FT	NO	Old ATC
In circling area and at AD	OTHER	235338.5N 0911439.0E	127 FT	NO	Flood Light Mast
In circling area and at AD	OTHER	235331.4N 0911437.5E	114 FT	NO	Beacon on Old ATC
In circling area and at AD	TREE	235315.6N 0911433.4E	78 FT	NO	Tree
In circling area and at AD	TREE	235257.7N 0911433.0E	94 FT	NO	Group of Tree
In circling area and at AD	TREE	235321.3N 0911422.0E	74 FT	NO	Tree
In circling area and at AD	TREE	235254.0N 0911432.6E	97 FT	NO	Group of Tree
In circling area and at AD	TREE	235248.5N 0911430.1E	70 FT	NO	Group of Tree
In circling area and at AD	OTHER	235331.3N 0911437.3E	122 FT	NO	Antenna on Old ATC
In circling area and at AD	TREE	235256.0N 0911432.6E	102 FT	NO	Group of Tree
In circling area and at AD	TREE	235251.9N 0911432.0E	100 FT	NO	Group of Tree
In circling area and at AD	TREE	235248.8N 0911418.2E	103 FT	NO	Group of Tree
In circling area and at AD	TREE	235250.3N 0911418.3E	107 FT	NO	Group of Tree
In circling area and at AD	TREE	235250.7N 0911432.0E	107 FT	NO	Group of Tree
In circling area and at AD	OTHER	235328.5N 0911435.3E	114 FT	NO	Flood Light Mast
In circling area and at AD	TREE	235248.7N 0911431.7E	111 FT	NO	Group of Tree
In circling area and at AD	OTHER	235330.1N 0911435.4E	115 FT	NO	Flood Light Mast
In circling area and at AD	OTHER	235331.7N 0911435.5E	115 FT	NO	Flood Light Mast

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	235334.2N 0911437.0E	133 FT	NO	Flood Light Mast
In circling area and at AD	TREE	235249.2N 0911433.1E	136 FT	NO	Group of Tree
In circling area and at AD	OTHER	235230.6N 0911637.5E	206 FT	NO	Cell Phone Mast
In circling area and at AD	OTHER	235256.9N 0911534.6E	227 FT	NO	Cell Phone Mast
In circling area and at AD	OTHER	235217.8N 0911714.3E	469 FT	NO	BSNL Micro Tower

VEAT AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

1	Name of the associated meteorological office	AMO Agartala
2	Hours of service and, where applicable, the designation of the responsible meteorological office outside these hours	As ATS
3	Office responsible for preparation of TAFs and periods of validity and interval of issuance of the forecasts	Agartala/Kolkata 9 [03-12, 06-15, 09-18, 12-21,15-24, 18-03 AND 21-06]
4	Availability of the trend forecast for the aerodrome and interval of issuance	Trend Type landing forecast during watch hours 30 Min
5	Information on how briefing and/or consultation is provided	Provided
6	Types of flight documentation supplied and language(s) used in flight documentation	Tabular Form (English)
7	Charts and other information displayed or available for briefing or consultation	Analysed surface and upper air chart, INSAT bulletin and satellite pictures
8	Supplementary equipment available for providing information on meteorological conditions, e.g. weather radar and receiver for satellite images;	Telefax, Satellite display work station, internet, HSDT DCWIS PROVIDED AT TDZ RWY 18
9	The air traffic services unit(s) provided with meteorological information	Agartala ATC AND ACS,
10	Additional information, e.g. concerning any limitation of service.	WX RADAR observation

VEAT AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

Designations	TRUE Bearings	Dimensions of RWY (M)	Strength of pavement (PCN) and associated data) and surface of runway and associated stopways	Geographical coordinates for threshold and runway end
1	2	3	4	5
18	184.32 DEG	2286 x 45 M	64/F/D/W/T Asphalt	THR: 235350.90N 0911430.15E RWY END: 235236.80N 0911424.07E
36	4.32 DEG	2286 x 45 M	64/F/D/W/T Asphalt	THR: 235236.80N 0911424.07E RWY END: 235350.90N 0911430.15E

THR elevation and highest elevation of TDZ of precision APP RWY	Slope of runway and associated stopway	Dimensions of stopway (M)	Dimensions of clearway (M)	Dimensions of strips (M)
6	7	8	9	10
THR: 54.0FT TDZ: 55.0FT	0.03%	NIL	NIL	2406 x 150 M
THR: 56.0FT TDZ: 55.0FT	-0.03%	NIL	NIL	2406 x 150 M

Dimensions of runway end safety areas	Location and description of arresting system (if any)	Existence of an obstacle-free zone	Remarks.
11	12	13	14
90M x 90M		NIL	All elevations in EGM 08.
90M x 90M		Nil	All elevations in EGM 08.

VEAT AD 2.13 DECLARED DISTANCES

RWY Designator	Take-off run available TORA (M)	Take-off distance available TODA (M)	Accelerate distance available ASDA (M)	Landing distance available LDA (M)	Remarks (including runway entry or start point where alternative reduced declared distances have been declared)
1	2	3	4	5	6
18	2286	2286	2286	2286	
36	2286	2286	2286	2286	

VEAT AD 2.14 APPROACH AND RUNWAY LIGHTING

Runway Designator	Type, length and intensity of approach lighting system	Runway threshold lights, colour and wing bars	Type of visual slope indicator system	Length of runway touchdown zone lights
1	2	3	4	5
18	SALS 420 M LIH	Green AVBL	PAPI LEFT/3.00 DEG MEHT (57.94FT)	NIL
36	SALS 420 M LIH	Green Not Available	PAPI LEFT/3.00 DEG MEHT (50.72FT)	NIL

Length, spacing, colour and intensity of runway centre line lights	Length, spacing, colour and intensity of runway edge lights	Colour of runway end lights and wing bars	Length and colour of stopway lights	Remarks
6	7	8	9	10
	2286 M 60 M White LIH	Red	NIL	Cross Bar at 300M
	2286 M 60 M White LIH	Red	NIL	Cross Bar at 300M Location of PAPI is at distance of 322M from beginning of RWY36.

VEAT AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Location, characteristics and hours of operation of aerodrome beacon/identification beacon (if any)	ABN	At Tower Building, FLG W&G EV2SEC As ATS HR
		IBN	NIL
2	Location and lighting (if any) of anemometer/ landing direction indicator;	LDI	South of Apron, lighted
		Anemometer	At TWR Bldg, Not lighted
3	Taxiway edge and taxiway centre line lights;	Edge	All TWY
		Centre Line	
4	Secondary power supply including switch-over time;	All lighting Switch-over time: 1 SECOND.	
5	Remarks	Apron markings and edge lights available.	

VEAT AD 2.16 HELICOPTER LANDING AREA

1	Geographical coordinates of the geometric centre of touchdown and lift-off (TLOF) or of each threshold of final approach and take-off (FATO) area	Not established
2	TLOF and/or FATO area elevation:	Not established
3	TLOF and FATO area dimensions to the nearest metre or foot, surface type, bearing strength and marking;	Not established
4	True bearings of FATO;	Not established
5	Declared distances available	Not established
6	Approach and FATO lighting;	Not established
7	Remarks	Not established

VEAT AD 2.17 AIR TRAFFIC SERVICE AIRSPACE

1	Airspace designation, geographical coordinates and lateral limits	CTR: Area bounded by lines joining points 242602N 0920949E; 234403N 0920949E then along India – Bangladesh Border up to point of origin.
2	Vertical limits	FL 200
3	Airspace classification	D
4	Call sign and language(s) of the air traffic services unit providing service;	Agartala TWR, English
5	Transition altitude	4000 FT
6	Hours of applicability	HO
7	Remarks	Limited to Indian territory

VEAT AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service Designation	Call sign	Channel(s)	SATVOICE Number(s), if available
1	2	3	4
APP	Agartala Tower	119.050 MHZ	
APP	Agartala Tower	120.400 MHZ	
TWR	Agartala TWR	118.050 MHZ	
TWR	Agartala TWR	119.050 MHZ	
ATIS	Agartala Information	128.800 MHZ	
ALRS	Emergency Frequency	121.500 MHZ	

Logon address, as appropriate	Hours of operation	Remarks
5	6	7
	HO	1. Functions of APP combined with TWR. 2. Backup FREQ
	As ATS	1. Functions of APP combined with TWR. 2. Main FREQ
	As ATS	NIL
	HO	Backup
	As ATS	NIL
	HO	NIL

VEAT AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of aids, magnetic variation and type of supported operation for ILS/ MLS, basic GNSS, SBAS and GBAS, and for VOR/ILS/MLS station used for technical lineup of the aid	Identification	Frequency(ies), Channel number(s), Service provider, and reference path identifier(s) (RPI), as appropriate	Hours of operation, as appropriate;
1	2	3	4
LOC 18 CAT I	IAGE	110.300 MHz	As ATS
GP 18		335.000 MHz	As ATS
DME ILS 18	IAGE	CH40X	As ATS
DVOR/DME	AAT	116.100 MHz CH108X	H24
NDB	AT	237 kHz	As ATS

Geographical coordinates of the position of the transmitting antenna	Elevation of transmitting antenna of DME/ elevation of GBAS reference point	Service volume radius from the GBAS reference point	Remarks
5	6	7	8
235226.7N 0911423.2E			
235340.5N 0911433.7E			Glide Angle: 3 DEG
235340.5N 0911433.8E	75 FT		1. Collocated with GP 18. 2. Gravity Model EGM 08.
235325.5N 0911419.1E	87 FT		1. Vertical datum: EGM08
235315.1N 0911436.5E			

VEAT AD 2.20 LOCAL AERODROME REGULATIONS

1. STAND ALLOTMENT PROCEDURES:

i. Airlines operator shall coordinate for parking bays with ATC Tower for their aircraft.

ii. The allotment of parking bay shall be done by Duty Officer Control Tower.

iii. Allotment of parking bays including PBB shall be normally done on first come first serve basis.

iv. Aircrafts will be allotted stand no. 06 to 11 as mentioned in PDC.

v. As far as practicable, last minute changes of allotted parking bay shall be avoided.

2. TAXIING PROCEDURES (From/To Runway):

i. TWY 'G' is available for entry to Apron and TWY 'F' is available for exit from Apron only.

ii. After landing, aircraft will back track RWY and vacate RWY via TWY 'G' and go straight and follow Taxi guidelines for parking at Bay No. 11.

iii. After landing, aircraft will back track RWY and vacate RWY via TWY 'G', turn left at the end of TWY 'G' to follow taxi guidelines for parking at Bay No. 6 to 10.

iv. All departure aircraft will turn left and then follow taxi guidelines to enter RWY via TWY 'F'.

3. PUSH BACK PROCEDURE:

i. **Stand 11:** For Runway 18/36 aircraft shall pushback following yellow guidelines facing north and pull forward till abeam stand 11 and start-up.

ii. **Stand 06 to 10:** For Runway 18/36 aircraft shall pushback following yellow guidelines facing north till abeam respective stands and start-up.

iii. Following cautions shall be taken during push back.

a) Simultaneous push back shall not be permitted.

b) Start up shall be given only after completion of push back with all necessary ground precautions.

c) Startup while pushing back shall not be allowed. Push back supervisor (airline staff) shall supervise during pushback for all necessary ground precautions and safe separations from ground equipment, vehicles, personnel or any other object on apron. Push back supervisor (Airline staff) will also supervise during start up and taxiing of aircraft till it takes the turn for TWY 'F'.

4. Visual Circling west of runway is not permitted due close proximity of Bangladesh border.

5. No Aircraft shall take lock turn/ pivotal turn on the Runway to avoid pavement damage.

6. LOW VISIBILITY PROCEDURES

1. INTRODUCTION

1.1 Until the latest amendment of DGCA Civil Aviation Requirements (CAR) section 8, Series 'C', Part-I on All-Weather Operations, Low visibility procedures were required at aerodromes for the purpose of ensuring safe operations during Categories II and III approaches and/or low visibility take-offs (LVTO).

1.2 However, in latest amendment to CAR (Rev. 10), para 5.3, following provision regarding Low visibility procedures is added. "An operator shall not conduct take-off with RVR/visibility less than standard Category I conditions of 550m RVR/800 m visibility unless low visibility procedures are enforced".

1.3 This provision necessitated the need for low visibility procedures for accommodating/permitting departures in Visibility/RVR less than 800M/550M even at such airports where there are no CAT II and CAT III operations.

1.4 As per provisions of Aerodrome Design and Operations CAR and ICAO Annex 14, Runway centre line lights are required for take-off in RVR below 400 M. Further, as per Aerodrome Design and operations CAR para 9.8.7, Surface Movement Radar (SMR) need to be provided at an aerodrome intended for use in Runway Visual Range conditions less than a value of 350 M.

1.5 Accordingly, Low visibility Procedures have been developed for Agartala Airport to accommodate/permit departures in Visibility/RVR less than 800M/550M from RWY 18 (runway served with RVR instruments). and since, there is no RWY centreline lights and SMR facility at Agartala Airport, these procedures will be applicable for take-off in VIS/RVR below 800M/550M but not less than 400 M RVR.

2. PURPOSE

2.1 The purpose of this document is to define the Standard Operating Procedures (SOP) for Low Visibility operation at Agartala Airport.

3. SCOPE

3.1 This is applicable to all the concerned personnel involved in the Low Visibility Operation as mentioned in this SOP.

3.2 The Low Visibility Procedure (LVP) describe the procedures and actions that are required to be taken by the Air Traffic Control (ATC), Pilots, Airline Operators, MET dept, Vehicle Operators, Airport Operations, Electrical Engg., CNS, Airport Fire Services and Ground Handling Agencies during Low Visibility Take-Offs at Agartala Airport.

3.3 The procedures contained in this document shall be read in conjunction with other applicable ICAO DOCs and Annexes / DGCA CARs and relevant circulars, AAI CHQ/RHQ instructions on the subject issued from time to time.

4. DEFINITIONS

4.1 Aerodrome Operating Minima:

The limits of usability of an aerodrome for:

a) take-off, expressed in terms of runway visual range and/or visibility and, if necessary, cloud conditions.

b) landing in 2D instrument approach operations, expressed in terms of visibility and/or runway visual range; minimum descent altitude/height (MDA/H) and, if necessary, cloud conditions; and

c) landing in 3D instrument approach operations, expressed in terms of visibility and/or runway visual range and decision altitude/height (DA/H) appropriate to the type and/or category of the operation.

4.2 Instrument approach operations (Annex 6): An approach and landing using instruments for navigation guidance based on an instrument approach procedure. There are two methods for executing instrument approach operations:

a) a two-dimensional (2D) instrument approach operation, using lateral navigation guidance only; and

b) a three-dimensional (3D) instrument approach operation, using both lateral and vertical navigation guidance

Note – Lateral and vertical navigation guidance refers to the guidance provided either by:

a) a ground-based radio navigation aid; or

b) computer-generated navigation data from ground-based, space-based, self-contained navigation aids or a combination of these.

Instrument approach operations shall be classified based on the designed lowest operating minima below which an approach operation shall only be continued with the required visual reference as follows:

a) Type A: a minimum descent height or decision height at or above 75 m (250 ft); and

b) Type B: a decision height below 75 m (250 ft). Type B instrument approach operations are categorized as:

i) Category I (CAT I): a decision height not lower than 60 m (200 ft) and with either a visibility not less than 800 m or a runway visual range not less than 550 m;

ii) Category II (CAT II): a decision height lower than 60 m (200 ft) but not lower than 30 m (100 ft) and a runway visual range not less than 300 m;

iii) Category III (CAT III): a decision height lower than 30 m (100 ft) or no decision height and a runway visual range less than 300 m or no runway visual range limitations.

4.3 Decision Altitude/Height: A specified altitude or height in a 3D instrument approach operation at which a missed approach must be initiated if the required visual reference to continue the approach has not been established.
Note: Decision altitude (DA) is referenced to mean sea level and decision height (DH) is referenced to the threshold elevation.

4.4 ILS Critical Area: An area of defined dimensions about the localizer and glide path antennas where aircraft and vehicles are excluded during all ILS operations. The critical area is protected because the presence of vehicles / or aircraft inside its boundaries will cause unacceptable disturbance to the ILS signal-in-space.

4.5 ILS Sensitive Area: An area extending beyond the ILS critical area where the parking and/or movement of vehicles, including aircraft, are controlled to prevent the possibility of unacceptable interference to the ILS signal during ILS operations. The sensitive area is protected to provide protection against interferences cause by large moving objects outside the critical area but still normally within the airfield boundary.

4.6 Low Visibility Procedures: Specific procedures applied at an aerodrome for the purpose of ensuring safe operations during Categories II/ III approaches and/or low visibility take-offs.

Note: As per para 5.3 of CAR on All Weather Operations, an operator shall not conduct take-off with RVR/Visibility less than standard CAT-I conditions of 550m RVR/800m Visibility unless low visibility procedures are enforced.

4.7 Low Visibility Take-Off (LVTO): A term used in relation to flight operations referring to a take-off on a Runway where the RVR is less than 400m.

4.8 Manoeuvring Area: That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.

4.9 Movement Area: That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, consisting of the manoeuvring area and the apron(s).

4.10 Visibility (Doc 9365): Visibility for aeronautical purposes is the greater of:

a) the greatest distance at which a black object of suitable dimensions, situated near the ground, can be seen and recognized when observed against a bright background;

b) the greatest distance at which lights in the vicinity of 1000 candelas can be seen and identified against an unlit background.

Note 1: The two distances have different values in air of a given extinction coefficient, and the latter b) varies with the background illumination. The former a) is represented by the meteorological optical range (MOR).

Note 2: The definition applies to the observations of visibility in local routine and special reports, to the observations of prevailing and minimum visibility reported in METAR and SPECI and to the observations of ground visibility.

5. ABBREVIATIONS

5.1 The abbreviations used in descriptions of Low Visibility Procedures have the following meanings:

ARFF: AIRCRAFT RESCUE & FIRE FIGHTING

AGL: AERONAUTICAL GROUND LIGHT

AOM: AERODROME OPERATING MINIMA

ATC: AIR TRAFFIC CONTROL

ATIS: AUTOMATIC TERMINAL INFORMATION SERVICE

CFT: CRASH FIRE TENDER

DG: DIESEL GENERATING SET

GP: GLIDE PATH

ILS: INSTRUMENT LANDING SYSTEM

IHP: INTERMEDIATE HOLDING POSITION

LOC: LOCALIZER

LSA: LOCALIZER SENSITIVE AREA

LVP: LOW VISIBILITY PROCEDURE

MID: MID POINT

MET: METEOROLOGY

NAV: NAVIGATIONAL

RVR: RUNWAY VISUAL RANGE

SMC: SURFACE MOVEMENT CONTROL

SP: SAFEGUARDING PROCEDURES

SSO: SHIFT SUPERVISORY OFFICER

TDZ: TOUCHDOWN ZONE

TSO: TOWER SUPERVISORY OFFICER

WSO: WATCH SUPERVISORY OFFICER

6. GENERAL

6.1 The Low Visibility Procedure (LVP) incorporates safeguarding measures to mitigate runway incursions and defines operational restrictions to ensure safe Airside Operations considering the available aerodrome facilities.

6.2 The provision mentioned in para 5.3 of DGCA Civil Aviation Requirements (CAR) (Rev.-10) section 8, Series ‘C’, Part- I on All-weather Operations necessitated the need of Low Visibility Procedures for accommodating/ permitting departures in Visibility/RVR less than 800M/550M at Agartala airport even though there are No CAT II and CAT III operations.

6.3 Accordingly, Low visibility Procedures have been developed for Agartala Airport to accommodate/permit departures in Visibility/RVR less than 800M/550M up to 400 M RVR from RWY 18.

7. MINIMUM REQUIREMENTS:

7.1 The following Aeronautical Ground lights and RVR equipment shall be serviceable to the required standard to support Low Visibility Procedures.

a) Runway edge lights,

b) Runway end lights,

c) Runway Guard lights

d) Road holding position lights

e) Apron flood lights

f) Instrumented RVR at the beginning (TDZ RVR).

g) Stand by Power supply to maintain switch over time of 1 Second for Runway Edge Lights

h) and Runway End Lights. This requirement can be met with the help of DG Set and/or UPS.

Unserviceability of Aeronautical Ground Lights/ Equipment before Implementation of LVP

Low Visibility Procedures will not be implemented when any of the light/equipment mentioned in para 4 above is un-serviceable or is not maintained as per the required standard.

Aeronautical Ground Lighting Facility	Un-serviceability	Restrictions
Runway Edge lights	More than 15% of all lights are unserviceable	LVP operations will be suspended.
	Any two consecutive lights or more are unserviceable	
Runway End lights	More than 15% of all lights are unserviceable	LVP operations will be suspended.
	Any two consecutive lights or more are unserviceable	
Standby Generators/UPS	Any of the generator/UPS is unserviceable	LVP operations will be suspended.

7.2 Unserviceability of Aeronautical Ground Lights / Equipment after Implementation of LVP:

When any of the light/equipment mentioned in para 4.1 above becomes un-serviceable or fails to meet the required standard during periods of LVP, TWR shall advise the aircraft accordingly and LVP shall be suspended and information to this effect shall be included in ATIS broadcast.

8. SAFEGUARDING PROCEDURES

8.1 Safeguarding Procedures (SP) are instructions for relevant airport departments to prepare ground services and facilities for low visibility operations in order that when LVP are implemented all safeguarding procedures are complete. WSO/Duty Officer Tower will initiate and co-coordinate with all the concerned agencies for completion of safeguarding procedures before implementation of Low Visibility Procedures.

8.2 Safeguarding Procedures shall be initiated when:

a) The Visibility/RVR is less than 1200m and visibility/RVR is forecast to deteriorate to 800m or less; and/or

b) The cloud ceiling is less than 400ft and forecast to fall to 200ft or less.

8.3 Whenever meteorological conditions stipulated in para 8.2 prevails or anticipated WSO shall coordinate with Airport Rescue Fire Station (ARFS) for implementing the Safeguarding Procedures (SP). WSO/Duty Officer Tower shall also coordinate with following agencies for initiation of implementation/ cancellation/completion of SP as appropriate.

a) Airport Operations

b) Civil & Electrical Engg. /Powerhouse

c) CNS /Equipment Room

d) Duty MET Officer

e) Concerned Airlines

f) CISF

8.4 When all the concerned agencies have completed their necessary actions, they shall report to WSO/Duty Officer Tower that their Safeguarding Procedure (SP) is completed, and the airport is safeguarded for LVP operations.

8.5 **Actions to be taken by Various Agencies:**

8.5.1 Before commencement of winter season, a meeting will be held by Airport Director in the month of October every year to inform all airlines and agencies operating at airport about their roles/ responsibilities and create awareness to ensure cooperation for safe airport operations during periods of low visibility.

8.5.2 All the agencies shall ensure that staff and drivers are suitably trained for Low visibility operations.

8.6 WSO/Duty Officer Tower shall ensure that the provision mentioned in para 8.7 are complied in respect of SP and proper log entry shall be made in respect of initiation of implementation/ cancellation/completion of SP as appropriate.

8.7 **Safeguarding procedures include:**

a) Positioning of CFTs at the predetermined positions (PDP)

b) Stopping of all maintenance works on the manoeuvring area as well as removal of all men and mobile equipment from the said area.

c) Ensuring availability of secondary power supply for change over time of maximum one second for RWY Edge and RWY End lights supported by UPS. RWY Edge and RWY End lights may continue to operate on main power supply during safeguarding Procedures. Whenever, LVP is to be implemented as per para 9 below, the RWY Edge and RWY End lights shall be put on Standby Power Supply (DG set or UPS). This operation needs to be completed before LVP is implemented.

As UPS is available at Agartala Airport and is capable of maintaining the required AGL system (refer table under para 7.2) with one second of Switch Over time with Main Supply, the main supply can continue to be primary supply, and the Generator Supply can be kept as Standby Power supply. In case of UPS is unserviceable, Generator supply will become primary source of power supply and Main power supply shall act as standby power supply.

d) Ensuring that Runways, Taxiways and other associated facilities such as Markings, Aeronautical Ground Lights are inspected within one hour preceding the implementation of LVP Operations. This is done to ensure that the lighting systems and markings are serviceable as described. Inspections should continue every 2 hours while LVP is in progress. These lighting inspections should be accorded priority and, if necessary, aircraft operations may be delayed.

e) Ensure all access roads are closed by switching on Road Holding position lights and placing temporary barricades at road holding position. Road Holding position lights shall be switched on by electrical jeep and temporary barricades shall be placed by Operation Dept.

9. LOW VISIBILITY PROCEDURES-TAKE OFF

Implementation of Low Visibility Take off Procedures:

9.1 MET officer shall inform when Visibility/RVR reduces to 800 Meters or below and/ or cloud ceiling is at 200 ft or below. WSO/Duty officer, ATC Tower shall coordinate with all the agencies to confirm whether the Safeguarding procedures have been completed or not. When Visibility/RVR falls below 800M/550M and or Cloud Ceiling is 200 ft or below and safeguarding procedures are complete WSO/Duty Officer Tower will implement Low Visibility Procedures. WSO/Duty Officer Tower shall inform all users of the imposition of low visibility take off procedures.

9.2 A take-off alternate aerodrome shall be selected and specified in the operational flight plan if either the meteorological conditions at the aerodrome of departure are below the operator's established aerodrome landing minima for that operation or if it would not be possible to return to the aerodrome of departure for other reasons.

9.3 Take-off minima established by the operator must be expressed as visibility or RVR limits, consideration all relevant factors for each aerodrome planned to be used and the aeroplane characteristics.

10. **ACTIONS BY VARIOUS UNITS DURING LVP**

10.1 Actions by ATC:

a) Inform CNS, Aircraft Rescue & Fire Fighting Services, Terminal Manager/Airside operations, Electrical, Civil, MT, CISF etc.

b) Only one aircraft shall be permitted at a time on the manoeuvring area during the time LVP is in force.

c) Towing of aircraft during LVP will be permitted only in case of extreme operational requirement. TWR shall ensure that the towing of aircraft is done under escort of "Follow Me" vehicles. "Follow Me" shall follow the route cleared by ATC.

d) TWR shall not permit any ground run on the manoeuvring area except idle power run on the stands;

e) TWR shall ensure that "Follow Me" services are provided to pilots on request;

f) The number of the vehicles on the manoeuvring area shall be restricted to bare minimum and records of all vehicles operating on the manoeuvring area shall be maintained and all vehicles operating on the manoeuvring area shall be in two-way contact with Aerodrome Control Tower.

g) The following may be included in ATIS. "LOW VISIBILITY PROCEDURES IN FORCE".

h) TWR shall permit departures only from the beginning of the Runway in use.

i) Whenever visibility/RVR is less than 800M/550M, Duty officer tower shall confirm from pilot that the reported RVR value is within minima before issuing take-off clearance.

j) Duty Officer Tower shall stop all flight operations whenever RVR falls below 400 M.

k) Runway inspection should be done when interval between two aircraft movements is 30 minutes or more.

l) Inform changes in RVR readings to the departing aircraft as required.

m) Inform pilots of all failures of ILS, lighting system etc. relevant to ILS CAT I Low Visibility Operations.

n) Initiate emergency action if aircraft on CAT I ILS is not in radio contact, as expected.

o) Duty officer tower shall take the Take – off Alternate from pilot before issuing take-off clearance.

10.2 **Actions by CNS In-charge/ Duty Officer, NAV AIDS:**

a) On receipt of "Initiating SP" from ATC, CNS In-charge will inform the Duty Officer, NAV AIDS and have the ILS equipment and its status indicators in ATC units checked up. He will inform ATC of any unserviceability in the equipment which is likely to affect ILS CAT I operation.

b) On receipt of "Initiating LVP" from ATC that LVP are to be made effective CNS In charge will maintain continuous watch on the performance of ILS equipment and will inform ATC of any un-serviceability which may affect ILS CAT I operation.

10.3 **Actions by Duty Manager, Airside operations (To be done by Duty officer ATC TWR):**

Duty officer shall ensure that:

a) No vehicle/person enters or is present in the sensitive/critical areas of localizer and glide path.

b) All civil/electrical works in progress are to be stopped in the manoeuvring area immediately and men/material/ equipment to be removed from the sensitive/critical areas of localizer and glide path.

c) Temporary barricades on Road Holding position shall be placed by Operation Dept.

NOTE:

After ensuring above, Follow-me vehicles/operational vehicles will confirm the same to the ATC. Subsequently, follow-me vehicle/ operational vehicles shall remain available and will maintain listening watch on Walkie-Talkie.

Any information about unserviceability of any of the Runway visual aids or power supply system will immediately inform ATC Tower accordingly.

No vehicles shall enter/cross in the vicinity of Runway without permission from ATC Control Tower. Such vehicles shall be able to communicate with ATC.

The vehicles of the ARFF services, civil, electrical division or of any other agency which are not equipped with RT but has to enter the Runway or taxiway for urgent operational requirement shall be escorted by the follow me jeep all the time.

d) On receipt of advice from ATC to implement Safeguarding procedure, the Terminal Duty Manager, will immediately inform to all airlines.

10.4 **Action by Shift Manager (Civil):**

a) Shift Manager (Civil) to ensure that all civil works in progress in manoeuvring area, are stopped and that the work area is restored in complete serviceable condition and confirm to WSO accordingly.

b) Shift Manager, Civil shall ensure closure of roads leading to critical/sensitive area by chains.

c) During CAT I operations, ATC may authorize operations of vehicles Specially trained about critical and sensitive area, on manoeuvring area, including the crossing of taxiways.

d) Ensure that Runways, Taxiways and other associated facilities such as Markings, Lights are inspected every 2 hours while LVP is in progress.

10.5 Action by Shift Manager (Electrical):

a) On receipt of advice to implement Low Visibility Procedures from ATC, Shift Manager (Electrical) will check that following visual aids are serviceable and can be operated at full intensity:

i) Approach lighting system

ii) Runway edge lights

iii) Runway threshold and end lights

NOTE: No adjustment in light intensity shall be made without permission from ATC Tower during LVP.

b) They shall ensure that no electrical maintenance works is carried out during LVP either in powerhouse or on any other electrical facilities used during CAT I operations.

c) They will inform the un-serviceability or any change in status of any facility/systems to ATC & Airside Ops Manager immediately.

10.6 **Actions by ARFF:**

a) Positioning of crash fire tenders on pre-determined positions.

b) ARFF/ CFTs must obtain clearances from ATC prior to entry to any aircraft movement area other than the designated service roads.

10.7 **Actions by CISF:**

a) The officer in charge on duty shall ensure by deploying adequate manpower that vital electrical installations are properly secured and protected against any unauthorized intrusion.

b) The Officer in charge, on receipt of advice to implement Low Visibility Procedures, will immediately inform all access gates and CISF posts under their respective controls in operational area to restrict movement of vehicles under their control.

10.8 **Actions by Duty Officer (Meteorological Office):**

a) Duty Meteorological Officer would issue an 'Outlook for Low Visibility Procedures' to the ATC whenever he expects that the RVR and/or cloud ceiling will fall below 800 m and/or 400ft or less respectively.

b) Whenever Duty Meteorological Officer visualizes that RVR is likely to fall below 800 m and/or cloud ceiling to 200ft or less within next 2 hours, he will issue an 'Advisory Message' to ATC to this effect.

c) When the RVR and/or cloud ceiling are 800m and/or 200ft respectively and the trend is towards improvement in these elements of weather conditions the Duty Met Officer may, when requested by ATC, advise him about such improving weather conditions for the purpose of termination of LVP.

d) The Duty Met Officer shall be present in Control Tower during periods of reduced visibility and ensure that the RVR displays in the Control Tower is serviceable.

e) In case, Instrumented RVR is not available, real time RVR shall be provided, whenever requested.

11. TERMINATION OF LOW VISIBILITY TAKE OFF PROCEDURES

11.1 When Visibility/RVR improves to 800M/550 M or more and cloud ceiling is 200 feet or higher and trend is for improvement, WSO/Duty Officer Tower would terminate operations of LVP. He may obtain advice from Duty Met. Officer regarding improvement in weather conditions before the termination of LVP.

a) The WSO/Duty Officer Tower will intimate the following regarding termination of operations:

i) ARFF

ii) Terminal Manager/Operations, who will advise all the previously notified personnel to resume normal operations.

iii) CNS, Civil, Electrical In-charge

iv) M.T Pool

v) Duty Met Officer

vi) CISF

11.2 On cancelling of LVP, following message shall be included in two subsequent ATIS broadcasts. “LOW VISIBILITY PROCEDURES CANCELLED”.

11.3 If SP are implemented and LVP are not subsequently implemented and the visibility/RVR improves and is more than 1200 m and/or the cloud ceiling is 400ft or higher and both are forecast to remain above the required SP criteria, WSO/ Duty Officer Tower may cancel SP.

12. ACTIONS BY OTHER AGENCIES (AIRLINES, REFUELLING COMPANIES, CATERING AGENCIES, ETC.)

12.1 Every year before commencement of monsoon/winter season, a meeting will be held by Airport Director, to inform all airlines and agencies operating at airport about their roles/responsibilities and create awareness to ensure cooperation for safe airport operations during periods of low visibility.

12.2 All the agencies shall ensure that staff and drivers are suitably trained during Low Visibility operations.

12.3 A refresher program for ATCO’s and personnel responsible for airside operations should be conducted every year.

12.4 All agencies operating in the operational area shall ensure that only those vehicles that are absolutely essential for aircraft operations operate in the operational area during periods of low visibility. The drivers of these vehicles should keep a look out for taxiing aircraft and other vehicles to prevent accidents.

12.5 All the vehicles must have their obstruction lights “ON” during Low Visibility Procedures operations.

12.6 All instructions/sign boards provided for vehicular movement area/service roads must be followed while operating in the operational area.

VEAT AD 2.21 NOISE ABATEMENT PROCEDURES

VEAT AD 2.22 FLIGHT PROCEDURES

ADS-B ground station at Agartala in OPR. ADS-B based ATS Surveillance services are provided to suitably equipped aircraft on opportunity basis within the coverage area of Agartala ADS-B sensors in the jurisdiction of Agartala Approach Control daily BTN 0530-0830 and 0930-1230. ADS-B equipped aircraft flying within the jurisdiction of Agartala Aproach Control to comply wth relevant provisions.

VEAT AD 2.23 ADDITIONAL INFORMATION

i. Wind Direction Indicator for RWY 18/36 is lighted.

ii. Obstruction relating RWY 18 due ILS installed. Locator Hut height 5.9 ft above RWY end level indication 670 ft south of the beginning of RWY 36.

iii. GP hut height 17 ft above RWY level. Location 1306 ft from the beginning of RWY 18 and 400 ft from the Centre line of RWY. Obstruction are marked. GP antenna height 39 ft offset distance from RWY centreline 366 ft distance from RWY 18 end threshold 789 ft erected. Obstruction light provided.

iv. New Installation TV Tower is provided with OBST LGT. Location A/D (Arundhati) Nagar 234800N 0911612E. Arial distance from Airport 13KM. GND/134.75M.

v. Three mast lights of height 16.5M have been installed east of the apron for stand no.3, 4 and 5.

vi. ADS-B ground station at Agartala in operation. ADS-B based ATS surveillance services are provided to suitably equipped aircraft on opportunity basis within the coverage area of Agartala ADS-B sensors in the jurisdiction of Agartala Approach Control daily between 0530-0830 and 0930-1230. ADS-B equipped aircraft flying within the jurisdiction of Agartala Approach Control to comply with relevant provisions.

vii. **Exemption Granted by DGCA:**
DGCA India has granted exemption vide letter dated 30.08.2022 for non-compliant width of runway strip against provisions in CAR Section-4 Series-B Part-1 Para 3.4.3 for the period up to 31.12.2023.

viii. Following intersection Take Off Run Available (TORA):

RWY	Intermediate Turn Pad	TORA (M)
RWY 36	Intermediate Turn Pad	1800

VEAT AD 2.24 CHARTS RELATED TO AN AERODROME

1 Aerodrome Chart (13 June 2024)
2 Aircraft Parking / Docking Chart (13 June 2024)
3 Aerodrome Obstacle Chart Type-A (Operating Limitations) RWY 18 (13 June 2024)
4 Aerodrome Obstacle Chart Type-A (Operating Limitations) RWY 36 (13 June 2024)
5 Instrument Approach Chart – ILS or LOC Z RWY 18 CAT A/B/C (16 May 2024)
6 Instrument Approach Chart – ILS (Y) Procedure RWY 18
7 ATC Surveillance Minimum Altitude Chart (16 May 2024)
8 Instrument Approach Chart – VOR Procedure RWY 18 (17 April 2025)
9 Instrument Approach Chart – VOR Procedure RWY 36 (17 April 2025)

VEAT AD 2.25 VISUAL SEGMENT SURFACE (VSS) PENETRATION

Procedure	Procedure Minima	VSS Penetration
1	**2**	**3**