AD 2. AERODROMES

VEBI AD 2.1 AERODROME LOCATION INDICATOR AND NAME

VEBI - BARAPANI AIRPORT, BARAPANI

VEBI AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome reference point coordinates and its site	254212N 0915841E MAG. BRG. 42.40 DEG / 850 M from physical beginning of RWY 04.	
2	Direction and distance of aerodrome reference point from the centre of the city or town which the aerodrome serves	45 DEG/34Km from Shillong	
3	Aerodrome elevation and reference temperature	2926 FT / 24.0 DEG C	
4	Magnetic variation, date of information and annual change	0.42 DEG W (2010) /0.00	
5	Name of aerodrome operator, address, telephone, telefax, e-mail address, AFS address, website (if available)	Airport Director, Airports Authority of India, Shillong Airport, Umroi, Shillong - 793116	
		Telephone:	(91) 3642307470
		Fax:	(91) 3642307471
		AFS:	VEBIYDYX
		Email:	apdshillong@aai.aero
6	Types of traffic permitted (IFR/VFR)	IFR/VFR	
7	Remarks	**Elevation in EGM08**	

VEBI AD 2.3 OPERATIONAL HOURS

1.	Aerodrome Operator	MON-FRI 0400-1230 UTC (0930-1800 IST) SAT, SUN+HOL: NIL	
2.	Custom and immigration	NIL	
3.	Health and sanitation	AVBL (M I Room)	
4.	AIS briefing office	As ATS	
5.	ATS reporting office (ARO)	As ATS	
6.	MET Briefing office	AVBL in AD Hrs	
7.	Air Traffic Service	Consult current NOTAM for ATS HRs	
8.	Fuelling	AVBL	
9.	Handling	AVBL	
10.	Security	H24	
11.	De-icing	NIL	
12.	Remarks	Outside of ATS HR service available O/R with H24 PN to AD.	
		ATS approved hourly runway traffic handling capacity	Maximum number of arrival and departure- 12 Maximum number of arrival only – 06 Maximum number of departure only -10

VEBI AD 2.4 HANDLING SERVICES AND FACILITIES

1.	Cargo-handling facilities	Available with local airline operator
2.	Fuel/Oil types	Not AVBL
3.	Fuelling facilities/capacity	REFUELLING FACILITY BY BPCL, IOCL AVAILABLE.
4.	De-icing facilities	NIL
5.	Hangar space for visiting aircraft	NIL
6.	Repair facilities for visiting aircraft	NIL
7.	Remarks	NIL

VEBI AD 2.5 PASSENGER FACILITIES

1.	Hotel(s) at or in the vicinity of aerodromes	In the city
2.	Restaurant(s) at or in the vicinity of aerodromes	In the city
3.	Transportation possibilities	Private Taxis available
4.	Medical Facilities	First aid at AD. CHC Bhoirymbong.
5.	Bank and post office at or in the vicinity of aerodromes	Banks: Umroi (2.3 Kms) Post office: Bhoirymbong
6.	Tourist office	State Tourism counter available at Airport
7.	Remarks	NIL

VEBI AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1.	Aerodrome category for fire fighting	Within ATS HR: CAT-5 CAT-6 During operation of Q-400
2.	Rescue equipment	Available as per category
3.	Capability for removal of disabled aircraft	1. The critical aircraft for the airport is ATR-72 2. Primary responsibility for removal of disabled aircraft rests with the concerned airline. 3. The airlines may contact 'Aerodrome Coordinator for Disabled Aircraft Removal Operations' for coordinating with the agencies having Disabled Aircraft Recovery Kit. 4. Contact Details of Aerodrome Coordinator for Disabled Aircraft Removal Operations: Airport Director Office: 0364-2307470 Mobile: 9436332580 E-mail: apdshillong@aai.aero
4.	Remarks	NIL

VEBI AD 2.7 SEASONAL AVAILABILITY CLEARING

1.	Types of clearing equipment	NIL
2.	Clearance priorities	NIL
3.	Remarks	NIL

VEBI AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS DATA

1	Designation, surface and strength of aprons	Refer Aircraft Parking/Docking Chart
2	Designation, width, surface and strength of taxiways	Refer Aircraft Parking/Docking Chart
3	Location and elevation of altimeter checkpoints	Location: Nose wheel point no.1 Elevation: 890.016M/2920FT

4	Location of VOR checkpoints	On TWYA: 254213.96N 0915836.66E Elevation(FT): 2914
5	Position of INS checkpoints	
6	Remarks	**1. Coordinates of RWY Holding Position** **TWY** **Coordinates** **Elevation(FT)** TWY A 254213.86N 0915836.80E 2914 TWY B 254217.52N 0915840.08E 2915 TWY F 254235.27N 0915904.27E 2898 **2. Coordinates of RWY & Taxi Intersection** **TWY** **Coordinates** **Elevation(FT)** TWY A 254212.10N 0915839.37E 2913 TWY B 254215.68N 0915842.58E 2913 TWY F 254237.11N 0915901.76E 2902 **3. Elevations in EGM08**

VEBI AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1.	Use of aircraft stand Identification signs, TWY guide lines and visual docking/parking guidance system of aircraft stands	Taxing guidance provided on r/t. Guidelines at Apron.
2.	RWY and TWY markings and LGT	RWY Markings Designation THR, TDZ, Centerline and Side strip, Displaced THR and Aiming point RWY Lights: Edge, THR, End LGT, Wingbar, Approach TWY Marking: Centerline, Holding Position, Side strip TWY Lights: Edge
3.	Stop bars	NIL
4.	Remarks	NIL

VEBI AD 2.10 AERODROME OBSTACLES

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
22/TKOF 04/APCH	TREE	254151.5N 0915816.9E	2962 FT	NO	Bushes (Ground Elev 900.2 M)
22/TKOF 04/APCH	TREE	254144.8N 0915812.2E	2970 FT	NO	Bushes (Ground Elev 899.6 M)
22/TKOF 04/APCH	NATURAL HIGHPOINT	254141.7N 0915809.0E	2958 FT	NO	Spot Level
22/TKOF 04/APCH	OTHER	254144.2N 0915805.4E	3003 FT	NO	Mobile Road Traffic (Road Elev. 910.4 M+5m Mobile Traffic Height)
22/TKOF 04/APCH	POLE	254143.0N 0915806.8E	2999 FT	NO	Electric Pole

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
22/TKOF 04/APCH	FENCE	254143.7N 0915804.8E	2996 FT	NO	Airport Boundary Wall with Fencing on Top
22/TKOF 04/APCH	OTHER	254142.9N 0915803.8E	3000 FT	NO	Mobile Road Traffic (Road Elev. 909.3 M+5m Mobile Traffic Height)
22/TKOF 04/APCH	POLE	254143.6N 0915804.7E	3009 FT	NO	Electric Pole
22/TKOF 04/APCH	NATURAL HIGHPOINT	254142.2N 0915806.1E	2984 FT	NO	Spot Level
22/TKOF 04/APCH	FENCE	254142.0N 0915803.4E	2996 FT	NO	Airport Boundary Wall with Fencing on Top (Wall Top 912.4 M)
22/TKOF 04/APCH	OTHER	254139.4N 0915806.3E	2969 FT	NO	L/C Rod on Localizer Hut (Hut Top 902.4 M)
22/TKOF 04/APCH	POLE	254140.2N 0915803.3E	3002 FT	NO	Electric Pole
22/TKOF 04/APCH	TREE	254134.8N 0915809.8E	2976 FT	NO	Group of Trees (Bamboo)
22/TKOF 04/APCH	FENCE	254140.2N 0915801.8E	2994 FT	NO	Airport Boundary Wall with Fencing on Top
22/TKOF 04/APCH	OTHER	254140.1N 0915801.7E	3002 FT	NO	Mobile Road Traffic (Road Elev. 910.0 M+5m Mobile Traffic Height)
22/TKOF 04/APCH	TREE	254139.0N 0915802.2E	3013 FT	NO	Group of Trees
22/TKOF 04/APCH	NATURAL HIGHPOINT	254138.4N 0915802.3E	2986 FT	NO	Spot Level
22/TKOF 04/APCH	OTHER	254137.2N 0915803.1E	2998 FT	NO	Mobile Road Traffic (Road Elev. 908.9 M+5m Mobile Traffic Height)
22/TKOF 04/APCH	TREE	254137.1N 0915802.9E	3005 FT	NO	Bushes (Ground Elev. 912.9 M)
22/TKOF 04/APCH	NATURAL HIGHPOINT	254136.7N 0915803.2E	2974 FT	NO	Spot Level
22/TKOF 04/APCH	NATURAL HIGHPOINT	254136.9N 0915802.3E	2981 FT	NO	Spot Level
22/TKOF 04/APCH	TREE	254136.8N 0915801.6E	3014 FT	NO	Group of Trees
22/TKOF 04/APCH	NATURAL HIGHPOINT	254136.1N 0915801.4E	2973 FT	NO	Spot Level
22/TKOF 04/APCH	OTHER	254136.5N 0915800.0E	2990 FT	NO	Mobile Road Traffic (Road Elev. 906.5 M+5m Mobile Traffic Height)

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
22/TKOF 04/APCH	TREE	254137.3N 0915758.6E	3010 FT	NO	Group of Trees
22/TKOF 04/APCH	BUILDING	254136.4N 0915759.5E	2985 FT	NO	House
22/TKOF 04/APCH	TREE	254133.3N 0915803.6E	2996 FT	NO	Group of Trees
22/TKOF 04/APCH	TREE	254100.4N 0915751.4E	3164 FT	NO	Tree on Hill (Hill Top 946.4 M)
22/TKOF 04/APCH	TREE	254100.4N 0915750.4E	3159 FT	NO	Group of Trees
22/TKOF 04/APCH	NATURAL HIGHPOINT	254059.9N 0915750.5E	3155 FT	NO	Spot Level
22/TKOF 04/APCH	TREE	254053.7N 0915747.2E	3171 FT	NO	Group of Trees
22/TKOF 04/APCH	TREE	254057.3N 0915736.3E	3084 FT	NO	Tree on Hill
22/TKOF 04/APCH	TREE	254047.3N 0915738.2E	3147 FT	NO	Tree on Hill (Hill Top 945.1 M)
22/TKOF 04/APCH	ANTENNA	254047.2N 0915738.2E	3140 FT	NO	Antenna
22/TKOF 04/APCH	ANTENNA	254048.0N 0915736.9E	3131 FT	NO	Antenna
22/TKOF 04/APCH	TREE	254049.3N 0915732.7E	3092 FT	NO	Tree on Hill
22/TKOF 04/APCH	ANTENNA	254048.4N 0915730.7E	3084 FT	NO	Antenna
22/TKOF 04/APCH	TREE	254040.5N 0915734.6E	3166 FT	NO	Group of Trees
22/TKOF 04/APCH	TREE	254041.0N 0915732.5E	3150 FT	NO	Tree on Hill (Hill Top 955.0 M)
22/TKOF 04/APCH	BUILDING	254045.1N 0915726.3E	3104 FT	NO	Church
22/TKOF 04/APCH	TREE	254045.2N 0915725.2E	3134 FT	NO	Group of Trees
22/TKOF 04/APCH	TREE	254040.4N 0915725.4E	3125 FT	NO	Group of Trees
22/TKOF 04/APCH	NATURAL HIGHPOINT	253613.8N 0915245.7E	4744 FT	NO	Hill
22/TKOF 04/APCH	NATURAL HIGHPOINT	253608.5N 0915433.2E	5252 FT	NO	Hill
22/TKOF 04/APCH	NATURAL HIGHPOINT	253928.5N 0915640.6E	3513 FT	NO	Hill Top
22/TKOF 04/APCH	NATURAL HIGHPOINT	253719.3N 0915336.9E	4432 FT	NO	Hill Top
22/TKOF 04/APCH	TREE	253815.7N 0915541.1E	4440 FT	NO	Tree on Hill (Hill Top 1337.3 M)
22/TKOF 04/APCH	TREE	253812.1N 0915556.1E	4513 FT	NO	Tree on Hill (Hill Top 1358.6 M)
22/TKOF 04/APCH	TREE	253825.9N 0915510.5E	4264 FT	NO	Tree on Hill (Hill Top 1283.3 M)
22/TKOF 04/APCH	TANK	253824.2N 0915509.4E	4229 FT	NO	Water Tank on Hill (Hill Top 1284.9m)

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
22/TKOF 04/APCH	BUILDING	253832.7N 0915507.7E	4193 FT	NO	Building on Hill
22/TKOF 04/APCH	BUILDING	253826.0N 0915456.2E	4229 FT	NO	Building on Hill
22/TKOF 04/APCH	TREE	253823.9N 0915457.0E	4223 FT	NO	Tree on Hill
22/TKOF 04/APCH	BUILDING	253810.2N 0915512.0E	4243 FT	NO	Building on Hill
22/TKOF 04/APCH	TREE	253836.3N 0915549.9E	3863 FT	NO	Tree on Hill
22/TKOF 04/APCH	TREE	253822.7N 0915559.8E	4067 FT	NO	Tree on Hill
22/TKOF 04/APCH	TREE	253925.1N 0915627.5E	3547 FT	NO	Tree on Hill
22/TKOF 04/APCH	TREE	253816.7N 0915521.6E	4209 FT	NO	Tree on Hill
22/TKOF 04/APCH	OTHER	254148.3N 0915818.1E	2931 FT	LGTD	Approach Light
22/TKOF 04/APCH	POLE	254045.9N 0915727.8E	3079 FT	NIL	Electric Pole
22/TKOF 04/APCH	POLE	254042.9N 0915727.5E	3084 FT	NIL	Electric Pole
22/TKOF 04/APCH	TREE	254144.8N 0915807.9E	3017 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254237.7N 0915905.9E	2919 FT	NIL	Bushes (Ground Elev. 884.8 M)
22/APCH 04/TKOF	TREE	254243.3N 0915902.7E	2916 FT	NIL	Bushes
22/APCH 04/TKOF	TREE	254241.8N 0915912.6E	2985 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254243.2N 0915913.8E	2972 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254246.4N 0915919.4E	2964 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254247.6N 0915920.5E	2955 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254256.8N 0915919.2E	2958 FT	NIL	Group of Trees (Bamboo)
22/APCH 04/TKOF	TREE	254327.1N 0915940.4E	3032 FT	NIL	Group of Trees on Hill
22/APCH 04/TKOF	TREE	254333.1N 0915938.3E	3027 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254334.4N 0915938.7E	3034 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254335.4N 0915938.9E	3035 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254333.9N 0915954.6E	3056 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254333.4N 0915955.6E	3070 FT	NIL	Group of Trees
22/APCH 04/TKOF	TREE	254332.8N 0915957.4E	3089 FT	NIL	Group of Trees

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
22/APCH 04/TKOF	NATURAL HIGHPOINT	254542.9N 0920057.4E	3394 FT	NIL	Ground Level
22/APCH 04/TKOF	TREE	254538.6N 0920111.7E	3436 FT	NIL	Group of Trees on Hill
22/APCH 04/TKOF	TREE	254558.9N 0920127.1E	3603 FT	NIL	Group of Trees on Hill
22/APCH 04/TKOF	TREE	254607.4N 0920125.4E	3667 FT	NIL	Group of Trees on Hill
22/APCH 04/TKOF	TREE	254613.9N 0920124.9E	3858 FT	NIL	Group of Trees on Hill GL 1153.5
22/APCH 04/TKOF	BUILDING	254610.8N 0920131.6E	3675 FT	NIL	House on Hill
22/APCH 04/TKOF	TREE	254634.4N 0920130.9E	3919 FT	NIL	Group of Trees on Hill GL 1178.9
In circling area and at AD	NATURAL HIGHPOINT	254159.3N 0915834.3E	2923 FT	NIL	Spot Level
In circling area and at AD	TREE	254157.0N 0915835.2E	2964 FT	NIL	Group of Trees (Bamboo)
In circling area and at AD	NATURAL HIGHPOINT	254156.7N 0915832.1E	2924 FT	NIL	Spot Level
In circling area and at AD	TREE	254202.3N 0915823.5E	2957 FT	NIL	Bushes (Ground Elev.898.6 M)
In circling area and at AD	POLE	254202.3N 0915820.8E	2989 FT	NIL	Electric Pole
In circling area and at AD	TREE	254201.0N 0915822.4E	2965 FT	NIL	Bushes (Ground Elev.902.1 M)
In circling area and at AD	BUILDING	254201.6N 0915820.9E	2984 FT	NIL	Security Hut
In circling area and at AD	FENCE	254201.5N 0915820.6E	2977 FT	NIL	Airport Boundary Wall with Fencing on Top (Wall Top = 906.8 M)
In circling area and at AD	BUILDING	254201.6N 0915820.4E	2982 FT	NIL	Shed
In circling area and at AD	TREE	254201.0N 0915820.0E	3003 FT	NIL	Group of Trees
In circling area and at AD	TREE	254158.7N 0915820.2E	2974 FT	NIL	Bushes (Ground Elev.902.9 M)
In circling area and at AD	TREE	254200.7N 0915816.7E	3019 FT	NIL	Group of Trees
In circling area and at AD	BUILDING	254159.2N 0915816.8E	2987 FT	NIL	Building
In circling area and at AD	TREE	254158.5N 0915817.5E	2996 FT	NIL	Group of Trees
In circling area and at AD	FENCE	254158.0N 0915817.5E	2978 FT	NIL	Airport Boundary Wall with Fencing on Top

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	TREE	254156.1N 0915817.4E	2966 FT	NIL	Bushes (Ground Elev.898.2 M)
In circling area and at AD	TREE	254154.6N 0915817.0E	2961 FT	NIL	Bushes (Ground Elev.898.1 M)
In circling area and at AD	TREE	254145.8N 0915827.4E	2984 FT	NIL	Group of Trees (Bamboo)
In circling area and at AD	TREE	254153.8N 0915816.0E	2986 FT	NIL	Bushes (Ground Elev.899.8 M)
In circling area and at AD	TREE	254154.5N 0915813.5E	3026 FT	NIL	Group of Trees (Bamboo)
In circling area and at AD	NATURAL HIGHPOINT	254152.8N 0915815.5E	2956 FT	NIL	Spot Level
In circling area and at AD	BUILDING	254153.0N 0915812.5E	2986 FT	NIL	Shed
In circling area and at AD	TREE	254153.1N 0915811.7E	3031 FT	NIL	Group of Trees
In circling area and at AD	TREE	254142.5N 0915823.7E	2971 FT	NIL	Group of Trees
In circling area and at AD	BUILDING	254152.2N 0915809.4E	3006 FT	NIL	Building
In circling area and at AD	TREE	254136.7N 0915818.8E	2988 FT	NIL	Bamboo Tree (Ground Elev.897.8 M)
In circling area and at AD	TREE	254142.6N 0915803.1E	3038 FT	NIL	Group of Trees
In circling area and at AD	BUILDING	254142.8N 0915802.4E	3008 FT	NIL	Building
In circling area and at AD	TREE	254106.0N 0915758.4E	3085 FT	NIL	Tree on Hill (Hill Top 928.8 M)
In circling area and at AD	TREE	254103.2N 0915755.9E	3091 FT	NIL	Tree on Hill
In circling area and at AD	TREE	254148.5N 0915805.3E	3016 FT	NIL	Group of Trees
In circling area and at AD	OTHER	254149.9N 0915819.5E	2929 FT	LGTD	Approach Light
In circling area and at AD	TREE	254147.4N 0915804.1E	3012 FT	NIL	Group of Trees
In circling area and at AD	TREE	254146.3N 0915802.7E	3031 FT	NIL	Group of Trees
In circling area and at AD	TREE	254143.7N 0915802.1E	3040 FT	NIL	Group of Trees
In circling area and at AD	TREE	254105.3N 0915803.1E	3138 FT	NIL	Tree Top on Hillock
In circling area and at AD	NATURAL HIGHPOINT	253904.9N 0915439.8E	4166 FT	NIL	Hill
In circling area and at AD	OTHER	253624.5N 0915456.2E	5498 FT	NIL	Mast on Hill (Hill Top 1642.8 M)
In circling area and at AD	OTHER	253634.8N 0915510.9E	5613 FT	NIL	Mast P & T Deptt.
In circling area and at AD	NATURAL HIGHPOINT	253802.8N 0915602.9E	4563 FT	NIL	Hill Top

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	NATURAL HIGHPOINT	253800.9N 0915241.2E	4120 FT	NIL	Hill Top
In circling area and at AD	TREE	254230.6N 0915845.5E	2970 FT	NIL	Group of Trees
In circling area and at AD	TREE	254222.6N 0915858.8E	2957 FT	NIL	Group of Trees
In circling area and at AD	BUILDING	254232.0N 0915851.6E	2916 FT	NIL	GP Hut
In circling area and at AD	NAVAID	254232.3N 0915851.9E	2959 FT	NIL	GP Main Antenna
In circling area and at AD	NAVAID	254232.4N 0915851.8E	2921 FT	NIL	GP DME Antenna
In circling area and at AD	TREE	254238.5N 0915846.6E	3058 FT	NIL	Tree on Hill
In circling area and at AD	NAVAID	254234.4N 0915853.7E	2928 FT	NIL	GP Monitor Antenna
In circling area and at AD	TREE	254240.8N 0915846.6E	3076 FT	NIL	Bamboo Tree on Hill
In circling area and at AD	TREE	254237.4N 0915852.5E	2951 FT	NIL	Group of Trees
In circling area and at AD	TREE	254241.7N 0915848.6E	3063 FT	NIL	Group of Trees
In circling area and at AD	OTHER	254238.9N 0915903.4E	2902 FT	LGTD	App Light
In circling area and at AD	TREE	254244.9N 0915856.7E	2966 FT	NIL	Group of Trees
In circling area and at AD	BUILDING	254248.6N 0915852.7E	3035 FT	NIL	Sintex on Building (Bldg. Top 923.8 M)
In circling area and at AD	TREE	254249.0N 0915853.5E	3050 FT	NIL	Group of Trees
In circling area and at AD	TREE	254248.5N 0915900.9E	2954 FT	NIL	Group of Trees (Bamboo)
In circling area and at AD	TREE	254253.1N 0915855.9E	3046 FT	NIL	Group of Trees
In circling area and at AD	TREE	254252.1N 0915859.6E	3002 FT	NIL	Group of Trees
In circling area and at AD	TREE	254242.3N 0915916.1E	2943 FT	NIL	Group of Trees
In circling area and at AD	TREE	254241.6N 0915918.1E	2975 FT	NIL	Group of Trees
In circling area and at AD	TREE	254252.5N 0915903.9E	2959 FT	NIL	Group of Trees
In circling area and at AD	TREE	254311.2N 0915917.4E	2993 FT	NIL	Group of Trees
In circling area and at AD	TREE	254240.5N 0915849.1E	3029 FT	NIL	Group of Trees on Hill
In circling area and at AD	OTHER	254227.3N 0915858.7E	2927 FT	NIL	LC Rod On MET Antenna
In circling area and at AD	TREE	254227.9N 0915901.6E	2968 FT	NIL	Group of Trees
In circling area and at AD	OTHER	254342.5N 0915931.7E	3133 FT	NIL	Mast

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	TREE	254613.5N 0920109.7E	3926 FT	NIL	Group of Trees on Hill Ground Level 1187.3M
In circling area and at AD	OTHER	254722.9N 0920151.1E	4196 FT	NIL	Cellphone Mast on Hill
In circling area and at AD	NAVAID	254223.4N 0915840.6E	2946 FT	NIL	New DVOR Monitor Antenna
In circling area and at AD	OTHER	254217.7N 0915830.5E	3001 FT	NIL	L/C Rod On ATC
In circling area and at AD	OTHER	254217.7N 0915830.7E	2993 FT	NIL	Antenna On ATC (ATC Bldg. Top 909.3M)
In circling area and at AD	OTHER	254210.1N 0915841.8E	2937 FT	NIL	WDI
In circling area and at AD	TREE	254202.2N 0915842.4E	2985 FT	NIL	Group of Trees on Hill Ground Level 1187.3M
In circling area and at AD	OTHER	254226.2N 0915843.0E	2951 FT	NIL	L/C Rod on New DVOR
In circling area and at AD	TREE	254207.5N 0915846.7E	3017 FT	NIL	Group of Trees
In circling area and at AD	TREE	254210.5N 0915847.4E	2976 FT	NIL	Group of Trees
In circling area and at AD	ANTENNA	254204.0N 0915837.5E	2943 FT	LGTD	MET Antenna Light Top
In circling area and at AD	TREE	254444.1N 0915848.4E	3989 FT	NIL	Tree on Hill
In circling area and at AD	TREE	254336.1N 0915750.0E	4140 FT	NIL	Tree on Hill
In circling area and at AD	TREE	254233.0N 0915523.4E	4465 FT	NIL	Tree on Hill
In circling area and at AD	NATURAL HIGHPOINT	253451.4N 0915715.3E	5239 FT	NIL	Hill
In circling area and at AD	NATURAL HIGHPOINT	253752.6N 0915743.9E	4448 FT	NIL	Hill
In circling area and at AD	NATURAL HIGHPOINT	254009.1N 0915856.5E	3766 FT	NIL	Hill
In circling area and at AD	NATURAL HIGHPOINT	253734.0N 0920020.0E	3943 FT	NIL	Hill
In circling area and at AD	NATURAL HIGHPOINT	254034.4N 0920012.1E	3415 FT	NIL	Hill
In circling area and at AD	NATURAL HIGHPOINT	254244.9N 0920027.1E	3113 FT	NIL	Hill
In circling area and at AD	TREE	254356.9N 0920136.5E	3572 FT	NIL	Tree on Hill
In circling area and at AD	TANK	254157.8N 0915614.6E	3487 FT	NIL	Over Head Water Tank
In circling area and at AD	TREE	254329.4N 0920112.6E	3418 FT	NIL	Tree on Hill
In circling area and at AD	TREE	254223.5N 0915943.8E	3179 FT	NIL	Tree on Hill

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM-08)	Marking/LGT	Remarks
In circling area and at AD	TREE	254137.4N 0915921.1E	3284 FT	NIL	Tree on Hill
In circling area and at AD	NATURAL HIGHPOINT	254915.4N 0915856.8E	3467 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254647.9N 0915657.5E	3448 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254833.2N 0920233.7E	3924 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254723.0N 0920144.3E	4052 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254543.5N 0920358.6E	3527 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254406.1N 0915707.8E	3776 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254253.8N 0915654.7E	3776 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254127.8N 0915706.4E	3225 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254055.1N 0915230.2E	3776 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254038.4N 0915926.4E	3448 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254033.2N 0915825.4E	3218 FT	NIL	Hut on Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254015.1N 0915128.5E	3917 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254222.6N 0920355.9E	3563 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254220.1N 0920516.7E	3612 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	253957.6N 0920022.6E	3320 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	253546.3N 0920138.7E	3989 FT	NIL	Hill Top
In circling area and at AD	NATURAL HIGHPOINT	254610.3N 0920605.0E	4051 FT	NIL	Hill Top
In circling area and at AD	TREE	254038.8N 0915946.3E	3610 FT	NIL	Tree on Hill
In circling area and at AD	TREE	254057.0N 0915516.9E	3492 FT	NIL	Group of Trees
In circling area and at AD	OTHER	254057.6N 0915518.8E	3570 FT	NIL	Cellphone Mast
In circling area and at AD	OTHER	254231.2N 0915517.8E	4542 FT	NIL	Cellphone Mast on Hill
In circling area and at AD	OTHER	254232.0N 0915525.8E	4530 FT	NIL	Cellphone Mast on Hill
In circling area and at AD	TREE	254322.8N 0915729.5E	4007 FT	NIL	Tree on Hill
In circling area and at AD	TREE	254400.6N 0915811.7E	4043 FT	NIL	Tree on Hill

VEBI AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

1.	Name of the associated meteorological office	GUWAHATI
2.	Hours of service and, where applicable, the designation of the responsible meteorological office outside these hours	0330-1030 UTC 0100-1130 UTC
3.	Office responsible for preparation of TAFs and periods of validity and interval of issuance of the forecasts	Guwahati
4.	Availability of the trend forecast for the aerodrome and interval of issuance	Yes, every 30 min
5.	Information on how briefing and/or consultation is provided	At MET office GUWAHATI
6.	Types of flight documentation supplied and language(s) used in flight documentation	NIL
7.	Charts and other information displayed or available for briefing or consultation	NIL
8.	Supplementary equipment available for providing information on meteorological conditions, e.g. weather radar and receiver for satellite images;	NIL
9.	The air traffic services unit(s) provided with meteorological information	VEBI Tower
10.	Additional information, e.g. concerning any limitation of service.	DCWIS for RWY 04 available.

VEBI AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

Designations	TRUE Bearings	Dimensions of RWY (M)	Strength of pavement (PCN) and associated data) and surface of runway and associated stopways	Geographical coordinates for threshold and runway end
1	2	3	4	5
04	39.03 DEG	1829 x 45 M	23/R/C/W/T Concrete	THR: 254158.93N 0915827.60E RWY END: 254237.40N 0915902.02E
22	219.03 DEG	1829 x 45 M	23/R/C/W/T Concrete	THR: 254237.40N 0915902.02E RWY END: 254151.24N 0915820.72E

THR elevation and highest elevation of TDZ of precision APP RWY	Slope of runway and associated stopway	Dimensions of stopway (M)	Dimensions of clearway (M)	Dimensions of strips (M)
6	7	8	9	10
THR: 2919.0FT TDZ: 2919.0FT	-0.43%			1949 x 280 M
THR: 2901.0FT TDZ: 2913.0FT	0.43%			1949 x 280 M

Dimensions of runway end safety areas	Location and description of arresting system (if any)	Existence of an obstacle-free zone	Remarks.
11	12	13	14
90M x 90M			Slope of RWY 04: -2.30% / -0.4%, Elevation in EGM08
90M x 90M			Slope of RWY 22: 2.30% / 0.4%, Elevation in EGM08

VEBI AD 2.13 DECLARED DISTANCES

RWY Designation	TORA (M)	TODA (M)	ASDA (M)	LDA (M)	Remarks (including runway entry or start point where alternative reduced declared distances have been declared) Remarks
1	2	3	4	5	6
04	1829	1829	1829	1524	
22	1829	1829	1829	1829	

VEBI AD 2.14 APPROACH AND RUNWAY LIGHTING

Runway Designator	Type, length and intensity of approach lighting system	Runway threshold lights, colour and wing bars	Type of visual slope indicator system	Length of runway touchdown zone lights
1	2	3	4	5
04	SALS 420 M LIH	Green	PAPI LEFT/3.00 DEG MEHT (8.53M)	
22	SALS 420 M LIH	Green	PAPI LEFT/3.20 DEG MEHT (16.72M)	

Length, spacing, colour and intensity of runway centre line lights	Length, spacing, colour and intensity of runway edge lights	Colour of runway end lights and wing bars	Length and colour of stopway lights	Remarks
6	7	8	9	10
	1829 M 60 M White LIH	Red Green		NIL
	1829 M 60 M White LIH	Red Green		NIL

VEBI AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Location, characteristics and hours of operation of aerodrome beacon/identification beacon (if any)	ABN	AVBL during watch hours, located on top of ATC TWR.
		IBN	NIL
2	Location and lighting (if any) of anemometer/ landing direction indicator;	LDI	AVBL and Lighted
		Anemometer	NIL
3	Taxiway edge and taxiway centre line lights;	Edge	Taxi Edge, Apron Edge LGT
		Centre Line	NIL
4	Secondary power supply including switch-over time;	Secondary Power supply (02 nos 380 KVA DG sets, 01 no 125 KVA & 01 No 35 KVA DG set) available to all the lighting at AD. Switch over time less than 15 Sec. Also 02 nos. 120 KVA UPS supply available for Runway lighting system. Switchover time less than 1 Sec.	
5	Remarks	RWY Guard lights available at TWY A, B & F.	

VEBI AD 2.16 HELICOPTER LANDING AREA

1.	Geographical coordinates of the geometric center of touchdown and lift off (TLOF) or of each threshold of final approach and take-off (FATO) area	Not established
2.	TLOF and/or FATO area elevation:	Not established
3.	TLOF and FATO area dimensions to the nearest meter or foot, surface type, bearing strength and marking;	Not established
4.	True bearings of FATO;	Not established
5.	Declared distances available	Not established
6.	Approach and FATO lighting;	Not established
7.	Remarks	Not established

VEBI AD 2.17 ATS AIRSPACE

1.	Airspace designation, geographical coordinates and lateral limits	ATZ: Circular area centered on 254212N 0915841E within a 10NM radius.
2.	Vertical limits	9000 FT AMSL
3.	Airspace classification	D
4.	Call sign and language(s) of the air traffic services unit providing service;	Barapani Tower, English
5.	Transition altitude	9000 FT
6.	Hours of applicability	HO
7.	Remarks	Barapani Approach Control Unit is combined with Barapani Aerodrome Control Tower.

VEBI AD 2.18 ATS COMMUNICATION FACILITIES

Service Designation	Call sign	Channel(s)	SATVOICE Number(s), if available
1	2	3	4
APP	Barapani TWR	119.150 MHZ	
APP	Barapani TWR	122.425 MHZ	
TWR	Barapani Tower	119.150 MHZ	
TWR	Barapani Tower	122.425 MHZ	

Logon address, as appropriate	Hours of operation	Remarks
5	6	7
		1.BACKUP FREQ 2. Functions of Approach Control Service provided by Aerodrome Control Tower.
		1. Main 2. Functions of Approach Control Service provided by Aerodrome Control Tower.
	AS ATS	BACKUP FREQ
	As ATS	NIL

VEBI AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of aids, magnetic and type of supported operation for ILS/MLS, basic GNSS, SBAS and GBAS, and for VOR/ILS/MLS station used for technical lineup of the aid	Identification	Frequency(ies), Channel number(s), Service provider, and reference path identifier(s) (RPI), as appropriate	Hours of operation, as appropriate;
1	2	3	4
LOC 22 CAT I	IBRP	108.900 MHz	AS ATS
GP 22		329.300 MHz	AS ATS
DME ILS 22	IBRP	CH26X	AS ATS
DVOR/DME	BPN	116.000 MHz CH107X	AS ATS

Geographical coordinates of the position of the transmitting antenna	Elevation of transmitting antenna of DME/ elevation of GBAS reference point	Service volume radius from the GBAS reference point	Remarks
5	6	7	8
254137.8N 0915808.7E			1. LOC IS USABLE UPTO 10 DEG TOWARDS 90 HZ SIDE (LEFT OF CENTERLINE ON APPROACH) AND UPTO 8 DEG TOWARDS 150 HZ SIDE (RIGHT OF CENTERLINE ON APPROACH) AT 2000FT ABOVE THRESHOLD. COVERAGE IS AVBL UPTO 17NM ONLY.
254232.3N 0915851.9E			1. GP ANGLE 3.2 DEG. 2. GLIDE PATH IS USABLE AT 10NM ABOVE 2500FT OVER THRESHOLD ELEVATION.
254232.4N 0915851.8E	2921 FT		1. COLOCATED WITH GP. 2. Elevation in EGM08.
254226.5N 0915842.6E	2948 FT		1. DME Collocated with DVOR. 2. Radio coverage is restricted at Radial 237.4 degree beyond FL100. Restriction is as per simulation study report.

VEBI AD 2.20 LOCAL AERODROME REGULATIONS

No Aircraft shall take lock turn/ pivotal turn on the Runway to avoid pavement damage.

1. **LOW VISIBILITY PROCEDURES**

2. **SCOPE**

Shillong Airport is certified ILS CAT I aerodrome with a prescribed landing minima of 550 m RVR for RWY 22. The DGCA CAR on All Weather Operations mandates establishment of Low Visibility Procedures for continuing operations below RVR values of 550 m. Accordingly Low Visibility Procedures (Only for Take-off up to (not less than) 400 m RVR) have been established at Shillong Airport to enhance and ensure safety during Low visibility/bad weather conditions.

3. DEFINITIONS

3.1 **ILS Critical Area:** An area of defined dimensions about the localizer and glide path antennas where aircraft and vehicles are excluded during all ILS operations. The critical area is protected because the presence of vehicles / or aircraft inside its boundaries will cause unacceptable disturbance to the ILS signal-in-space.

3.2 **ILS Sensitive Area:** An area extending beyond the ILS critical area where the parking and/or movement of vehicles, including aircraft, are controlled to prevent the possibility of unacceptable interference to the ILS signal during ILS operations. The sensitive area Airports is protected to provide protection against interferences cause by large moving objects outside the critical area but still normally within the airfield boundary.

3.3 **Low Visibility Procedures (LVP)**: Specific procedures applied at an aerodrome for the purpose of ensuring safe operations during Categories II and III approaches and/or low visibility take-offs.

Note: as per para 5.3 of CAR on All Weather Operations, an operator shall not conduct Take-off with RVR/ Visibility less than standard CAT-I conditions of 550m RVR/800m Visibility unless low visibility procedure are enforced.

3.4 **Low Visibility Take-Off (LVTO):** A term used in relation to flight operations referring to a take-off on a runway where the RVR is less than 400m.

3.5 **Manoeuvring Area:** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.

3.6 **Obstacle Free Zone:** The airspace above the inner approach surface, inner transitional surface and balked landing surface and that portion of the strip bounded by these surfaces, which is not penetrated by any fixed obstacle other than of low mass and frangible mounting, required for air navigation purposes.

3.7 **Runway Visual Range:** The range over which the pilot of an aircraft on the centre line of a runway can see the runway surface markings or the lights delineating the runway or identifying its centre line.

3.8 **Safeguarding Procedures:** Safeguarding Procedures (SP) are instructions for relevant airport departments and airside operators to prepare ground services and facilities for low visibility operations, in order that when LVP are implemented all SP are complete and airport is configured for Low Visibility Procedures and Low Visibility Take-offs.

3.9 **Missed approach procedure:** The procedure to be followed if the approach cannot be continued.

3.10 **Aerodrome Operating Minima**: The limits of usability of an aerodrome for:

i) take-off, expressed in terms of runway visual range and / or visibility and, if necessary, cloud conditions;

ii) landing in 2 D instrument approach operations, expressed in terms of visibility and/or runway visual range; minimum descent altitude/height (MDA/H) and, if necessary, cloud conditions.

iii) landing in 3D instrument approach operations, expressed in terms of visibility and/or runway visual range and decision altitude/height (DA/H) appropriate to the type and/or category of the operation.

3.11 **Touchdown Zone:** The portion of a runway, beyond the threshold, where it is intended landing aeroplanes first contact the runway.

3.12 **Visibility**: Visibility for aeronautical purposes is the greater of:
i) the greatest distance at which a black object of suitable dimensions, situated near the ground, can be seen and recognized when observed against a bright background;
ii) The greatest distance at which lights in the vicinity of 1000 candelas can be seen and identified against an unlit background.
Note 1. — The two distances have different values in air of a given extinction coefficient, and the latter b) varies with the background illumination. The former a) is represented by the meteorological optical range (MOR).
Note 2. — The definition applies to the observations of visibility in local routine and special reports, to the observations of prevailing and minimum visibility reported in METAR and SPECI and to the observations of ground visibility.

4. ABBREVIATIONS

ADC: Aerodrome Control
ARFF: Airport Rescue and Fire Fighting Services
ATC: Air Traffic Control
ATM: Air Traffic Management
CFT: Crash Fire Tender
ATIS: Automatic Terminal Information Service
DG: Diesel Generating Set
LVP: Low Visibility Procedures
MET: Meteorology
OPS: Operations
RWY: Runway
RVR: Runway Visual Range
SMC: Surface Movement Control
SP: Safeguarding Procedures
TDZ: Touchdown Zone
TMO: Tower Metrological Officer
TWY: Taxiway

5. **LOW VISIBILITY PROCEDURES:**

5.1 **Regulations**: CIVIL AVIATION REQUIREMENT SECTION 8 - AIRCRAFT OPERATIONS SERIES 'C' PART I ISSUE II, DATED 28TH OCTOBER 2022:
An operator shall not conduct low visibility take-offs in less than 400 m RVR unless approved by DGCA. Operators may be authorized LVTO minima of up to 75m. Foreign operators, who are authorized by their State Regulatory Authority for LVTO, shall submit requisite documents to DGCA for approval of LVTO at Indian aerodromes.
An Operator shall not conduct take-off with RVR/visibility less than standard Category I conditions of 550m RVR/800 m visibility unless low visibility procedures are enforced.

6. **GENERAL:**

6.1 Low Visibility Procedures (Only for Take-off up to (not less than) 400 m RVR) have been developed for Barapani Airport, Shillong to accommodate/permit departures in visibility/RVR less than 800M/550M (from RWY 04 beginning (runway served with RVR instrument).
6.2 The Low Visibility Procedure (LVP) incorporates safeguarding measures to mitigate runway incursions and defines operational restrictions to ensure safe Airside Operations taking into account the available Aerodrome facilities.

7. **MINIMUM REQUIREMENTS**

7.1 The following Aeronautical Ground lights and RVR equipment shall be serviceable to the required standard to support Low Visibility Procedures:

i) Runway edge lights,
ii) Runway end lights,
iii) Runway Guard Lights (available on TWY 'A', TWY 'B'&TWY 'F'.)
iv) Instrument RVR (Available for TDZ runway 04).
v) Stand by Power supply to maintain switch over time of 1 Second for Runway Edge Light and Runway End Lights. This requirement can be met with the help of DG Set and/or UPS. Unserviceability of Aeronautical Ground Lights/ Equipment before Implementation of LVP Visibility Procedures will not be implemented when any of the light/equipment mentioned in para 7.1 above is un- serviceable or is not maintained as per the required standard.

Aeronautical Ground Lighting Facility	Un-serviceability	Restrictions
Runway Edge lights	**More than 15% of all lights are unserviceable**	**LVP operations will be suspended.**
	Any two consecutive lights or more are unserviceable	
Runway End lights	**More than 15% of all lights are unserviceable**	**LVP operations will be suspended.**
	Any two consecutive lights or more are unserviceable	
Standby Generators/UPS	**Any of the generator/UPS is unserviceable**	**LVP operations will be suspended.**

Note: When any of the light/equipment mentioned in para 7.1 above becomes un- serviceable or fails to meet the required standard during periods of LVP, Tower shall advise the aircraft accordingly and LVP shall be suspended and information to this effect shall be included in ATIS broadcast.

8. **EQUIPMENT AND SERVICES**

8.1 RVR Equipments

i) AWOS (Automated Weather Observing System) for Runway 04 side
ii) RVR is reported in the following scales:
a) The maximum reportable value of RVR is 2000 m. When RVR is above 1500 m, it is reported as 2000 m.
b) In the increments 100 m when greater than 800 m.
c) In the increments 50 m when RVR greater than 400 m but less than 800 m.
d) In the increments 25 m when less than 400 m. (as per Annex 3, Appendix 3, 4.3.6.1)

iii) In case of unserviceability of the above mereological equipment, the LVP shall be suspended.

8.2 ILS

8.2.1 Runway is equipped with CAT 1 ILS.

9. **SAFEGUARDING PROCEDURES**

9.1 Safeguarding Procedures (SP) are instructions for relevant airport, departments and airside operators to prepare ground services and facilities for low visibility operations in order that when LVP are implemented all Safeguarding procedures are complete.

9.2 Safeguarding Procedures shall be initiated when-

i) The Visibility/RVR is less than 1200m and visibility/RVR is forecast to deteriorate to 800m or less; and/or
ii) The cloud ceiling is less than 400ft and forecast to fall to 200ft or less.

9.3 Safeguarding procedures include-

i) Positioning of 1 CFT and ambulance at the predetermined position (Fire approach road).
ii) Stopping of all maintenance works on the manoeuvring area, ILS sensitive and critical area as removal of all men and mobile equipment from the said area.
iii) Ensuring availability of secondary power supply for change over time of maximum one second for Runway Edge and Runway End lights supported by UPS/ DG.
iv) The appropriate Aeronautical ground lights must have been inspected during the hour preceding implementation of LVP, and thereafter once every two-hour period. These lighting inspections should be accorded priority and, if necessary, aircraft operations may be delayed.
Note- Runway Edge and Runway End lights may continue to operate on main power supply during safeguarding Procedures. Whenever, LVP is to be implemented as per para 10 below, the Runway Edge and Runway End lights shall be put on Standby Power Supply
(DG set or UPS). This operation needs to be completed before LVP is implemented. In case the Lights are running on DG set, Main power supply shall act as stand by power. If UPS is capable of maintaining the required AGL system with one second of Switch Over time with Main Supply, the main supply can continue to be primary supply and t he Generator Supply can be kept as Stand by Power supply.
v) Ensure all access roads are closed.

9.4 Process of initiation of Safeguarding Procedures-

i) When meteorological conditions meet the criteria for initiation of SP as stipulated in Para 7.2, the Tower Supervisor/ Duty Officer will initiate and co coordinate with Electrical team, CNS, Duty Terminal Manager and Fire Station for completion of safeguarding procedures before implementation of Low Visibility Procedures.

ii) When all the CCR(Electrical), SSO (CNS), Duty Terminal Manager and Fire Station have completed their necessary actions, they shall report to Tower Supervisor/Duty Officer that their Safeguarding Procedure (SP) is completed, and the airport is safeguarded for LVP operations.

10. LOW VISIBILITY OPERATIONS

Low Visibility Procedures are the procedures to ensure the safe operation of aircraft during periods of reduced visibility or low cloud base. LVP shall only be implemented when Safeguarding Procedure (SP) has been completed, and the airport is configured for low visibility operations.

10.1 Implementation of Low Visibility Procedures-

i) Whenever Visibility/RVR reduces to 800 Meters or below and/ or cloud ceiling is at 200 ft or below the Tower Supervisor/Duty Officer shall coordinate with CCR (Electrical), SSO (CNS), Duty Terminal Manager and Fire Station to confirm whether the Safeguarding procedures have been completed or not.
ii) Once, it is confirmed that Safeguarding Procedures are implemented and LVP is necessitated, the Tower Supervisor/Duty Officer will implement Low Visibility Procedures and shall inform CCR(Electrical), SSO (CNS), Duty Terminal Manager and Fire Station of the imposition of low visibility procedures.

10.2 Actions by Tower Controller

i) Whenever visibility/RVR is less than 800M/550M, Tower shall confirm from pilot that the reported RVR value is within minima before issuing take-off clearance
ii) Tower shall ensure only one aircraft movement on the manoeuvring area at a time.
iii) Tower shall not permit any high-power ground run on the manoeuvring area except idle power run on the stands.
iv) The number of the vehicles on the manoeuvring area shall be restricted to bare minimum and records of all operating on the manoeuvring area shall be maintained by Tower.
v) As ATIS is not available the duty officer (Tower) shall inform all aircrafts in contact "Low Visibility Procedures in Force" in contact regarding on VHF.

10.3 Actions by SSO (CNS)

10.3.1 On receipt of "Initiating SP" from Tower Supervisor/Duty Officer, SSO (CNS) will inform the Duty Officer, NAV AIDS and have the ILS equipment and its status indicators in ATC units checked up.
10.3.2 On receipt of "Initiating LVP" from Tower Supervisor/Duty Officer that LVP are to be made effective SSO(CNS) will maintain continuous watch on the performance of ILS equipment.
10.3.3 He will inform Tower Supervisor/Duty Officer of any unserviceability in the equipment which is likely to affect Low Visibility operations.

10.4 Actions by Duty Terminal Manager (Airside)

10.4.1 On receipt of advice from Tower Supervisor/Duty Officer to implement Safeguarding procedure, the Terminal Duty Manager, will immediately inform the following:
i) Central Industrial Security Force (CISF) Control Room.
ii) All airlines/GHA.
iii) Civil In-charge.

10.4.2 Duty Terminal Manager (Airside) shall ensure that-
i) No vehicle/person enters or is present in the sensitive/critical areas of localizer and glide path.
ii) All civil/electrical works in progress are to be stopped in the manoeuvring area immediately and men/material/ equipment to be removed from the sensitive/critical areas of localizer and glide path.

10.4.3 Duty Terminal Manager (Airside) would advise Tower Supervisor/Duty Officer when all actions allocated to them are completed.
10.4.4 Subsequently, Duty Terminal Manager shall remain available in apron and will maintain listening watch on Walkie-Talkie.

10.4.5 The vehicles which are not equipped with RT but has to enter the runway or taxiway for urgent operational requirement shall be escorted by follow me/vehicle equipped with RT at all times...

10.4.6 Duty Terminal Manager (Airside) shall ensure that all the roads are closed during the Low Visibility Operations, except the Fire approach road designated as PDPs.

10.5 Actions by Shift In-Charge (Civil)

10.5.1 Shift In-Charge (Civil) to ensure that all civil works in progress in manoeuvring area, are stopped and that the work area is restored in complete serviceable condition and confirm to Tower Supervisor/Duty Officer accordingly.
10.5.2 Shift In-Charge (Civil) to ensure that during Low Visibility Operations, no equipment, manpower shall be present in sensitive areas of localizer and glide path.
10.5.3 Shift In-Charge (Civil) to ensure that none of the civil contract workers/vehicles shall enter the manoeuvring area during the Low Visibility operations.

10.6 Actions by Shift In-Charge (Electrical)

10.6.1 On receipt of advice to implement Low Visibility Procedures from Tower Supervisor/Duty Officer, will check that following visual aids are serviceable and can be operated at full intensity:

i) Approach lighting system.
ii) Runway edge lights.
iii) Runway threshold and end lights.
iv) Runway guard lights.
v) Taxiway edge lights.

(NOTE - No adjustment in light intensity shall be made without permission from ATC Tower during LVP)

10.6.2 Shift In-Charge (Electrical) shall ensure that no electrical maintenance works is carried out during LVP either in powerhouse or on any other electrical facilities used during Low visibility operations.

10.6.3 Shift In-Charge (Electrical) will ensure that Runway switch room is manned and position themselves at halls for ground lighting facilities.
10.6.4 Shift In-Charge (Electrical) will inform the un-serviceability or any change in status of any facility/systems to Tower Supervisor/Duty Officer immediately.

10.7 Actions by ARFF/Fire Station

10.7.1 Positioning of 1 CFT and Ambulance at the predetermined positions (Fire approach road).
10.7.2 ARFF/ CFTs must obtain clearances from Tower prior to entry to any aircraft movement area.

10.8 Actions by Tower Met Officer (Meteorological Office)

10.8.1 Tower Met Officer would issue an 'Outlook for Low Visibility Procedures' to the Tower Supervisor/ Duty Officer of air traffic services whenever he expects that the RVR and/or cloud ceiling will fall below 800 m and/or 200ft or less respectively.
10.8.2 Whenever Tower Met Officer visualizes that RVR is likely to fall below 800 m and/or cloud ceiling to 200ft or less within next 2 hours, he will inform to Tower Supervisor/Duty Officer to this effect.
10.8.3 When the RVR and/or cloud ceiling are 800m and/or 200ft respectively and the trend is towards improvement in these elements of weather conditions the Duty Met Officer may, when requested by Tower Supervisor/Duty Officer, advise him about such improving weather conditions for the purpose of termination of LVP.
10.8.4 The Tower Met Officer shall be present in Tower during periods of reduced visibility and ensure that the RVR displays in ATC units in the Tower and Approach Control are serviceable.

11. **Termination of Low Visibility Procedures**

11.1 When Visibility/RVR improves to 800M or more and cloud ceiling is 200 feet or Higher and trend is for improvement, Tower Supervisor/Duty Officer Tower would terminate operations of LVP. He may obtain advice from Tower Met Officer regarding improvement in weather conditions before the termination of LVP.
11.2 As ATIS is not available, on termination of LVP, following message shall be broadcast by the duty officer (Tower) shall inform all aircrafts in contact “LOW VISIBILITY PROCEDURES TERMINATED” on VHF.

11.3 If SP are implemented and LVP are not subsequently implemented and the visibility/RVR improves and is more than 1200 m and/or the cloud ceiling is 400ft or higher and both are forecast to remain above the required SP criteria, Tower Supervisor/ Duty Officer Tower may cancel SP.

12. **Other Actions: -**

i) Every year before commencement of monsoon/winter season, a meeting will be held by Airport Director, to inform all airlines and agencies operating at airport about their roles/responsibilities and create awareness to ensure co-operation for safe airport operations during periods of low visibility.
ii) Before issuing the Airside drive permits, the OPS In charge shall ensure that staff and drivers are suitably trained for Low Visibility operations.
iii) All agencies operating in the operational area shall ensure that only those vehicles that are absolutely essential for aircraft operations operate in the operational area during periods of low visibility. The drivers of these vehicles should keep a look out for taxiing aircraft and other vehicles to prevent accidents.
iv) All the vehicles must have their obstruction lights "ON" during Low Visibility Procedures operations.
v) A refresher program for ATCO's and personnel responsible for airside operations shall be conducted every year.

VEBI AD 2.21 NOISE ABATEMENT PROCEDURES

NIL

VEBI AD 2.22 FLIGHT PROCEDURES

NIL

VEBI AD 2.23 ADDITIONAL INFORMATION

1. Only RWY22 (ILS Procedure is designed and approved for CAT A/B/C type ACFT) shall be used for all weather OPS.

VEBI AD 2.24 CHARTS RELATED TO AN AERODROME

1. Aerodrome Chart (07 August 2025)
2. Aircraft Parking / Docking Chart (07 August 2025)
3. Aerodrome Obstacle Chart Type-A (Operating Limitations) RWY 04 (07 August 2025)
4. Aerodrome Obstacle Chart Type-A (Operating Limitations) RWY 22 (07 August 2025)
5. Aerodrome Obstacle Chart Type-B (07 August 2025)
6. ILS Procedure RWY 22 (17 April 2025)
7. Standard Departure Chart Instrument (SID) RWY 04 (17 April 2025)

VEBI AD 2.25 VISUAL SEGMENT SURFACE (VSS) PENETRATION

Procedure	Procedure Minima	VSS Penetration
1	2	3