AD 2. AERODROMES

VEPT AD 2.1 AERODROME LOCATION INDICATOR AND NAME

VEPT - JAI PRAKASH NARAYAN INTERNATIONAL AIRPORT, PATNA

VEPT AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome reference point coordinates and its site	253537N 0850531E MAG. BRG. 263.22DEG /510 M from physical beginning of RWY 25.	
2	Direction and distance of aerodrome reference point from the center of the city or town which the aerodrome serves	259 DEG, 5KM from Patna Railway Station.	
3	Aerodrome elevation and reference temperature	175 FT / 35.4 DEG C	
4	Magnetic variation, date of information and annual change	0.25 DEG W (2010) /0.017 DEG E	
5	Name of aerodrome operator, address, telephone, telefax, e-mail address, AFS address, website (if available)	Airport Director, Airports Authority of India, Jai Prakash Narayan International Airport,, Patna - 800014	
		Telephone:	(91) 612 2220683 (91) 9431821772
		Fax:	(91) 612 2225227
		AFS:	VEPTYHYX
		Email:	apdpatna@aai.aero
6	Types of traffic permitted (IFR/VFR)	IFR/VFR	
7	Remarks	Elevation in EGM08	

VEPT AD 2.3 OPERATIONAL HOURS

1	Aerodrome Operator	MON-FRI: 0400-1230 UTC (0930-1800 IST) SAT,SUN & HOL: NIL	
2	Custom and immigration	See Remark No. 1	
3	Health and sanitation	As ATS	
4	AIS briefing office	As ATS	
5	ATS reporting office (ARO)	As ATS	
6	MET Briefing office	As ATS	
7	Air Traffic Service	H24	
8	Fuelling	As ATS	
9	Handling	As ATS	
10	Security	As ATS	
11	De-icing	NIL	
12	Remarks	1. Customs and immigration facilities are provided on limited basis to cover operations of scheduled international flights. The facilities can be arranged to cover any authorized non-SKED operations.	
		2.ATS approved hourly runway traffic handling capacity	Maximum number of arrival and departure- 10 Maximum number of arrival only – 05 Maximum number of departure only -05

VEPT AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo-handling facilities	Nil

2	Fuel and Oil types	ATF-K50 Mj0-2
3	Fuelling facilities and capacity	Refueler: ATF2 16000 & 9000Litres each 25Ltr/sec, AVG1 9000 Ltr, 12.5 Litres/sec.
4	De-icing facilities	NIL
5	Hangar space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	NIL

VEPT AD 2.5 PASSENGER FACILITIES

1	Hotel(s) at or in the vicinity of aerodrome	In the City
2	Restaurant(s) at or in the vicinity of aerodrome	At AD and in the City
3	Transportation possibilities	Buses,Taxis.
4	Medical Facilities	First Aid at AD. Hospitals in the city.
5	Bank and post office at or in the vicinity of aerodrome	Banks: At AD Post office: At AD
6	Tourist office	At AD
7	Remarks	NIL

VEPT AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	Within ATS HR: CAT-7
2	Rescue equipment	AVBL as per category
3	Capability for removal of disabled aircraft	1. The critical aircraft for the airport is [A320]. 2. Primary responsibility for removal of disabled aircraft rests with the concerned airline. 3. The airlines may contact 'Aerodrome Coordinator for Disabled Aircraft Removal Operations' for coordinating with the agencies having Disabled Aircraft Recovery Kit. 4. Contact Details of Aerodrome Coordinator for Disabled Aircraft Removal Operations: [HOD Operations] [0612-2220683 (O)] [Email: apdpatna@aai.aero]
4	Remarks	NIL

VEPT AD 2.7 SEASONAL AVAILABILITY CLEARING

1	Type(s) of clearing equipment	NIL
2	Clearance priorities	NIL
3	Remarks	NIL

VEPT AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Designation, surface and strength of aprons	Refer Aircraft Parking/Docking Chart
2	Designation, width, surface and strength of taxiways	Refer Aircraft Parking/Docking Chart
3	Location and elevation of altimeter checkpoints	Location At apron Elevation 168FT
4	Location of VOR checkpoints	On TWYA: 253534.01N 0850525.17E ELEV: 174 FT.
5	Position of INS checkpoints	

6	Remarks	**1. Coordinates of RWY Holding positions:** a. TWY A: 253533.74N 0850525.29E, Elev: 174 FT b. TWY B: 253535.45N 0850530.12E, Elev: 174 FT c. TWY C: 253538.26N 0850537.08E, Elev: 174 FT d. TWY D: 253539.17N 0850540.09E, Elev: 174 FT e. TWY E: 253526.44N 0850522.66E, Elev: 173 FT f. TWY F: 253517.37N 0850440.14E, Elev: 175 FT **2. Coordinates of RWY and Taxi intersection:** a. TWY A: 253530.98N 0850526.52E, Elev: 174 FT b. TWY B: 253532.70N 0850531.32E, Elev: 175 FT c. TWY C: 253536.58N 0850542.09E, Elev: 175 FT d. TWY D: 253536.61N 0850542.19E, Elev: 175 FT e. TWY E: 253529.16N 0850521.46E, Elev: 174 FT f. TWY F: 253514.46N 0850440.50E, Elev: 175 FT **3**. Isolated Aircraft Parking Position (IAPP): South of Runway connected via TWY E, surface Concrete strength (PCR): 547/R/B/W/T. **4. All elevations in EGM08**

VEPT AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand identification signs, taxiway guidelines and visual docking/parking guidance system at aircraft stands	Taxiing guidance provided on R/T, Guidelines at Apron. VDGS provided on Parking stand No 7, 8, 9, 10 & 11 with aerobridge facility Remote parking stand no 1,2 and 3 shifted.
2	Runway and taxiway markings and lights	RWY Markings: Designation, THR, Fixed Distance, Centreline, EDGE, Aiming Point Lights: THR, End , Edge and Turn Pad TWY Marking: Centreline, Holding Position, Edge Lights: Edge.
3	Stop bars (if any)	Nil
4	Remarks	NIL

VEPT AD 2.10 AERODROME OBSTACLES

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	TREE	253513.3N 0850430.3E	210 FT	NIL	TREE
25/TKOF 07/APCH	TREE	253515.2N 0850425.2E	248 FT	NIL	TREE
25/TKOF 07/APCH	POLE	253509.6N 0850429.5E	208 FT	NIL	POLE
25/TKOF 07/APCH	POLE	253509.1N 0850424.6E	210 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	TREE	253509.1N 0850419.2E	221 FT	NIL	GROUP OF TREE
25/TKOF 07/APCH	POLE	253513.1N 0850425.4E	200 FT	NIL	ELECTRIC POLE WITH TRANSFORMER
25/TKOF 07/APCH	BUILDING	253513.9N 0850423.5E	218 FT	NIL	BUILDING

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	OTHER	253510.2N 0850432.7E	217 FT	NIL	RAILWAY TRACK CROSSING BARRIER
25/TKOF 07/APCH	OTHER	253509.8N 0850432.5E	196 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 54.7 M. + TRAFFIC HEIGHT 5.0 M.)
25/TKOF 07/APCH	OTHER	253510.0N 0850435.1E	204 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.7 M. + TRAFFIC HEIGHT 7.6 M.)
25/TKOF 07/APCH	BUILDING	253508.8N 0850432.1E	202 FT	NIL	BUILDING
25/TKOF 07/APCH	OTHER	253507.1N 0850432.9E	229 FT	NIL	FLAG ON BUILDING (BUILDING. TOP 64.4 M.)
25/TKOF 07/APCH	BUILDING	253504.7N 0850423.4E	212 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253503.8N 0850420.6E	220 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253503.2N 0850423.1E	221 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 66.0 M.)
25/TKOF 07/APCH	BUILDING	253503.3N 0850418.8E	216 FT	NIL	BUILDING
25/TKOF 07/APCH	OTHER	253500.8N 0850418.2E	224 FT	NIL	ROD ON BUILDING
25/TKOF 07/APCH	BUILDING	253459.4N 0850418.2E	221 FT	NIL	Building
25/TKOF 07/APCH	TREE	253507.8N 0850412.2E	248 FT	NIL	GROUP OF TREE
25/TKOF 07/APCH	TREE	253514.6N 0850434.3E	216 FT	NIL	TREE
25/TKOF 07/APCH	TREE	253516.0N 0850434.3E	225 FT	NIL	TREE
25/TKOF 07/APCH	OTHER	253510.5N 0850438.5E	204 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.7 M. + TRAFFIC HEIGHT 7.6 M.)
25/TKOF 07/APCH	POLE	253511.0N 0850439.0E	204 FT	NIL	POLE
25/TKOF 07/APCH	POLE	253510.8N 0850437.7E	208 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	POLE	253510.6N 0850435.8E	208 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	POLE	253510.2N 0850434.0E	208 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	BUILDING	253509.5N 0850433.5E	211 FT	NIL	RAILWAY OUTERSIGNAL BUILDING

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	FENCE	253510.7N 0850434.9E	188 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/TKOF 07/APCH	BUILDING	253516.0N 0850432.9E	187 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253516.0N 0850435.1E	198 FT	NIL	TEMPLE
25/TKOF 07/APCH	BUILDING	253515.4N 0850434.3E	191 FT	NIL	SECURITY HUT
25/TKOF 07/APCH	FENCE	253514.3N 0850434.6E	187 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/TKOF 07/APCH	OTHER	253514.2N 0850432.5E	190 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.9 M. + TRAFFIC HEIGHT 5.0 M.)
25/TKOF 07/APCH	TREE	253507.7N 0850422.9E	214 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253507.6N 0850426.3E	210 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 63.7 M.)
25/TKOF 07/APCH	BRIDGE	253506.9N 0850428.4E	215 FT	NIL	BUILDING
25/TKOF 07/APCH	OTHER	253457.3N 0850403.4E	267 FT	NIL	CELLPHONE MAST
25/TKOF 07/APCH	OTHER	253444.5N 0850344.3E	314 FT	NIL	CELLPHONE MAST
25/TKOF 07/APCH	OTHER	253511.3N 0850438.6E	190 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 53.0 M. + TRAFFIC HEIGHT 5.0 M.)
25/TKOF 07/APCH	FENCE	253511.0N 0850438.0E	189 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/TKOF 07/APCH	OTHER	253511.9N 0850433.2E	191 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 53.2 M. + TRAFFIC HEIGHT 5.0 M.)
25/TKOF 07/APCH	BUILDING	253508.0N 0850437.1E	227 FT	NIL	SINTEX TANK ON BUILDING
25/TKOF 07/APCH	BUILDING	253507.9N 0850435.3E	209 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253508.7N 0850433.0E	218 FT	NIL	BUILDING
25/TKOF 07/APCH	OTHER	253458.0N 0850415.6E	287 FT	NIL	MAST
25/TKOF 07/APCH	TREE	253516.0N 0850431.4E	227 FT	NIL	TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253504.3N 0850429.6E	223 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 67.8 M.)
25/TKOF 07/APCH	BUILDING	253513.9N 0850420.2E	213 FT	NIL	SINTEX TANK ON BUILDING
25/TKOF 07/APCH	TREE	253513.8N 0850417.4E	255 FT	NIL	GROUP OF TREE(PALM)
25/TKOF 07/APCH	TREE	253515.7N 0850429.1E	215 FT	NIL	Tree
25/TKOF 07/APCH	BUILDING	253513.6N 0850422.9E	218 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253511.5N 0850425.8E	223 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253508.2N 0850436.1E	225 FT	NIL	SINTEX TANK ON BUILDING (BUILDING. TOP 38.2 M.)
25/TKOF 07/APCH	TREE	253508.9N 0850437.3E	224 FT	NIL	Tree
25/TKOF 07/APCH	BUILDING	253511.9N 0850425.1E	212 FT	NIL	Building
25/TKOF 07/APCH	TREE	253512.1N 0850409.5E	234 FT	NIL	GROUP OF TREE
25/TKOF 07/APCH	TREE	253512.0N 0850422.9E	208 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253506.6N 0850430.2E	198 FT	NIL	BUILDING
25/TKOF 07/APCH	POLE	253509.4N 0850431.6E	209 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	TREE	253501.2N 0850403.0E	252 FT	NIL	Group of trees
25/TKOF 07/APCH	TREE	253517.4N 0850434.4E	242 FT	NIL	Tree
25/TKOF 07/APCH	TREE	253506.2N 0850433.1E	242 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253502.1N 0850421.1E	233 FT	NIL	SINTEX TANK ON BUILDING
25/TKOF 07/APCH	SIGN	253511.3N 0850438.2E	179 FT	NIL	SIGN BOARD
25/TKOF 07/APCH	POLE	253510.6N 0850436.3E	204 FT	NIL	POLE
25/TKOF 07/APCH	POLE	253509.9N 0850435.9E	208 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	BUILDING	253507.7N 0850436.0E	210 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 63.1 M.)
25/TKOF 07/APCH	BUILDING	253508.6N 0850436.6E	214 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253508.5N 0850437.0E	227 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253508.4N 0850437.2E	214 FT	NIL	BUILDING

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	POLE	253510.3N 0850434.4E	205 FT	NIL	POLE
25/TKOF 07/APCH	BUILDING	253510.3N 0850436.8E	205 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.9 M. + TRAFFIC HEIGHT 7.6 M.)
25/TKOF 07/APCH	POLE	253509.7N 0850434.1E	208 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	BUILDING	253509.6N 0850433.8E	202 FT	NIL	RAILWAY GANGHUT BUILDING
25/TKOF 07/APCH	POLE	253510.1N 0850433.1E	205 FT	NIL	Pole
25/TKOF 07/APCH	BUILDING	253508.3N 0850432.8E	218 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.1 M.)
25/TKOF 07/APCH	BUILDING	253506.4N 0850433.7E	223 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253506.2N 0850432.5E	240 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253507.0N 0850432.0E	225 FT	NIL	BUILDING
25/TKOF 07/APCH	OTHER	253513.3N 0850433.4E	189 FT	NIL	LIGHTED TOP ON LLZ HUT (HUT TOP 56.5 M.)
25/TKOF 07/APCH	TREE	253514.2N 0850433.2E	210 FT	NIL	Tree
25/TKOF 07/APCH	OTHER	253515.2N 0850434.5E	192 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 53.4 M. + TRAFFIC HEIGHT 5.0 M.)
25/TKOF 07/APCH	TREE	253516.4N 0850436.7E	216 FT	NIL	TREE
25/TKOF 07/APCH	POLE	253516.5N 0850432.4E	198 FT	NIL	ELECTRIC POLE
25/TKOF 07/APCH	TREE	253515.8N 0850432.2E	221 FT	NIL	TREE
25/TKOF 07/APCH	TREE	253513.3N 0850432.2E	187 FT	NIL	SHED
25/TKOF 07/APCH	TREE	253513.7N 0850432.0E	216 FT	NIL	TREE
25/TKOF 07/APCH	TREE	253514.6N 0850432.0E	217 FT	NIL	Tree
25/TKOF 07/APCH	BUILDING	253510.0N 0850432.7E	196 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 54.8 M. + TRAFFIC HEIGHT 5.0 M.)
25/TKOF 07/APCH	POLE	253509.9N 0850431.6E	208 FT	NIL	RAILWAY ELECTRIC POLE
25/TKOF 07/APCH	TREE	253508.8N 0850431.8E	227 FT	NIL	PALM TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253507.4N 0850431.4E	218 FT	NIL	BUILDING
25/TKOF 07/APCH	OTHER	253507.3N 0850431.1E	219 FT	NIL	SHED ON BUILDING (BUILDING. TOP 64.7 M.)
25/TKOF 07/APCH	TREE	253505.2N 0850430.2E	229 FT	NIL	TREE
25/TKOF 07/APCH	ANTENNA	253504.4N 0850430.1E	231 FT	NIL	COMMUNICATIO N ANTENNA ON BUILDING (BUILDING. TOP 68.3 M.)
25/TKOF 07/APCH	BUILDING	253503.3N 0850427.0E	206 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253504.5N 0850426.8E	207 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253505.2N 0850427.8E	216 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 64.8 M.)
25/TKOF 07/APCH	BUILDING	253506.4N 0850429.4E	215 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253506.2N 0850428.6E	216 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253507.3N 0850430.0E	213 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253507.9N 0850430.2E	208 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253507.3N 0850429.1E	210 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253507.8N 0850428.6E	216 FT	NIL	Building
25/TKOF 07/APCH	TREE	253509.0N 0850429.5E	216 FT	NIL	PALM TREE
25/TKOF 07/APCH	POLE	253509.2N 0850429.3E	207 FT	NIL	POLE
25/TKOF 07/APCH	OTHER	253508.9N 0850424.9E	205 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.8 M. + TRAFFIC HEIGHT 7.6 M.)
25/TKOF 07/APCH	POLE	253509.3N 0850427.3E	207 FT	NIL	POLE
25/TKOF 07/APCH	POLE	253511.8N 0850426.0E	201 FT	NIL	ELECTRIC POLE
25/TKOF 07/APCH	BUILDING	253512.1N 0850426.3E	197 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 58.7 M.)
25/TKOF 07/APCH	BUILDING	253512.4N 0850425.5E	220 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.5 M.)

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253512.1N 0850425.5E	216 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 64.6 M.)
25/TKOF 07/APCH	BUILDING	253510.4N 0850425.3E	209 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253509.6N 0850425.2E	226 FT	NIL	TREE
25/TKOF 07/APCH	POLE	253508.7N 0850424.8E	211 FT	NIL	POLE
25/TKOF 07/APCH	BUILDING	253511.5N 0850424.1E	209 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253510.8N 0850424.0E	207 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253511.4N 0850423.3E	216 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253510.0N 0850423.3E	205 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253509.8N 0850422.9E	208 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253509.0N 0850423.0E	209 FT	NIL	RAILWAY POLE
25/TKOF 07/APCH	BUILDING	253507.7N 0850423.8E	212 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 63.6 M.)
25/TKOF 07/APCH	BUILDING	253507.7N 0850424.2E	208 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 62.4 M.)
25/TKOF 07/APCH	BUILDING	253507.1N 0850424.4E	213 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 64.7 M.)
25/TKOF 07/APCH	BUILDING	253506.8N 0850424.9E	214 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253507.4N 0850425.7E	207 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 62.0 M.)
25/TKOF 07/APCH	BUILDING	253507.2N 0850426.3E	210 FT	NIL	TEMPLE
25/TKOF 07/APCH	BUILDING	253507.8N 0850426.9E	215 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253507.9N 0850427.0E	212 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 63.3 M.)
25/TKOF 07/APCH	ANTENNA	253508.0N 0850427.8E	213 FT	NIL	DISH ANTENNA ON BUILDING (BUILDING. TOP 64.2 M.)
25/TKOF 07/APCH	BUILDING	253507.3N 0850428.1E	214 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253507.3N 0850427.2E	214 FT	NIL	BUILDING

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253506.9N 0850427.0E	213 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253506.7N 0850427.7E	215 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253506.7N 0850428.2E	215 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253505.9N 0850426.8E	216 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.0 M.)
25/TKOF 07/APCH	BUILDING	253506.3N 0850426.7E	211 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253506.4N 0850425.9E	218 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 64.5 M.)
25/TKOF 07/APCH	BUILDING	253506.2N 0850425.3E	217 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.5 M.)
25/TKOF 07/APCH	BUILDING	253506.1N 0850424.8E	218 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.7 M.)
25/TKOF 07/APCH	BUILDING	253506.2N 0850424.7E	215 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253505.3N 0850424.7E	216 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253505.3N 0850425.2E	220 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.5 M.)
25/TKOF 07/APCH	BUILDING	253504.9N 0850425.7E	220 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 66.3 M.)
25/TKOF 07/APCH	BUILDING	253504.4N 0850425.4E	221 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253510.6N 0850421.8E	210 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253511.1N 0850421.8E	214 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253512.5N 0850422.4E	214 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.1 M.)
25/TKOF 07/APCH	TREE	253512.2N 0850421.7E	242 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253513.7N 0850421.6E	211 FT	NIL	BUILDING
25/TKOF 07/APCH	POLE	253513.1N 0850426.0E	199 FT	NIL	ELECTRIC POLE WITH TRANSFORMER
25/TKOF 07/APCH	BUILDING	253513.4N 0850422.7E	219 FT	NIL	BUILDING

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253513.7N 0850423.1E	219 FT	NIL	Building
25/TKOF 07/APCH	TREE	253511.2N 0850420.7E	232 FT	NIL	PALM TREE
25/TKOF 07/APCH	BUILDING	253511.3N 0850419.2E	219 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 65.1 M.)
25/TKOF 07/APCH	BUILDING	253510.7N 0850417.7E	221 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253510.1N 0850415.2E	221 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253510.7N 0850414.2E	238 FT	NIL	GROUP OF TREE (PALM)
25/TKOF 07/APCH	POLE	253508.3N 0850421.3E	209 FT	NIL	RAILWAY POLE
25/TKOF 07/APCH	TREE	253507.4N 0850419.8E	225 FT	NIL	GROUP OF TREE(PALM)
25/TKOF 07/APCH	BUILDING	253506.1N 0850418.8E	216 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253505.8N 0850420.0E	236 FT	NIL	TREE
25/TKOF 07/APCH	ANTENNA	253506.4N 0850421.0E	229 FT	NIL	ANTENNA ON BUILDING (BUILDING. TOP 63.5 M.)
25/TKOF 07/APCH	BUILDING	253506.1N 0850423.5E	216 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 64.7 M.)
25/TKOF 07/APCH	BUILDING	253505.7N 0850422.5E	220 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253506.0N 0850422.2E	222 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253505.1N 0850421.5E	221 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253504.8N 0850422.8E	214 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 64.2 M.)
25/TKOF 07/APCH	BUILDING	253503.9N 0850422.3E	217 FT	NIL	Building
25/TKOF 07/APCH	BUILDING	253502.8N 0850423.3E	224 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 67.1 M.)
25/TKOF 07/APCH	BUILDING	253458.1N 0850417.6E	227 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 68.6 M.)
25/TKOF 07/APCH	BUILDING	253458.2N 0850417.0E	230 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 69.5 M.)
25/TKOF 07/APCH	BUILDING	253500.4N 0850416.0E	226 FT	NIL	BIRLA TEMPLE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253500.6N 0850415.1E	229 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 68.4 M.)
25/TKOF 07/APCH	BUILDING	253503.0N 0850417.4E	226 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 67.2 M.)
25/TKOF 07/APCH	BUILDING	253502.9N 0850421.1E	218 FT	NIL	BUILDING
25/TKOF 07/APCH	BUILDING	253503.5N 0850421.2E	219 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253503.9N 0850420.9E	251 FT	NIL	TREE
25/TKOF 07/APCH	OTHER	253458.4N 0850413.6E	248 FT	NIL	MULTI MAST ON BUILDING (BUILDING. TOP 66.7 M.)
25/TKOF 07/APCH	OTHER	253458.6N 0850411.6E	234 FT	NIL	FLAG ON BUILDING (BUILDING. TOP 66.5 M.)
25/TKOF 07/APCH	OTHER	253509.0N 0850434.3E	211 FT	NIL	CATENARY MAST
25/TKOF 07/APCH	TREE	253514.6N 0850434.0E	196 FT	NIL	GROUP OF TREES
25/TKOF 07/APCH	OTHER	253513.4N 0850433.1E	185 FT	NIL	TIN SHEET COVER ON TOP OF BOUNDARY WALL
25/TKOF 07/APCH	TREE	253510.6N 0850433.1E	188 FT	NIL	TIN SHEET COVER ON TOP OF BOUNDARY WALL
25/TKOF 07/APCH	OTHER	253509.4N 0850433.1E	228 FT	NIL	MAST NEAR RLY GUMTI BUILDING
25/TKOF 07/APCH	OTHER	253509.2N 0850432.3E	204 FT	NIL	VEHICLE HEIGHT RESTRICTION BAR (FLAG TOP=62.1M)
25/TKOF 07/APCH	BUILDING	253512.6N 0850414.7E	224 FT	NIL	WATER TANK ON BUILDING (BUILDING ELEVATION=67.2 M)
25/TKOF 07/APCH	OTHER	253500.7N 0850413.2E	244 FT	NIL	MAST ON BUILDING (BUILDING ELEVATION=67.5 M)
25/TKOF 07/APCH	NAVAID	253513.1N 0850436.6E	178 FT	NIL	LOCALIZER MONITOR ANTENNA
25/TKOF 07/APCH	BUILDING	253507.4N 0850433.6E	235 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP=70.5 M.)

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/TKOF 07/APCH	BUILDING	253506.4N 0850432.8E	206 FT	NIL	BUILDING
25/TKOF 07/APCH	TREE	253513.9N 0850432.1E	216 FT	NIL	TREE
25/TKOF 07/APCH	BUILDING	253508.2N 0850432.7E	217 FT	NIL	STAIRCASE ROOM TOP ON BUILDING
25/TKOF 07/APCH	OTHER	253516.9N 0850435.8E	208 FT	NIL	LIGHTENING ROD ON SPEEDCRAFTS INFRATECH FACTORY SHED (SHED TOP=62.6M)
25/TKOF 07/APCH	OTHER	253513.2N 0850433.1E	185 FT	NIL	GATE WITH FENCING TOP (GATE TOP - 55.87 M.)
25/TKOF 07/APCH	POLE	253512.6N 0850433.5E	188 FT	NIL	LIGHTED POLE
25/TKOF 07/APCH	OTHER	253511.5N 0850434.1E	184 FT	NIL	LIGHT ON LOCALIZER ANTENNA (ANTENNA TOP=55.5 M.)
25/TKOF 07/APCH	BUILDING	253509.6N 0850418.3E	216 FT	NIL	BUILDING U/C
25/TKOF 07/APCH	BUILDING	253512.7N 0850417.1E	224 FT	NIL	BUILDING U/C
25/TKOF 07/APCH	BUILDING	253512.0N 0850421.2E	220 FT	NIL	BUILDING U/C
25/TKOF 07/APCH	TREE	253508.9N 0850433.7E	220 FT	NIL	Group of trees
25/TKOF 07/APCH	OTHER	253514.1N 0850428.5E	219 FT	NIL	MAST
25/TKOF 07/APCH	OTHER	253511.5N 0850408.5E	233 FT	NIL	SHED ON BUILDING (BUILDING TOP=68.1 M.)
25/TKOF 07/APCH	OTHER	253459.4N 0850412.2E	239 FT	NIL	SHED ON BUILDING (BUILDING TOP=70.7 M.)
25/APCH 07/TKOF	TREE	253544.5N 0850552.4E	239 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	OTHER	253543.3N 0850552.8E	190 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.9 M. + TRAFFIC HEIGHT 5.0 M.)
25/APCH 07/TKOF	TREE	253543.2N 0850554.3E	210 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253536.9N 0850556.7E	250 FT	NIL	TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/APCH 07/TKOF	OTHER	253538.5N 0850556.2E	189 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.5 M. + TRAFFIC HEIGHT 5.0 M.)
25/APCH 07/TKOF	TREE	253540.2N 0850604.7E	220 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253546.4N 0850607.3E	228 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253545.5N 0850607.7E	242 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253546.5N 0850608.6E	218 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253547.0N 0850609.7E	228 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253549.0N 0850609.2E	230 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253549.0N 0850611.6E	238 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253550.5N 0850612.1E	234 FT	NIL	Group of trees
25/APCH 07/TKOF	BUILDING	253552.5N 0850612.0E	237 FT	NIL	Security hut (l)
25/APCH 07/TKOF	TREE	253553.4N 0850615.4E	263 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253550.7N 0850616.6E	246 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253551.9N 0850623.1E	255 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253553.9N 0850624.8E	263 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253546.1N 0850630.2E	256 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253544.1N 0850628.1E	237 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253544.3N 0850626.3E	249 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253543.4N 0850618.3E	239 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253545.3N 0850617.4E	226 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253546.0N 0850616.4E	239 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253544.5N 0850616.3E	245 FT	NIL	Group of trees
25/APCH 07/TKOF	OTHER	253558.5N 0850701.2E	338 FT	NIL	CLOCK TOWER ROD TOP (LIGHTED TOP 101.9 M. & TOWER TOP 101.7 M.)
25/APCH 07/TKOF	TREE	253544.7N 0850600.0E	206 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253548.3N 0850605.3E	219 FT	NIL	Group of trees

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/APCH 07/TKOF	TREE	253544.0N 0850555.3E	219 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253543.8N 0850556.1E	219 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253542.1N 0850558.0E	189 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253541.3N 0850600.5E	200 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253550.3N 0850608.5E	229 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253557.6N 0850622.9E	267 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253539.3N 0850602.4E	208 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253546.7N 0850600.6E	201 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253539.1N 0850556.6E	190 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.8 M. + TRAFFIC HEIGHT 5.0 M.)
25/APCH 07/TKOF	FENCE	253538.3N 0850556.2E	183 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/APCH 07/TKOF	TREE	253538.7N 0850556.5E	183 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/APCH 07/TKOF	OTHER	253542.9N 0850552.1E	187 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.0 M. + TRAFFIC HEIGHT 5.0 M.)
25/APCH 07/TKOF	FENCE	253543.3N 0850551.8E	181 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/APCH 07/TKOF	OTHER	253541.5N 0850618.9E	188 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.3 M. + TRAFFIC HEIGHT 5.0 M.)
25/APCH 07/TKOF	FENCE	253543.1N 0850552.4E	182 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
25/APCH 07/TKOF	TREE	253540.1N 0850606.5E	240 FT	NO	Group of trees
25/APCH 07/TKOF	TREE	253544.1N 0850557.2E	222 FT	NO	Group of trees
25/APCH 07/TKOF	TREE	253544.7N 0850557.7E	217 FT	NO	Group of trees
25/APCH 07/TKOF	TREE	253544.3N 0850558.3E	216 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253542.0N 0850559.5E	199 FT	NIL	Group of trees

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/APCH 07/TKOF	TREE	253543.3N 0850600.8E	205 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253544.2N 0850601.1E	212 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253544.5N 0850602.3E	211 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253545.0N 0850604.9E	201 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253545.4N 0850601.5E	212 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253547.6N 0850601.4E	235 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253547.3N 0850559.2E	248 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253548.6N 0850604.2E	243 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253549.3N 0850605.4E	260 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253548.5N 0850607.8E	239 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253545.1N 0850612.5E	227 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253540.5N 0850608.6E	253 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253542.9N 0850613.7E	250 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253544.6N 0850618.9E	241 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253550.9N 0850620.6E	246 FT	NIL	Group of trees
25/APCH 07/TKOF	TREE	253551.5N 0850613.6E	246 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253554.4N 0850612.4E	290 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253549.8N 0850627.2E	248 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253547.9N 0850559.5E	237 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253549.1N 0850601.6E	254 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253550.3N 0850602.1E	269 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253550.5N 0850602.9E	260 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253543.7N 0850553.3E	224 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253544.8N 0850556.0E	224 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253545.9N 0850557.6E	247 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253546.7N 0850558.6E	247 FT	NIL	GROUP OF TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/APCH 07/TKOF	TREE	253550.3N 0850605.8E	244 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253544.9N 0850609.5E	238 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253540.6N 0850602.8E	212 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253536.9N 0850553.8E	225 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	BUILDING	253536.9N 0850556.1E	194 FT	NIL	BUILDING
25/APCH 07/TKOF	TREE	253536.0N 0850554.5E	247 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253546.3N 0850556.0E	243 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253538.5N 0850557.8E	231 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253544.2N 0850553.0E	238 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	OTHER	253551.1N 0850610.7E	243 FT	NIL	MAST
25/APCH 07/TKOF	TREE	253542.4N 0850600.5E	205 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253553.0N 0850609.1E	223 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253544.9N 0850554.9E	242 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253547.1N 0850619.3E	240 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253544.3N 0850613.6E	224 FT	NIL	Tree
25/APCH 07/TKOF	OTHER	253541.9N 0850557.0E	186 FT	NIL	APPROACH LIGHT
25/APCH 07/TKOF	BUILDING	253543.9N 0850549.5E	191 FT	NIL	SECURITY HUT
25/APCH 07/TKOF	TREE	253544.3N 0850549.9E	190 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.9 M. + TRAFFIC HEIGHT 5.0 M.)
25/APCH 07/TKOF	TREE	253538.3N 0850556.4E	221 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253537.7N 0850556.9E	237 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253546.6N 0850557.2E	243 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253537.0N 0850557.8E	250 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253540.8N 0850559.3E	198 FT	NIL	Tree
25/APCH 07/TKOF	OTHER	253537.9N 0850600.3E	201 FT	NIL	PIPE ON BUILDING (BUILDING TOP 58.1 M.)

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/APCH 07/TKOF	TREE	253540.0N 0850601.4E	217 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253537.6N 0850601.7E	257 FT	NIL	GROUP OF PALM TREE
25/APCH 07/TKOF	TREE	253539.3N 0850602.9E	221 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253539.5N 0850603.2E	216 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253541.4N 0850603.3E	214 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253540.1N 0850603.6E	218 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253540.8N 0850603.8E	207 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253540.7N 0850604.1E	214 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253539.0N 0850604.4E	219 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253540.7N 0850604.5E	221 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253538.5N 0850605.0E	231 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253540.2N 0850605.0E	212 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253540.4N 0850606.3E	238 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253551.6N 0850608.7E	231 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253545.8N 0850610.2E	227 FT	NIL	TREE
25/APCH 07/TKOF	OTHER	253544.9N 0850610.2E	236 FT	NIL	CELLPHONE MAST (PORTABLE)
25/APCH 07/TKOF	TREE	253550.9N 0850610.6E	236 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253552.7N 0850607.4E	275 FT	NIL	Tree
25/APCH 07/TKOF	TREE	253556.3N 0850616.1E	242 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253554.7N 0850614.0E	247 FT	NIL	Tree
25/APCH 07/TKOF	OTHER	253544.9N 0850619.6E	232 FT	NIL	MAST
25/APCH 07/TKOF	TREE	253547.2N 0850612.0E	236 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253550.0N 0850609.4E	265 FT	NIL	LYPTUS TREE
25/APCH 07/TKOF	TREE	253543.4N 0850607.0E	235 FT	NIL	TREE
25/APCH 07/TKOF	TREE	253544.6N 0850607.3E	219 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253538.7N 0850607.4E	244 FT	NIL	TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
25/APCH 07/TKOF	TREE	253543.8N 0850604.0E	193 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	OTHER	253540.4N 0850552.8E	181 FT	NIL	APPROACH LIGHT
25/APCH 07/TKOF	TREE	253551.0N 0850624.3E	240 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253549.2N 0850624.9E	244 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253543.4N 0850606.2E	233 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253541.2N 0850605.7E	221 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	TREE	253542.7N 0850555.9E	185 FT	NIL	GROUP OF TREE
25/APCH 07/TKOF	BUILDING	253536.3N 0850554.8E	188 FT	NIL	HOUSE
25/APCH 07/TKOF	OTHER	253620.2N 0850758.5E	414 FT	NIL	MAST LIGHTED TOP
25/APCH 07/TKOF	OTHER	253620.8N 0850757.0E	404 FT	NIL	P & T MAST
25/APCH 07/TKOF	FENCE	253544.1N 0850549.5E	182 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
In circling area and at AD	BUILDING	253516.8N 0850430.4E	207 FT	NIL	PHOOLTAS FACTORY
In circling area and at AD	OTHER	253517.1N 0850437.7E	205 FT	NIL	SHED TRUSS TOP
In circling area and at AD	OTHER	253510.7N 0850440.4E	204 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.7 M. + TRAFFIC HEIGHT 7.6 M.)
In circling area and at AD	FENCE	253512.2N 0850443.3E	187 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
In circling area and at AD	POLE	253510.9N 0850441.6E	210 FT	NIL	ELECTRIC POLE
In circling area and at AD	OTHER	253511.1N 0850440.4E	203 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.4 M. + TRAFFIC HEIGHT 7.6 M.)
In circling area and at AD	POLE	253510.9N 0850440.0E	208 FT	NIL	RAILWAY ELECTRIC POLE
In circling area and at AD	OTHER	253511.3N 0850445.3E	204 FT	NIL	MOBILE RAIL TRAFFIC (RAIL TRACK ELEVATION 54.6 M. + TRAFFIC HEIGHT 7.6 M.)
In circling area and at AD	POLE	253511.8N 0850446.3E	209 FT	NIL	LIGHT POLE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	POLE	253511.7N 0850445.2E	210 FT	NIL	RAILWAY ELECTRIC POLE
In circling area and at AD	POLE	253511.5N 0850444.1E	210 FT	NIL	RAILWAY ELECTRIC POLE
In circling area and at AD	POLE	253511.3N 0850442.0E	210 FT	NIL	RAILWAY LIGHT POLE
In circling area and at AD	POLE	253511.4N 0850443.0E	210 FT	NIL	POLE
In circling area and at AD	POLE	253512.0N 0850448.8E	208 FT	NIL	ELECTRIC POLE
In circling area and at AD	TREE	253520.5N 0850432.5E	248 FT	NIL	PALM TREE
In circling area and at AD	OTHER	253521.7N 0850454.1E	196 FT	NIL	WDI LGT TOP (WDI TOP 57.3 M.)
In circling area and at AD	OTHER	253512.5N 0850452.4E	214 FT	NIL	RAILWAY FOOTOVER BRIDGE
In circling area and at AD	TREE	253510.7N 0850446.1E	227 FT	NIL	GROUP OF TREE
In circling area and at AD	OTHER	253513.0N 0850444.8E	195 FT	NIL	SECURITY HUT LIGHTED TOP (HUT TOP 58.9 M.)
In circling area and at AD	BUILDING	253507.9N 0850444.2E	222 FT	NIL	BUILDING
In circling area and at AD	OTHER	253456.4N 0850422.1E	288 FT	NIL	CELLPHONE MAST
In circling area and at AD	BUILDING	253516.3N 0850427.3E	219 FT	NIL	PHOOLTAS FACTORY TRUSS TOP
In circling area and at AD	OTHER	253510.4N 0850449.0E	247 FT	NIL	FLOOD LIGHT MAST (L)
In circling area and at AD	BUILDING	253506.6N 0850440.9E	223 FT	NIL	SINTEX TANK ON BUILDING
In circling area and at AD	TREE	253522.2N 0850439.0E	266 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253518.1N 0850425.1E	246 FT	NIL	GROUP OF TREE
In circling area and at AD	BUILDING	253514.8N 0850420.8E	212 FT	NIL	SINTEX TANK ON BUILDING
In circling area and at AD	TREE	253518.0N 0850433.7E	235 FT	NIL	TREE
In circling area and at AD	BUILDING	253508.4N 0850442.7E	226 FT	NIL	SINTEX TANK ON BUILDING (BUILDING. TOP 67.5 M.)
In circling area and at AD	BUILDING	253508.8N 0850445.3E	233 FT	NIL	BUILDING
In circling area and at AD	BUILDING	253509.3N 0850442.9E	208 FT	NIL	TEMPLE
In circling area and at AD	BUILDING	253509.4N 0850448.0E	219 FT	NIL	BUILDING
In circling area and at AD	TREE	253510.4N 0850452.6E	238 FT	NIL	GROUP OF TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	253510.9N 0850450.5E	229 FT	NIL	RAILWAY MAST ON BUILDING
In circling area and at AD	BUILDING	253508.1N 0850440.1E	224 FT	NIL	SINTEX TANK ON BUILDING (BUILDING. TOP 67.3 M.)
In circling area and at AD	TREE	253526.4N 0850449.9E	247 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253517.1N 0850437.8E	220 FT	NIL	GROUP OF TREE
In circling area and at AD	OTHER	253514.7N 0850458.6E	193 FT	NIL	SECURITY HUT LIGHTED TOP(HUT TOP 58.6 M.)
In circling area and at AD	TREE	253513.1N 0850448.6E	220 FT	NIL	Group of trees
In circling area and at AD	TREE	253513.5N 0850454.2E	210 FT	NIL	TREE
In circling area and at AD	TREE	253512.4N 0850445.7E	213 FT	NIL	TREE
In circling area and at AD	FENCE	253514.2N 0850454.9E	188 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
In circling area and at AD	TREE	253520.9N 0850438.4E	240 FT	NIL	Tree
In circling area and at AD	TREE	253515.7N 0850424.4E	228 FT	NIL	TREE
In circling area and at AD	OTHER	253456.4N 0850422.1E	285 FT	NIL	CELLPHONE MAST
In circling area and at AD	BUILDING	253518.7N 0850434.4E	201 FT	NIL	BUILDING
In circling area and at AD	OTHER	253511.0N 0850449.6E	221 FT	NIL	MAST
In circling area and at AD	POLE	253512.9N 0850455.3E	213 FT	NIL	ELECTRIC POLE
In circling area and at AD	POLE	253513.2N 0850446.3E	197 FT	NIL	LIGHT POLE
In circling area and at AD	BUILDING	253520.0N 0850437.0E	215 FT	NIL	BUILDING
In circling area and at AD	OTHER	253516.8N 0850427.6E	219 FT	NIL	SPEED CRFT.SHED
In circling area and at AD	BUILDING	253517.4N 0850437.6E	204 FT	NIL	BUILDING
In circling area and at AD	TREE	253519.0N 0850432.6E	220 FT	NIL	TREE
In circling area and at AD	TREE	253526.4N 0850448.3E	259 FT	NIL	LYPTUS TREE
In circling area and at AD	POLE	253511.3N 0850448.6E	208 FT	NIL	POLE
In circling area and at AD	POLE	253511.9N 0850447.4E	210 FT	NIL	RAILWAY ELECTRIC POLE
In circling area and at AD	POLE	253512.1N 0850446.3E	203 FT	NIL	POLE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	BUILDING	253509.4N 0850446.3E	217 FT	NIL	BUILDING
In circling area and at AD	BUILDING	253508.7N 0850446.6E	221 FT	NIL	SINTEX TANK ON BUILDING (BUILDING. TOP 66.8 M.)
In circling area and at AD	BUILDING	253506.4N 0850437.2E	222 FT	NIL	SINTEX TANK ON BUILDING (BUILDING. TOP 67.1 M.)
In circling area and at AD	BUILDING	253507.4N 0850439.3E	226 FT	NIL	SINTEX TANK ON BUILDING (BUILDING. TOP 68.0 M.)
In circling area and at AD	OTHER	253507.7N 0850439.9E	235 FT	NIL	FLAG ON BUILDING (BUILDING. TOP 68.3 M.)
In circling area and at AD	BUILDING	253508.6N 0850442.0E	217 FT	NIL	BUILDING
In circling area and at AD	BUILDING	253508.3N 0850440.5E	221 FT	NIL	BUILDING
In circling area and at AD	POLE	253511.6N 0850441.8E	204 FT	NIL	POLE
In circling area and at AD	FENCE	253511.4N 0850440.7E	188 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING ON TOP
In circling area and at AD	POLE	253511.3N 0850440.4E	204 FT	NIL	POLE
In circling area and at AD	BUILDING	253504.0N 0850432.9E	228 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 68.3 M.)
In circling area and at AD	BUILDING	253502.7N 0850431.6E	231 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 69.3 M.)
In circling area and at AD	FENCE	253517.1N 0850438.4E	187 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
In circling area and at AD	BUILDING	253502.8N 0850429.8E	225 FT	NIL	BUILDING
In circling area and at AD	BUILDING	253502.1N 0850428.4E	221 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 66.1 M.)
In circling area and at AD	BUILDING	253501.9N 0850428.0E	218 FT	NIL	BUILDING
In circling area and at AD	TREE	253500.6N 0850426.7E	246 FT	NIL	PALM TREE
In circling area and at AD	BUILDING	253501.6N 0850426.6E	218 FT	NIL	BUILDING
In circling area and at AD	BUILDING	253501.7N 0850425.6E	222 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 66.9 M.)

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	TREE	253515.0N 0850417.4E	226 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 68.8 M.)
In circling area and at AD	BUILDING	253500.7N 0850423.8E	224 FT	NIL	SINTEX TANK ON BUILDING (BUILDING.TOP 66.8 M.)
In circling area and at AD	BUILDING	253457.5N 0850418.5E	230 FT	NIL	BUILDING
In circling area and at AD	TREE	253518.5N 0850432.1E	245 FT	NIL	GROUP OF TREES
In circling area and at AD	POLE	253514.7N 0850458.4E	198 FT	NIL	LIGHT POLE
In circling area and at AD	BUILDING	253509.0N 0850445.0E	229 FT	NIL	Building
In circling area and at AD	BUILDING	253507.7N 0850437.0E	219 FT	NIL	BUILDING
In circling area and at AD	POLE	253511.3N 0850442.5E	208 FT	NIL	RAILWAY ELECTRIC POLE
In circling area and at AD	BUILDING	253508.0N 0850437.6E	230 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP=69.2 M.)
In circling area and at AD	BUILDING	253508.1N 0850444.1E	225 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP=67.2 M.)
In circling area and at AD	BUILDING	253510.9N 0850449.8E	210 FT	NIL	RAILWAY STATION BUILDING
In circling area and at AD	OTHER	253515.7N 0850459.2E	183 FT	NIL	COOLING PIT TOP
In circling area and at AD	BUILDING	253508.5N 0850440.3E	225 FT	NIL	WATER TANK TOP ON BUILDING
In circling area and at AD	OTHER	253508.8N 0850445.5E	234 FT	NIL	PVC PIPE TOP ON BUILDING (BUILDING ELEVATION=70.9 M)
In circling area and at AD	BUILDING	253508.8N 0850449.2E	230 FT	NIL	BUILDING
In circling area and at AD	OTHER	253511.3N 0850449.2E	224 FT	NIL	MAST
In circling area and at AD	OTHER	253512.6N 0850453.2E	207 FT	NIL	CATENARY MAST
In circling area and at AD	TREE	253526.8N 0850448.3E	259 FT	NIL	GROUP OF TREES
In circling area and at AD	TREE	253522.2N 0850438.8E	266 FT	NIL	GROUP OF TREES
In circling area and at AD	TREE	253517.1N 0850437.9E	216 FT	NIL	PIPAL TREE
In circling area and at AD	TREE	253519.3N 0850438.1E	211 FT	NIL	GROUP OF TREE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	TREE	253517.6N 0850438.4E	187 FT	NIL	LIGHT POLE
In circling area and at AD	BUILDING	253517.2N 0850438.6E	194 FT	NIL	SECURITY HUT
In circling area and at AD	POLE	253521.8N 0850441.9E	201 FT	NIL	LIGHT POLE
In circling area and at AD	TREE	253522.4N 0850443.0E	240 FT	NIL	GROUP OF TREE
In circling area and at AD	OTHER	253525.2N 0850443.1E	248 FT	NIL	MAST
In circling area and at AD	OTHER	253507.9N 0850443.7E	232 FT	NIL	CELLPHONE MAST
In circling area and at AD	POLE	253522.5N 0850443.8E	203 FT	NIL	LIGHT POLE
In circling area and at AD	POLE	253523.4N 0850446.4E	203 FT	NIL	LIGHT POLE
In circling area and at AD	TREE	253524.5N 0850446.7E	239 FT	NIL	GROUP OF TREE
In circling area and at AD	BUILDING	253522.2N 0850452.9E	182 FT	NIL	BIRD CHASER HUT
In circling area and at AD	OTHER	253506.8N 0850438.7E	232 FT	NIL	CELLPHONE MAST ON BUILDING (BUILDING TOP=65.4M.)
In circling area and at AD	OTHER	253515.0N 0850413.1E	258 FT	NIL	CELLPHONE MAST ON BUILDING (BUILDING TOP=69.0 M.)
In circling area and at AD	OTHER	253516.2N 0850425.6E	226 FT	NIL	FLOOD LIGHT MAST
In circling area and at AD	BUILDING	253504.1N 0850434.9E	236 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP=69.9 M.)
In circling area and at AD	OTHER	253437.7N 0850359.6E	325 FT	NIL	CELLPHONE MAST
In circling area and at AD	BUILDING	253534.8N 0850552.0E	198 FT	NIL	BUILDING
In circling area and at AD	OTHER	253535.7N 0850551.8E	186 FT	NIL	SECURITY HUT LIGHTED TOP(HUT TOP 56.6 M.)
In circling area and at AD	TREE	253544.9N 0850544.7E	249 FT	NIL	GROUP OF TREE
In circling area and at AD	FENCE	253535.0N 0850550.4E	182 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING TOP
In circling area and at AD	TREE	253533.6N 0850551.3E	245 FT	NIL	TREE
In circling area and at AD	TREE	253535.7N 0850555.3E	243 FT	NIL	Group of trees
In circling area and at AD	BUILDING	253537.6N 0850602.8E	198 FT	NIL	WATER TANK ON HOUSE

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	TREE	253537.7N 0850608.7E	267 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253544.8N 0850549.6E	254 FT	NIL	TREE
In circling area and at AD	TREE	253545.4N 0850550.9E	246 FT	NIL	GROUP OF TREE
In circling area and at AD	POLE	253534.4N 0850551.7E	193 FT	NIL	ELECTRIC POLE
In circling area and at AD	BUILDING	253534.0N 0850551.8E	197 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP 59.4 M.)
In circling area and at AD	BUILDING	253535.5N 0850552.4E	183 FT	NIL	HOUSE
In circling area and at AD	BUILDING	253535.5N 0850552.4E	183 FT	NIL	HOUSE
In circling area and at AD	TREE	253537.1N 0850600.5E	257 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253542.8N 0850538.7E	226 FT	NIL	TREE
In circling area and at AD	TREE	253546.4N 0850550.4E	250 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253544.2N 0850546.2E	207 FT	NIL	Tree
In circling area and at AD	OTHER	253528.1N 0850532.0E	192 FT	LGTD	Security hut LGT. Top (hut top 58.3 m.)
In circling area and at AD	TREE	253524.8N 0850533.2E	231 FT	NIL	Group of trees
In circling area and at AD	TREE	253525.9N 0850530.1E	224 FT	NIL	Group of trees
In circling area and at AD	OTHER	253539.1N 0850527.2E	224 FT	NIL	FLOOD LIGHT MAST ROD TOP (LIGHTED TOP 67.6 & MAST TOP 67.1 M.)
In circling area and at AD	TREE	253549.8N 0850550.6E	251 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253535.0N 0850600.7E	257 FT	NIL	TREE
In circling area and at AD	TREE	253527.2N 0850545.6E	255 FT	NIL	LYPTUS TREE
In circling area and at AD	OTHER	253602.6N 0850622.1E	263 FT	NIL	MAST
In circling area and at AD	TREE	253535.0N 0850604.6E	243 FT	NIL	TREE
In circling area and at AD	BUILDING	253537.8N 0850603.4E	198 FT	NIL	BUILDING
In circling area and at AD	OTHER	253538.4N 0850525.4E	224 FT	NIL	FLOOD LIGHT MAST ROD TOP (LIGHTED TOP 67.5 & MAST TOP 67.0 M.)
In circling area and at AD	SIGN	253534.1N 0850526.2E	176 FT	NIL	SIGN BOARD

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	253534.6N 0850527.8E	177 FT	NIL	LANDING T
In circling area and at AD	SIGN	253533.0N 0850528.1E	176 FT	NIL	Sign board
In circling area and at AD	OTHER	253533.2N 0850528.5E	176 FT	NIL	SIGN BOARD
In circling area and at AD	OTHER	253539.6N 0850528.8E	222 FT	NIL	FLOOD LIGHT MAST TOP (LIGHTED TOP 67.3 M.)
In circling area and at AD	SIGN	253535.1N 0850529.3E	176 FT	NIL	Sign board
In circling area and at AD	SIGN	253535.8N 0850531.1E	176 FT	NIL	SIGN BOARD
In circling area and at AD	ANTENNA	253536.8N 0850531.9E	181 FT	NIL	RVR ANTENNA
In circling area and at AD	TREE	253527.8N 0850532.2E	219 FT	NIL	GROUP OF TREE
In circling area and at AD	ANTENNA	253537.1N 0850532.9E	181 FT	NIL	RVR ANTENNA
In circling area and at AD	SIGN	253534.7N 0850532.9E	176 FT	NIL	Sign board
In circling area and at AD	TREE	253543.2N 0850534.9E	243 FT	NIL	TREE
In circling area and at AD	TREE	253528.2N 0850536.6E	206 FT	NIL	TREE
In circling area and at AD	OTHER	253545.6N 0850536.6E	268 FT	NIL	MAST ROD TOP (LIGHTED TOP 81.7 & MAST TOP 81.4 M.)
In circling area and at AD	TREE	253545.8N 0850537.3E	271 FT	NIL	TREE
In circling area and at AD	TREE	253531.9N 0850545.2E	242 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253546.8N 0850546.3E	253 FT	NIL	TREE
In circling area and at AD	TREE	253546.6N 0850547.0E	263 FT	NIL	TREE
In circling area and at AD	OTHER	253543.3N 0850547.4E	189 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 52.7 M. + TRAFFIC HEIGHT 5.0 M.)
In circling area and at AD	TREE	253546.5N 0850547.5E	249 FT	NIL	TREE
In circling area and at AD	TREE	253545.6N 0850548.4E	242 FT	NIL	TREE
In circling area and at AD	OTHER	253544.0N 0850549.2E	186 FT	NIL	MOBILE ROAD TRAFFIC (ROAD ELEVATION 51.7 M. + TRAFFIC HEIGHT 5.0 M.)
In circling area and at AD	TREE	253545.6N 0850549.2E	248 FT	NIL	Tree

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	TREE	253532.7N 0850550.8E	253 FT	NIL	Tree
In circling area and at AD	BUILDING	253533.1N 0850551.8E	207 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP 62.1 M.)
In circling area and at AD	BUILDING	253534.5N 0850552.3E	199 FT	NIL	BUILDING
In circling area and at AD	BUILDING	253533.4N 0850552.5E	209 FT	NIL	SINTEX TANK ON BUILDING (BUILDING TOP 62.9 M.)
In circling area and at AD	TREE	253535.6N 0850557.3E	260 FT	NIL	TREE
In circling area and at AD	TREE	253534.8N 0850557.4E	252 FT	NIL	TREE
In circling area and at AD	TREE	253551.2N 0850559.9E	257 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253553.2N 0850603.8E	279 FT	NIL	Tree
In circling area and at AD	BUILDING	253538.1N 0850618.6E	269 FT	NIL	TOMB ON HAJ BHAWAN
In circling area and at AD	NAVAID	253528.0N 0850533.0E	199 FT	LGTD	DVOR MONITOR ANTENNA (LGT)
In circling area and at AD	OTHER	253530.2N 0850536.1E	226 FT	NIL	LIGHTNING ARRESTER ON GP MAIN ANTENNA
In circling area and at AD	NAVAID	253530.1N 0850536.2E	195 FT	NIL	GP DME ANTENNA LIGHTED TOP
In circling area and at AD	OTHER	253531.1N 0850538.6E	189 FT	NIL	LIGHTNING ARRESTER ON GP MONITOR ANTENNA
In circling area and at AD	TREE	253527.4N 0850532.2E	219 FT	NIL	COCONUT TREE
In circling area and at AD	OTHER	253530.1N 0850535.7E	248 FT	NIL	LIGHT ON GP HUT (HUT TOP=56.2 M.)
In circling area and at AD	OTHER	253532.7N 0850546.9E	191 FT	NIL	SECURITY HUT LIGHTED TOP (HUT TOP 57.09 M.)
In circling area and at AD	ANTENNA	253537.2N 0850532.6E	207 FT	NIL	MET ANTENNA
In circling area and at AD	ANTENNA	253537.2N 0850532.3E	208 FT	NIL	MET ANTENNA
In circling area and at AD	OTHER	253542.6N 0850525.7E	278 FT	NIL	LIGHT ON NEW TERMINAL (BUILDING TOP=82.6 M.)
In circling area and at AD	OTHER	253543.5N 0850531.1E	262 FT	NIL	FLOOD LIGHT MAST

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	FENCE	253533.5N 0850546.6E	183 FT	NIL	AIRPORT BOUNDARY WALL WITH FENCING ON TOP
In circling area and at AD	OTHER	253606.2N 0850630.3E	276 FT	NIL	CELLPHONE MAST
In circling area and at AD	TREE	253533.8N 0850549.3E	219 FT	NIL	Group of trees
In circling area and at AD	TREE	253544.4N 0850542.9E	230 FT	NIL	GROUP OF TREE
In circling area and at AD	TREE	253533.3N 0850546.9E	216 FT	NIL	GROUP OF TREE
In circling area and at AD	BUILDING	253536.3N 0850552.6E	186 FT	NIL	HOUSE
In circling area and at AD	OTHER	253539.7N 0850542.0E	196 FT	NIL	LIGHT ON WDI (WDI TOP=59.3 M.)
In circling area and at AD	OTHER	253645.5N 0850706.3E	338 FT	NIL	CELLPHONE MAST
In circling area and at AD	OTHER	253536.6N 0850520.9E	220 FT	NIL	FLOOD LIGHT MAST ROD TOP (MAST TOP 67.1 M.)
In circling area and at AD	TREE	253544.9N 0850544.7E	249 FT	NIL	TREE
In circling area and at AD	TREE	253517.3N 0850506.2E	219 FT	NO	TREE
In circling area and at AD	TREE	253518.8N 0850512.0E	224 FT	NO	TREE
In circling area and at AD	TREE	253520.1N 0850513.6E	214 FT	NO	TREE
In circling area and at AD	TREE	253520.7N 0850514.9E	209 FT	NO	TREE
In circling area and at AD	SIGN	253531.4N 0850523.7E	176 FT	NO	Sign board
In circling area and at AD	SIGN	253533.4N 0850524.4E	176 FT	NO	Sign board
In circling area and at AD	TREE	253526.3N 0850528.3E	212 FT	NO	Group of trees
In circling area and at AD	OTHER	253509.2N 0850547.7E	343 FT	NO	COMMUNICATION TOWER
In circling area and at AD	ANTENNA	253519.2N 0850505.4E	210 FT	NO	MET ANTENNA
In circling area and at AD	ANTENNA	253519.5N 0850505.4E	209 FT	NO	MET ANTENNA
In circling area and at AD	BUILDING	253518.8N 0850507.6E	182 FT	NO	BIRD CHASER HUT
In circling area and at AD	ANTENNA	253529.7N 0850513.6E	208 FT	NO	MET ANTENNA
In circling area and at AD	BUILDING	253529.9N 0850514.2E	181 FT	NO	BIRD CHASER HUT
In circling area and at AD	TREE	253522.4N 0850519.5E	206 FT	NO	Group of trees

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM 08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	253532.1N 0850519.5E	179 FT	NO	OBSERVATORY
In circling area and at AD	POLE	253522.8N 0850520.1E	188 FT	NO	CAMERA POLE
In circling area and at AD	ANTENNA	253540.4N 0850521.8E	262 FT	NO	VHF ANTENNA ON ATC BUILDING
In circling area and at AD	POLE	253525.6N 0850527.3E	188 FT	NO	CAMERA POLE
In circling area and at AD	BUILDING	253526.6N 0850527.6E	180 FT	NO	BIRD CHASER HUT
In circling area and at AD	OTHER	253643.5N 0850711.4E	347 FT	NO	Mast
In circling area and at AD	OTHER	253658.4N 0850652.9E	349 FT	NO	Mast
In circling area and at AD	OTHER	253536.9N 0851015.9E	684 FT	NO	T.V TOWER TOP
In circling area and at AD	OTHER	253444.4N 0850253.8E	328 FT	LGTD	MAST LGT. TOP
In circling area and at AD	OTHER	253511.1N 0850240.9E	354 FT	NO	MICROWAVE TOWER
In circling area and at AD	OTHER	253623.0N 0850400.1E	338 FT	NO	CELLPHONE MAST
In circling area and at AD	OTHER	253606.3N 0850425.6E	347 FT	NO	CELLPHONE MAST
In circling area and at AD	OTHER	253425.4N 0850434.0E	347 FT	NO	CELLPHONE MAST
In circling area and at AD	OTHER	253403.0N 0850437.3E	346 FT	NO	CELLPHONE MAST
In circling area and at AD	OTHER	253633.3N 0850441.3E	345 FT	NO	CELLPHONE MAST
In circling area and at AD	OTHER	253358.5N 0850446.0E	341 FT	NO	CELLPHONE MAST
In circling area and at AD	OTHER	253406.4N 0850545.6E	400 FT	NO	CELLPHONE MAST
In circling area and at AD	BUILDING	253450.9N 0850633.2E	341 FT	NO	BUILDING
In circling area and at AD	OTHER	253719.8N 0850712.8E	437 FT	NIL	CELLPHONE MAST
In circling area and at AD	OTHER	253446.3N 0850407.7E	346 FT	NIL	Cellphone Mast
In circling area and at AD	TREE	253503.4N 0850437.5E	242 FT	NIL	Group of Tree

VEPT AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

1	Name of the associated meteorological office	Meteorological Centre Patna
2	Hours of service and, where applicable, the designation of the responsible meteorological office outside these hours	H24
3	Office responsible for preparation of TAFs and periods of validity and interval of issuance of the forecasts	Met Centre Patna 9,12,24 HR

4	Availability of the trend forecast for the aerodrome and interval of issuance	Trend Forecast 30Min
5	Information on how briefing and/or consultation is provided	Provided
6	Types of flight documentation supplied and language(s) used in flight documentation	Tabular form English
7	Charts and other information displayed or available for briefing or consultation	Surface, Upper Air, Satellite Imagery, T-PHI GRAM
8	Supplementary equipment available for providing information on meteorological conditions, e.g. weather radar and receiver for satellite images;	Tele printer / Telephone Transmissometer (DRISHTI) for TDZ RVR RWY 25
9	The air traffic services unit(s) provided with meteorological information	VEPT Patna ATC and ACS
10	Additional information, e.g. concerning any limitation of service.	Round the Clock Met Service

VEPT AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

Designations	TRUE Bearings	Dimensions of RWY (M)	Strength of pavement (PCR) and associated data) and surface of runway and associated stopways	Geographical coordinates for threshold and runway end
1	2	3	4	5
07	68.40 DEG	2072 x 45 M	503/F/C/W/T Asphalt	THR: 253519.10N 0850453.40E RWY END: 253539.17N 0850549.29E
25	248.40 DEG	2072 x 45 M	503/F/C/W/T Asphalt	THR: 253537.55N 0850544.80E RWY END: 253514.37N 0850440.22E

THR elevation and highest elevation of TDZ of precision APP RWY	Slope of runway and associated stopway	Dimensions of stopway (M)	Dimensions of clearway (M)	Dimensions of strips (M)
6	7	8	9	10
THR: 175.0FT TDZ: 175.0FT		NIL	NIL	2192 x 150 M
THR: 175.0FT TDZ: 175.0FT		NIL	NIL	2192 x 150 M

Dimensions of runway end safety areas	Location and description of arresting system (if any)	Existence of an obstacle-free zone	Remarks.
11	12	13	14
90M x 90M		----	All elevations in EGM08
100M x 90M		----	All elevations in EGM08.

VEPT AD 2.13 DECLARED DISTANCES

RWY Designator	Take-off run available TORA (M)	Take-off distance available TODA (M)	Accelerate distance available ASDA (M)	Landing distance available LDA (M)	Remarks (including runway entry or start point where alternative reduced declared distances have been declared)
1	2	3	4	5	6
07	2072	2072	2072	1677	THR Displaced by 395M 1:40 (Slope)
25	2072	2072	2072	1938	THR Displaced by 134M 1:40 (Slope)

VEPT AD 2.14 APPROACH AND RUNWAY LIGHTING

Runway Designator	Type, length and intensity of approach lighting system	Runway threshold lights, colour and wing bars	Type of visual slope indicator system	Length of runway touchdown zone lights
1	2	3	4	5
07	SALS 420 M LIH	Green Wing bar LGT provided for RWY 07 only	PAPI LEFT/3.00 DEG MEHT (46.85FT)	
25	SALS 420 M LIH	Green	PAPI LEFT/3.15 DEG MEHT (53.59FT)	

Length, spacing, colour and intensity of runway centre line lights	Length, spacing, colour and intensity of runway edge lights	Colour of runway end lights and wing bars	Length and colour of stopway lights	Remarks
6	7	8	9	10
	2072 M 60 M White LIH	Red		NIL
	2072 M 60 M White LIH	Red		NIL

VEPT AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Location, characteristics and hours of operation of aerodrome beacon/identification beacon (if any)	ABN	At Tower Building, FLG W&G EV2SEC As ATS HR
		IBN	NIL
2	Location and lighting (if any) of anemometer/ landing direction indicator;	LDI	Available between TWY A and TWY B
		Anemometer	NIL
3	Taxiway edge and taxiway centre line lights;	Edge	TWY A, TWY B, TWY C, TWY E and TWY F
		Centre Line	NIL
4	Secondary power supply including switch-over time;	Secondary Power supply to all lighting at AD. Switch-over time: 8 Sec	

5	Remarks	NIL

VEPT AD 2.16 HELICOPTER LANDING AREA

1	Geographical coordinates of the geometric centre of touchdown and lift-off (TLOF) or of each threshold of final approach and take-off (FATO) area	Not Established
2	TLOF and/or FATO area elevation:	Not Established
3	TLOF and FATO area dimensions to the nearest metre or foot, surface type, bearing strength and marking;	Not Established
4	True bearings of FATO;	Not Established
5	Declared distances available	Not Established
6	Approach and FATO lighting;	Not Established
7	Remarks	Not Established

VEPT AD 2.17 AIR TRAFFIC SERVICE AIRSPACE

1	Airspace designation, geographical coordinates and lateral limits	CTR: Circular area centered on 253537N 0850531E within a 15NM radius.
2	Vertical limits	FL 65
3	Airspace classification	D
4	Call sign and language(s) of the air traffic services unit providing service;	Patna Tower / Patna Approach, English
5	Transition altitude	4000 FT
6	Hours of applicability	H24
7	Remarks	NIL

VEPT AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service Designation	Call sign	Channel(s)	SATVOICE Number(s), if available
1	**2**	**3**	**4**
APP	Patna Approach	121.100 MHZ	
APP	Patna Approach	127.775 MHZ	
TWR	Patna Tower	118.300 MHZ	
ATIS	Patna Information	128.000 MHZ	
ALRS	PATNA EMERGENCY	121.500 MHZ	

Logon address, as appropriate	Hours of operation	Remarks
5	**6**	**7**
	H24	NIL
	H24	SDBY FREQ FOR TWR and APP
	H24	NIL
	As ATS	NIL
	H24	NIL

VEPT AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of aids, magnetic variation and type of supported operation for ILS/ MLS, basic GNSS, SBAS and GBAS, and for VOR/ILS/MLS station used for technical lineup of the aid	Identification	Frequency(ies), Channel number(s), Service provider, and reference path identifier(s) (RPI), as appropriate	Hours of operation, as appropriate;
1	2	3	4
LOC 25 CAT I	IPAT	110.300 MHz	H24
GP 25		335.000 MHz	H24
DME ILS 25	IPAT	CH40X	H24
DVOR/DME	PPT	112.100 MHz CH58X	H24

Geographical coordinates of the position of the transmitting antenna	Elevation of transmitting antenna of DME/ elevation of GBAS reference point	Service volume radius from the GBAS reference point	Remarks
5	6	7	8
253512.1N 0850433.9E			
253530.2N 0850536.1E			1. GP RESTRICTED AT 8NM, 1500FEET HAT (HEIGHT ABOVE TRESHOLD) 2. Glide Angle: 3.15 DEG
253530.2N 0850536.1E	194 FT		1. Collocated with GP25. 2. Elevations in EGM08
253526.4N 0850536.1E	202 FT		Vertical datum: EGM08

VEPT AD 2.20 LOCAL AERODROME REGULATIONS

• No Aircraft shall take lock turn/ pivotal turn on the Runway to avoid pavement damage.

VEPT AD 2.21 NOISE ABATEMENT PROCEDURES

NIL

VEPT AD 2.22 FLIGHT PROCEDURES

1.Opportunity basis ADS-B based APP surveillance SER provided with jurisdiction of Patna APP to suitably equipped acft withe coverage area of Patna ADS-B sensor.

2. ADS-B equipped aircraft flying within the jurisdiction of Patna Approach Control to comply with relevant provisions.

VEPT AD 2.23 ADDITIONAL INFORMATION

I. LOW VISIBILITY PROCEDURE

1. BACKGROUND:

Until the latest amendment of DGCA Civil Aviation Requirements (CAR) section 8, Series 'C', Part-I on All-weather Operations, Low visibility procedures were required at aerodromes for the purpose of ensuring safe operations during Categories II and III approaches and/or low visibility take-offs(LVTO).
However, in latest amendment to CAR (Rev. 10) para 5.3 following provision regarding Low Visibility Procedures is added.
"Quote" **An operator shall not conduct take-off with RVR/visibility less than standard Category I conditions of 550m RVR/ 800 m visibility unless low visibility procedures are enforced.** "Unquote".
This provision necessitated the need of Low Visibility Procedures for accommodating/permitting departures in Visibility/RVR less than 800M/550M even at such airports where there are No CAT II and CAT III operations.
Accordingly, Low visibility Procedures have been developed for Jai Prakash International Airport, Patna to accommodate/ permit departures in Visibility/RVR less than 800M/550M from RWY 07 & 25. (both RWY 07/25 served with RVR instruments vide eAIP GEN 3.5 VEPT).

2. DEFINITIONS:

2.1 Low Visibility Procedures (LVP): Specific procedures applied at an aerodrome for the purpose of ensuring safe operations during Categories II and III approaches and/or low visibility take-offs.

Note: as per para 5.3 of CAR on All Weather Operations, an operator shall not conduct Take-off with RVR/Visibility less than standard CAT-I conditions of 550m RVR/800m Visibility unless low visibility procedures are enforced.

2.2 Manoeuvring Area: That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.

2.3 Runway Visual Range: The range over which the pilot of an aircraft on the centerline of a runway can see the runway surface markings or the lights delineating the runway or identifying its centerline.

2.4 Aerodrome Operating Minima: The limits of usability of an aerodrome for:

a. Take off, expressed in terms of runway visual range and / or visibility and, if necessary, cloud conditions.
b. landing in 2 D instrument approach operations, expressed in terms of visibility and/or runway visual range; minimum descent altitude/height (MDA/H) and, if necessary, cloud conditions; and
c. landing in 3D instrument approach operations, expressed in terms of visibility and/or runway visual range and decision altitude/height(DA/H) appropriate to the type and/or category of the operation.

2.5 Visibility - Visibility for aeronautical purposes is the greater of:
a. the greatest distance at which a black object of suitable dimensions, situated\ near the ground, can be seen and recognized when observed against a bright background;
b. The greatest distance at which lights in the vicinity of 1 000 candelas can be seen and identified against an unlit background.

Note 1. — The two distances have different values in air of a given extinction coefficient, and the latter b) varies with the background illumination. The former a) is represented by the meteorological optical range (MOR).

Note 2. — The definition applies to the observations of visibility in local routine and special reports, to the observations of prevailing and minimum visibility reported in METAR and SPECI and to the observations of ground visibility.

3. GENERAL:

The Low Visibility Procedure (LVP) incorporates safeguarding measures to mitigate runway incursions and defines operational restrictions to ensure safe Airside Operations taking into account the available Aerodrome facilities.

Refer eAIP GEN 3.5 VEPT; at Patna:

a) DCWIS (Digital Current Weather Indication System) at RWY 07 and 25;
b) Drishti Transmissometer at RWY 25; and
c) FSM (Forward Scatter Meter) at RWY 07 and 25

4. MINIMUM REQUIREMENTS:

The following aeronautical Ground lights and RVR equipment shall be serviceable to the required standard to support Low Visibility Procedures.
a. Runway edge lights,
b. Runway end lights,
c. Real time TDZ RVR.
d. Stand by Power supply to maintain switch over time of 1 Second for Runway Edge Lights and Runway End Lights. This requirement can be met with thehelp of DG Set and/or UPS.
Note: - At Patna switch over time for Runway Edge Lights and Runway End Lights is less than 1 Second.

5. UNSERVICEABILITY OF AERONAUTICAL GROUND LIGHTS/EQUIPMENT BEFORE IMPLEMENTATION OF LVP.
Low Visibility Procedures will not be implemented when any of the light/equipment mentioned in para 4 above is un-serviceable or is not maintained as per the required standard.

5.1 Unserviceability of Aeronautical Ground Lights/ Equipment after Implementation of LVP.
When any of the light/equipment mentioned in para 4 above becomes un-serviceable or fails to meet the required standard during periods of LVP, TWR/SMC shall advise the aircraft accordingly and LVP shall be suspended and information to this effect shall be included in ATIS broadcast.

6. SAFEGUARDING PROCEDURES:

Safeguarding Procedures (SP) are instructions for relevant airport, departments and airside operators to prepare ground services and facilities for low visibility operations in order that when LVP are implemented all Safeguarding procedures are complete.
Duty Officer Tower/Tower Supervisor will initiate and co-coordinate with all the concerned agencies for completion of safeguarding procedures before implementation of Low Visibility Procedures.

6.1 Safeguarding Procedures shall be initiated when:
a. The Visibility/RVR is less than 1200m and visibility/RVR is forecast to deteriorate to 800m or less; and/or
b. The cloud ceiling is less than 400ft and forecast to fall to 200ft or less.

6.2 Safeguarding procedures include:
a. Positioning of 1 CFT each at the two predetermined positions, i.e. when Runway in use:

i. **RWY 07** - 1 CFT at Holding Point of Fire Approach Road and 1 CFT at Holding Point at Road Holding Position Near DUMBBELL RWY 25'; and
ii. **RWY 25** - 1 CFT at Holding Point of Fire Approach Road and 1 CFT at Holding Point at Fire - Pit Approach Road.

b. Stopping of all maintenance works on the manoeuvring area as well as removal of all men and mobile equipment from the said area.
c. Ensuring availability of secondary power supply for change over time of maximum one second for RWY Edge and Rwy End lights supported by UPS.

Note: RWY Edge and Rwy End lights may continue to operate on main power supply during safe Guarding Procedures. Whenever, LVP is to be implemented as per para 6 below, the RWY Edge and Rwy End lights shall be put on Standby Power Supply (DG set or UPS). This operation need to be completed before LVP is implemented.
In case of DG set, Main power supply shall act as stand by power. At airports where UPS is capable of maintaining the required AGL system with one second of Switch Over time with Main Supply, the main supply can continue to be primary supply and the Generator Supply can be kept as Stand by Power supply.

d. The appropriate Aeronautical ground lights must have been inspected during the hour preceding implementation of LVP, and thereafter once every two-hour period. These lighting inspections should be accorded priority and, if necessary, aircraft operations may be delayed.

7. Low Visibility Procedures:

7.1 Implementation of Low Visibility Procedures:

Duty MET Officer shall inform Tower Supervisor whenever Visibility/RVR reduces to 800 Meters or below and/ or cloud ceiling is at 200 ft or below. Tower Supervisor shall coordinate with all the agencies to confirm whether the Safeguarding procedures have been completed or not. When Visibility/RVR falls below 800m/550M and or Cloud Ceiling is 200 ft or below and safeguarding procedures are complete, Tower supervisor will implement Low Visibility Procedures. Duty Officer Tower/ Tower Supervisor shall inform all users of the imposition of low visibility procedures.

7.2 Action by various units during LVP:

a. Duty MET Officer shall keep Duty Officer Tower/Tower Supervisor informed of any change in Visibility/ RVR.
b. TOWER/ OPS shall ensure that the towing of aircraft is done under escort of "Follow Me" vehicles. "Follow Me" shall inform ATC of any deviation fromthe route cleared by ATC;
c. Tower shall not permit any ground run on the manoeuvring area except idle power run on the stands;
d. Tower shall ensure that "Follow Me" services are provided to pilots on request;
e. The number of the vehicles on the manoeuvring area shall be restricted to bare minimum and records of all operating on the manoeuvring area shall be maintained by TOWER / OPS.
f. The following may be included in DATIS. "Low Visibility Procedures in force".
g. TWR shall permit departures only from the beginning of the Runway in use.
h. Whenever visibility/RVR is less than 800M/550M, Duty officer tower shal confirm from pilot that the reported RVR value is within minima before issuing take-off clearance.
i. Duty officer Tower shall take the Take-off Alternate from pilot before issuing take-off clearence.
j. In-Charge Electrical shall continuously monitor the main and Standby Power supply to ensure change over time of maximum one second for RWY Edge and Rwy End lights during low visibility operations and report any unserviceability to Tower immediately.

8. TERMINATION OF LOW VISIBILITY PROCEDURES:

a. When Visibility/RVR improves to 800M or more and cloud ceiling is 200 feet or Higher and trend is for improvement, Tower Supervisor/Duty Officer Tower would terminate operations of LVP. He may obtain advice from Duty Met. Officer regarding improvement in weather conditions before the termination of LVP.
b. The Tower Supervisor will intimate OPS/ARFF/ In-Charge ElectricalEngineering regarding the termination of LVP operations.
c. On cancelling of LVP, following message shall be included in two subsequent ATIS broadcasts. “LOW VISIBILITY PROCEDURES CANCELLED”.
d. If SP are implemented and LVP are not subsequently implemented and the visibility/RVR improves and is more than 1200m and/or the cloud ceiling is 400ft or higher and both are forecast to remain above the required SP criteria, Tower Supervisor/ Duty Officer Tower may cancel SP.

9. ACTIONS BY OTHER AGENCIES (AIRLINES, REFUELING COMPANIES, CATERING AGENCIES, ETC.):

a. Every Year before commencement of monsoon/winter season, a meeting will be held by Airport Director, to inform all airlines and agencies operating at airport about their roles/responsibilities and create awareness to ensure cooperation for safe airport operations during periods of low visibility.
b. All the agencies shall ensure that staff and drivers are suitably trained during Low Visibility operations.
c. A refresher program for ATCO’s and personnel responsible for airside operations shall be conducted every year.
d. All agencies operating in the operational area shall ensure that only those vehicles that are absolutely essential for aircraft operations operate in the operational area during periods of low visibility. The drivers of these vehicles should keep a look out for taxiing aircraft and other vehicles to prevent accidents.
e. All the vehicles must have their obstruction lights “ON” during Low Visibility Procedures operations.
f. Everybody must follow all instructions/sign boards provided for vehicular movement area/service roads.

II. ADS-B Ground receiver is commissioned and operational.

III. Bird activity observed in and around airfield.Pilots to exercise caution while landing and takeoff.

IV. Exemption granted by DGCA:Tempo exemption granted by DGCA india for non compliant width of rwy strip against provisions in CAR sec 4 series B part 1 para 3.4.3 till 4 apr 2027.

VEPT AD 2.24 CHARTS RELATED TO AN AERODROME

1. Aerodrome Chart (29 OCT 2026)
2. Aircraft Parking/Docking chart (29 OCT 2026)
3. Aerodrome Obstacle Chart Type - A, (Operating Limitations) RWY 07(11 June 2026)
4. Aerodrome Obstacle Chart Type - A, (Operating Limitations) RWY 25(11 June 2026)
5. Aerodrome Obstacle Chart Type - B(11 June 2026)
6. Instrument Approach Chart - ILS or LOC Procedure RWY 25 (CAT A/B/C) (13 June 2024)
7. Instrument Approach Chart - VOR Procedure RWY 07
8. ATC Surveillance Minimum Altitude Chart
9. Instrument Approach Chart - RNP Y Procedure RWY 07
10. Coding Table - RNP Y Procedure RWY 07
11. Instrument Approach Chart - RNP Y Procedure RWY 25
12. Coding Table - RNP Y Procedure RWY 25

VEPT AD 2.25 VISUAL SEGMENT SURFACE (VSS) PENETRATION

Procedure	Procedure Minima	VSS Penetration
1	2	3

RNP Y RWY 25	LNAV/VNAV OCA(OCH)=560(385), LNAV OCA(OCH)=780(605)	**OBST: GROUP OF TREE** LCA:253544.1860N 0850552.9580E ELEV:75.0M **OBST: GROUP OF TREE** LCA:253543.2780N 0850600.7660E ELEV:78.6M **OBST: GROUP OF TREE** LCA:253543.6820N 0850553.3070E ELEV:72.3M **OBST: TREE** LCA:253544.9206N 0850554.9430E ELEV:73.6M **OBST: GROUP OF TREE** LCA:253545.8720N 0850557.5880E ELEV:75.0M **OBST: GROUP OF TREE** LCA:253546.6560N 0850558.6350E ELEV:74.8M **OBST: TREE** LCA:253547.3083N 0850559.1708E ELEV:75.0M **OBST: GROUP OF TREE** LCA:253544.8170N 0850556.0210E ELEV:70.9M **OBST: GROUP OF TREE** LCA:253554.4280N 0850612.4220E ELEV:87.5M **OBST: TREE** LCA:253542.3580N 0850600.5400E ELEV:73.2M **OBST: TREE** LCA:253538.4640N 0850557.7975E ELEV:69.4M **OBST: GROUP OF TREE** LCA:253549.3316N 0850605.4184E ELEV:78.4M **OBST: GROUP OF TREE** LCA:253540.5390N 0850608.6170E ELEV:76.0M **OBST: LYPTUS TREE** LCA:253549.9654N 0850609.4228E ELEV:79.6M **OBST: GROUP OF TREE** LCA:253547.5680N 0850601.4040E ELEV:70.9M **OBST: TREE** LCA:253548.5544N 0850604.2141E ELEV:73.4M **OBST: GROUP OF TREE** LCA:253540.1260N 0850606.4910E ELEV:71.9M **OBST: TREE** LCA:253540.3476N 0850606.2802E ELEV:71.0M **OBST: GROUP OF TREE** LCA:253550.3440N 0850605.7700E ELEV:73.8M **OBST: MAST** LCA:253559.0000N 0850623.0000E ELEV:90.0M