AD 2. AERODROMES

VAUD AD 2.1 AERODROME LOCATION INDICATOR AND NAME

VAUD - MAHARANA PRATAP AIRPORT, UDAIPUR

VAUD AD 2.2 AERODROME GEOGRAPHICAL AND ADMINISTRATIVE DATA

1	Aerodrome reference point coordinates and its site	243706N 0735334E M. Brg. 73.05 DEG / 1034 M from Physical beginning of RWY 08	
2	Direction and distance of aerodrome reference point from the center of the city or town which the aerodrome serves	075 DEG/20 KM from Udaipur City Railway Station.	
3	Aerodrome elevation and reference temperature	1690 FT / 39.0 DEG C	
4	Magnetic variation, date of information and annual change	0.00 DEG (2010) /0.033 DEG E	
5	Name of aerodrome operator, address, telephone, telefax, e-mail address, AFS address, website (if available)	Airport Director, Airports Authority of India, Maharana Pratap Airport, Udaipur -313022.,	
		Telephone:	(91) 294-2655950 (91) 9414159950 (91) 294-2655279 (91) 9414159962
		Fax:	(91) 294-2655953 (91) 294-2655279
		AFS:	Airport Director: VAUDYHYX Air Traffic Services: VAUDZTZX
		Email:	Airport Director: apdvaud@aai.aero Air Traffic Services: vaud_atc@aai.aero
6	Types of traffic permitted (IFR/VFR)	IFR/VFR	
7	Remarks	Gravity Model: EGM-08	

VAUD AD 2.3 OPERATIONAL HOURS

1	Aerodrome Operator	MON-FRI 0400-1230 UTC (0930-1800 IST) SAT, SUN+ HOL: NIL
2	Custom and immigration	NIL
3	Health and sanitation	Provided as per ATS
4	AIS briefing office	As ATS
5	ATS reporting office (ARO)	As ATS
6	MET Briefing office	As ATS
7	Air Traffic Service	Consult NOTAM for current ATS HR.
8	Fuelling	As ATS
9	Handling	As ATS
10	Security	H24
11	De-icing	NIL
12	Remarks	1.Outside of ATS HRS, services are available on request with 24 HR prior notice to Airport Director. 2.The approved hourly RWY traffic handling capacity is as follows: Maximum number of arrivals and departures: 12 Maximum number of arrival only: 06 Maximum number of departures only: 10

VAUD AD 2.4 HANDLING SERVICES AND FACILITIES

1	Cargo-handling facilities	Available
2	Fuel and Oil types	JET A1 JET A1 (ATF)
3	Fuelling facilities and capacity	IOCL: 3 Bowsers -16000 Liters each, 20 Litres/sec Reliance: 2 Bowsers -16000 Liters each, 700 Liters/min 2 Bowsers -11000 Liters each, 600 Liters/min
4	De-icing facilities	NIL
5	Hangar space for visiting aircraft	Nil
6	Repair facilities for visiting aircraft	Nil
7	Remarks	Two hangers: One with NCC and other AAI Hanger with A R Airways (on lease).

VAUD AD 2.5 PASSENGER FACILITIES

1	Hotel(s) at or in the vicinity of aerodrome	Near the AD
2	Restaurant(s) at or in the vicinity of aerodrome	Near the AD
3	Transportation possibilities	Taxis and car hire from the AD.
4	Medical Facilities	MI Room at AD, Hospitals in the city.
5	Bank and post office at or in the vicinity of aerodrome	Banks: SBI & BOB Bank Post office: A post drop box is available outside Terminal Building.
6	Tourist office	At Aerodrome
7	Remarks	NIL

VAUD AD 2.6 RESCUE AND FIRE FIGHTING SERVICES

1	Aerodrome category for fire fighting	Within ATS HR: CAT-7
2	Rescue equipment	Available as per category.
3	Capability for removal of disabled aircraft	1. The critical aircraft for the airport is A321. 2. Primary responsibility for removal of disabled aircraft rests with the concerned airline. 3. The airlines may contact 'Aerodrome Coordinator for Disabled Aircraft Removal Operations' for coordinating with the agencies having Disabled Aircraft Recovery Kit. 4. Contact Details of Aerodrome Coordinator for Disabled Aircraft Removal Operations: Airport Director Contact No.: 9414159950, 0294-2655950, 0294-267735-38 Ext. 111 0294-2655953 (Fax) email: apdvaud@aai.aero
4	Remarks	NIL

VAUD AD 2.7 SEASONAL AVAILABILITY CLEARING

1	Type(s) of clearing equipment	NIL
2	Clearance priorities	NIL
3	Remarks	NIL

VAUD AD 2.8 APRONS, TAXIWAYS AND CHECK LOCATIONS/POSITIONS DATA

1	Designation, surface and strength of aprons	Refer Aircraft Parking/Docking Chart.
2	Designation, width, surface and strength of taxiways	Refer Aircraft Parking/Docking Chart.
3	Location and elevation of altimeter checkpoints	On Apron I: 1674 FT On Apron II: 1676 FT
4	Location of VOR checkpoints	Available on TWY B and TWY F
5	Position of INS checkpoints	Nil
6	Remarks	1. Isolated Aircraft Parking Position: With shoulders 7.5 on each side. Location: 193M North of RWY 08/26 at a distance of 2525M from beginning of RWY 08. Elevation of the highest point 507.782M 2. Coordinates of Runway Holding Positions: i. TWY A: 243703.276N 0735324.382E, ELEV:1674 FT ii. TWY B: 243703.957N 0735329.344E, ELEV:1674 FT iii. TWY C: 243706.015N 0735344.541E, ELEV:1672 FT iv. TWY D: 243711.738N 0735426.854E, ELEV:1664 FT v. TWY E: 243701.846N 0735313.851E, ELEV:1679 FT vi. TWY F: 243702.689N 0735320.058E, ELEV:1676 FT 3. Coordinates of Runway-Taxiway Intersection Points: i. TWY A:243700.313N 0735324.853E, ELEV:1677 FT ii. TWY B: 243700.985N 0735329.805E, ELEV:1676 FT iii. TWY C: 243703.050N 0735344.993E, ELEV:1674 FT iv. TWY D: 243708.785N 0735427.341E, ELEV:1665 FT v. TWY E: 243658.880N 0735314.403E, ELEV:1682 FT vi. TWY F: 243659.728N 0735320.540E, ELEV:1679 FT 4. Gravity Model: EGM-08

VAUD AD 2.9 SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM AND MARKINGS

1	Use of aircraft stand identification signs, taxiway guidelines and visual docking/parking guidance system at aircraft stands	All stands are provided with stand identification signs. Nose-wheel guide lines at apron. Taxing guidance signage's are provided on all TWY as per ICAO Annex-14. Visual Docking and Guidance System provided for Bay No. 2 & Bay No.3
2	Runway and taxiway markings and lights	RWY Markings: Designation, THR, TDZ, Centreline, Aiming point, edge. RWY Lights: THR, EDGE and RWY END TWY Marking: Centreline, Holding Position, Edge. TWY Lights: Edge.
3	Stop bars (if any)	Nil

4	Remarks	1. Medium Intensity Apron and TWY Edge Lights 2. RWY Guard LGT provided on TWY A,B,E and F

VAUD AD 2.10 AERODROME OBSTACLES

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
26/TKOF 08/APCH	POLE	243650.8N 0735246.0E	1725 FT	NO	Electric Pole
26/TKOF 08/APCH	TREE	243650.9N 0735252.6E	1746 FT	NO	Group Of Trees
26/TKOF 08/APCH	POLE	243650.5N 0735249.1E	1722 FT	NO	Electric Pole
26/TKOF 08/APCH	FENCE	243651.3N 0735249.6E	1708 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	FENCE	243655.8N 0735249.0E	1717 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	OTHER	243655.2N 0735249.4E	1719 FT	NO	Mobile Road Traffic (Road Elev. 518.8 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243655.2N 0735248.9E	1721 FT	NO	Mobile Road Traffic (Road Elev. 519.7 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	FENCE	243657.4N 0735248.8E	1719 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	OTHER	243659.5N 0735248.6E	1720 FT	NO	Security Hut
26/TKOF 08/APCH	OTHER	243700.0N 0735248.7E	1720 FT	NO	Crash Gate
26/TKOF 08/APCH	OTHER	243659.8N 0735249.0E	1727 FT	NO	Mobile Road Traffic (Road Elev. 521.4 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	POLE	243659.4N 0735244.7E	1733 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243700.6N 0735242.6E	1734 FT	NO	Electric Pole
26/TKOF 08/APCH	FENCE	243700.7N 0735252.8E	1710 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	OTHER	243658.6N 0735253.0E	1709 FT	NO	Localizer Hut
26/TKOF 08/APCH	ANTENNA	243658.9N 0735252.8E	1722 FT	LGTD	Antenna Top on LLZ Hut (LGT)
26/TKOF 08/APCH	OTHER	243656.2N 0735254.1E	1707 FT	NO	Localizer Antenna Rod Top (Antenna Top 518.8 M.)
26/TKOF 08/APCH	OTHER	243656.5N 0735254.1E	1707 FT	NO	Localizer Antenna (Light Top)
26/TKOF 08/APCH	OTHER	243654.4N 0735255.1E	1702 FT	NO	Spot Level
26/TKOF 08/APCH	TREE	243700.3N 0735238.8E	1757 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243657.1N 0735233.8E	1755 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243654.8N 0735232.9E	1753 FT	NO	Group of Trees

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
26/TKOF 08/APCH	TREE	243656.1N 0735226.5E	1767 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243651.0N 0735234.4E	1757 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243648.6N 0735223.4E	1753 FT	NO	Group of Trees
26/TKOF 08/APCH	POLE	243652.7N 0735236.7E	1738 FT	NO	Electric Pole
26/TKOF 08/APCH	TREE	243654.5N 0735236.4E	1748 FT	NO	Group of Trees
26/TKOF 08/APCH	POLE	243656.2N 0735236.8E	1735 FT	NO	Electric Pole
26/TKOF 08/APCH	OTHER	243656.3N 0735236.6E	1726 FT	NO	Mobile Road Traffic (Road Elev. 521.1 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	POLE	243659.2N 0735237.1E	1736 FT	NO	Electric Pole
26/TKOF 08/APCH	OTHER	243655.9N 0735252.2E	1705 FT	NO	Spot Level
26/TKOF 08/APCH	OTHER	243504.7N 0734623.3E	2365 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243547.7N 0734502.9E	2418 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243634.1N 0734451.2E	2518 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243606.9N 0734616.8E	2323 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243616.7N 0734611.4E	2273 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243638.5N 0734959.3E	2101 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243627.9N 0735011.0E	1985 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243632.9N 0734812.2E	2523 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243559.4N 0734829.0E	2541 FT	NO	Solar Light on Hill Top
26/TKOF 08/APCH	POLE	243655.1N 0735245.5E	1728 FT	NO	Electric Pole
26/TKOF 08/APCH	OTHER	243645.5N 0734957.4E	2093 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243652.0N 0735257.0E	1714 FT	NO	Mobile Road Traffic (Road Elev. 517.4 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	FENCE	243651.8N 0735256.6E	1710 FT	NO	Fence Top
26/TKOF 08/APCH	OTHER	243651.6N 0735255.7E	1717 FT	NO	Mobile Road Traffic (Road Elev. 518.3 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243656.4N 0735256.3E	1691 FT	NO	Ground Level
26/TKOF 08/APCH	OTHER	243656.3N 0735255.3E	1692 FT	NO	Ground Level

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
26/TKOF 08/APCH	OTHER	243655.7N 0735254.2E	1707 FT	NO	L/C Rod Near Localizer
26/TKOF 08/APCH	OTHER	243700.8N 0735254.5E	1707 FT	NO	Mobile Road Traffic (Road Elev. 515.3 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	FENCE	243700.9N 0735255.2E	1705 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	OTHER	243700.9N 0735255.6E	1704 FT	NO	Mobile Road Traffic (Road Elev. 514.3 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243700.3N 0735251.5E	1718 FT	NO	Mobile Road Traffic (Road Elev. 518.5 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243651.2N 0735250.7E	1715 FT	NO	Mobile Road Traffic (Road Elev. 517.6 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	FENCE	243700.1N 0735249.2E	1722 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	POLE	243700.2N 0735248.1E	1728 FT	NO	Solar Light
26/TKOF 08/APCH	OTHER	243659.6N 0735248.4E	1727 FT	NO	Mobile Road Traffic (Road Elev. 521.5 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243659.6N 0735248.8E	1727 FT	NO	Mobile Road Traffic (Road Elev. 521.4 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243655.5N 0735249.2E	1721 FT	NO	Mobile Road Traffic (Road Elev. 519.6 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	FENCE	243655.5N 0735249.1E	1715 FT	NO	Airport Boundary Wall With F/T
26/TKOF 08/APCH	OTHER	243655.4N 0735249.0E	1722 FT	NO	Mobile Road Traffic (Road Elev. 520.0 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	OTHER	243651.7N 0735249.5E	1716 FT	NO	Mobile Road Traffic (Road Elev. 518.1 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	POLE	243652.6N 0735245.9E	1724 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243657.4N 0735245.1E	1731 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243700.6N 0735244.4E	1735 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243700.4N 0735241.0E	1730 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243700.2N 0735239.0E	1731 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243700.3N 0735237.0E	1732 FT	NO	Electric Pole
26/TKOF 08/APCH	OTHER	243659.7N 0735237.1E	1733 FT	NO	Mobile Road Traffic (Road Elev. 523.2 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	POLE	243657.7N 0735236.9E	1736 FT	NO	Electric Pole

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
26/TKOF 08/APCH	POLE	243654.7N 0735236.7E	1736 FT	NO	Electric Pole
26/TKOF 08/APCH	OTHER	243653.4N 0735236.6E	1729 FT	NO	Mobile Road Traffic (Road Elev. 522.0 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	POLE	243653.1N 0735236.8E	1732 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243651.8N 0735236.9E	1734 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243650.5N 0735236.8E	1734 FT	NO	Electric Pole
26/TKOF 08/APCH	POLE	243648.5N 0735236.7E	1735 FT	NO	Electric Pole
26/TKOF 08/APCH	OTHER	243646.7N 0735236.3E	1733 FT	NO	Mobile Road Traffic (Road Elev. 523.2 M + Traffic Ht. 5 M)
26/TKOF 08/APCH	TREE	243652.7N 0735234.7E	1749 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243658.7N 0735231.8E	1762 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243659.8N 0735231.7E	1751 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243700.6N 0735232.2E	1762 FT	NO	Group of Trees
26/TKOF 08/APCH	BUILDING	243659.7N 0735230.8E	1750 FT	NO	Building
26/TKOF 08/APCH	TREE	243657.2N 0735225.8E	1767 FT	NO	Group of Trees
26/TKOF 08/APCH	TREE	243656.9N 0735228.4E	1769 FT	NO	Group of Trees
26/TKOF 08/APCH	OTHER	243631.6N 0735006.6E	2010 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243632.7N 0735006.0E	2002 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243641.1N 0734959.9E	2030 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243647.3N 0734957.4E	2093 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243634.8N 0734956.8E	2040 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243648.0N 0734754.8E	2732 FT	NO	Solar Light on Hill
26/TKOF 08/APCH	OTHER	243639.3N 0734759.4E	2715 FT	NO	Hill Top
26/TKOF 08/APCH	OTHER	243640.9N 0734805.8E	2713 FT	NO	Solar Light on Hill
26/APCH 08/TKOF	TREE	243715.9N 0735443.9E	1713 FT	NO	Group of Trees
26/APCH 08/TKOF	OTHER	243718.3N 0735511.0E	1732 FT	NO	JK Cement Conveyor Belt Line
26/APCH 08/TKOF	OTHER	243719.1N 0735511.1E	1736 FT	NO	JK Cement Truss Top

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
26/APCH 08/TKOF	OTHER	243719.0N 0735511.2E	1737 FT	NO	JK Cement Level Check Point LGT Top (526.6 M Structure Top)
26/APCH 08/TKOF	OTHER	243717.9N 0735512.6E	1732 FT	NO	JK Cement Pillar Top
26/APCH 08/TKOF	TREE	243719.0N 0735516.2E	1751 FT	NO	Tree
26/APCH 08/TKOF	ANTENNA	243717.9N 0735515.1E	1745 FT	NO	Antenna on Structure (Structure Top 526 M)
26/APCH 08/TKOF	TREE	243707.2N 0735500.6E	1711 FT	NO	Group of Trees
26/APCH 08/TKOF	TREE	243710.2N 0735501.1E	1708 FT	NO	Group of Trees
26/APCH 08/TKOF	TREE	243710.2N 0735454.4E	1698 FT	NO	Group of Trees
26/APCH 08/TKOF	TREE	243706.8N 0735452.9E	1696 FT	NO	Group of Trees
26/APCH 08/TKOF	FENCE	243706.0N 0735441.3E	1679 FT	NO	Airport Boundary Wall With F/T
26/APCH 08/TKOF	OTHER	243708.5N 0735441.0E	1671 FT	NO	Spot Level
26/APCH 08/TKOF	FENCE	243705.6N 0735438.2E	1679 FT	NO	Airport Boundary Wall With F/T
26/APCH 08/TKOF	OTHER	243705.6N 0735437.7E	1681 FT	NO	Mobile Road Traffic (Road Elev. 507.4 M + Traffic Ht. 5 M)
26/APCH 08/TKOF	OTHER	243710.1N 0735437.0E	1664 FT	NO	Approach Light
26/APCH 08/TKOF	OTHER	243706.3N 0735442.2E	1672 FT	NO	Gate Top
26/APCH 08/TKOF	FENCE	243715.4N 0735442.0E	1674 FT	NO	Airport Boundary Wall With F/T
26/APCH 08/TKOF	OTHER	243715.4N 0735443.0E	1676 FT	NO	Mobile Road Traffic (Road Elev. 505.8 M + Traffic Ht. 5 M)
26/APCH 08/TKOF	TREE	243707.8N 0735500.8E	1716 FT	NO	Group of Trees
26/APCH 08/TKOF	TREE	243706.9N 0735506.5E	1716 FT	NO	Group of Trees
26/APCH 08/TKOF	OTHER	243710.5N 0735512.9E	1737 FT	NO	Flood Light
26/APCH 08/TKOF	TREE	243713.0N 0735512.1E	1731 FT	NO	Group of Trees
26/APCH 08/TKOF	OTHER	243718.8N 0735510.6E	1732 FT	NO	Dust Pipe
26/APCH 08/TKOF	OTHER	243718.6N 0735510.8E	1732 FT	NO	Shed Structure
26/APCH 08/TKOF	OTHER	243718.5N 0735511.0E	1733 FT	NO	Conveyor Belt
26/APCH 08/TKOF	OTHER	243717.1N 0735510.8E	1727 FT	NO	Conveyor Belt

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
26/APCH 08/TKOF	OTHER	243717.4N 0735512.4E	1730 FT	NO	Dust Pipe
26/APCH 08/TKOF	OTHER	243717.9N 0735512.2E	1733 FT	NO	Shed Structure
26/APCH 08/TKOF	OTHER	243718.4N 0735512.8E	1731 FT	NO	Structure
26/APCH 08/TKOF	TREE	243717.5N 0735514.4E	1739 FT	NO	Group Of Trees
In circling area and at AD	OTHER	243652.7N 0735302.6E	1706 FT	NO	Security Hut
In circling area and at AD	BUILDING	243650.6N 0735257.0E	1715 FT	NO	House
In circling area and at AD	BUILDING	243701.7N 0735251.1E	1718 FT	NO	House
In circling area and at AD	TREE	243703.3N 0735251.6E	1748 FT	NO	Group of Trees
In circling area and at AD	OTHER	243656.6N 0735257.3E	1697 FT	NO	Localizer Monitor Antenna
In circling area and at AD	TREE	243702.5N 0735238.7E	1747 FT	NO	Group of Trees
In circling area and at AD	POLE	243645.9N 0735236.3E	1741 FT	NO	Electric Pole
In circling area and at AD	POLE	243702.4N 0735244.6E	1738 FT	NO	Electric Pole
In circling area and at AD	OTHER	243753.0N 0735134.4E	1886 FT	NO	Cell Phone Mast
In circling area and at AD	OTHER	243753.3N 0735136.6E	1886 FT	NO	Cell Phone Mast
In circling area and at AD	OTHER	243738.0N 0735144.5E	1871 FT	NO	Cell Phone Mast
In circling area and at AD	OTHER	243726.4N 0735145.3E	1864 FT	NO	Cell Phone Mast (BSNL)
In circling area and at AD	OTHER	243819.5N 0735301.4E	2085 FT	NO	Dhuni Mata Temple on Hill
In circling area and at AD	STACK	243703.5N 0735057.9E	1839 FT	NO	Chimney
In circling area and at AD	TREE	243653.4N 0735321.0E	1730 FT	NO	Group of Trees
In circling area and at AD	TREE	243654.4N 0735320.8E	1724 FT	NO	Group of Trees
In circling area and at AD	OTHER	243655.2N 0735320.6E	1692 FT	NO	Mobile Road Traffic (Road Elev. 510.8 M + Traffic Ht. 5 M)
In circling area and at AD	OTHER	243657.5N 0735320.2E	1680 FT	NO	Bird Chaser Hut
In circling area and at AD	OTHER	243701.4N 0735319.4E	1681 FT	NO	Bird Chaser Hut
In circling area and at AD	FENCE	243704.1N 0735318.6E	1686 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	POLE	243704.0N 0735317.9E	1684 FT	NO	Light Pole on B/W
In circling area and at AD	OTHER	243702.4N 0735306.9E	1688 FT	NO	Security Shed

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
In circling area and at AD	OTHER	243702.6N 0735307.2E	1691 FT	NO	Gate Top
In circling area and at AD	OTHER	243702.4N 0735307.2E	1696 FT	NO	Mobile Road Traffic (Road Elev. 511.8 M + Traffic Ht. 5 M)
In circling area and at AD	FENCE	243703.0N 0735310.2E	1692 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	OTHER	243702.1N 0735310.8E	1706 FT	NO	WDI Top
In circling area and at AD	POLE	243703.6N 0735314.7E	1685 FT	NO	Light Pole on B/W
In circling area and at AD	OTHER	243703.3N 0735314.7E	1684 FT	NO	Security Hut
In circling area and at AD	OTHER	243700.3N 0735312.0E	1686 FT	NO	Bird Chaser Hut
In circling area and at AD	OTHER	243656.7N 0735313.2E	1683 FT	NO	Bird Chaser Hut
In circling area and at AD	FENCE	243654.8N 0735318.4E	1691 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	OTHER	243654.6N 0735316.2E	1695 FT	NO	Mobile Road Traffic (Road Elev. 511.6 M + Traffic Ht. 5 M)
In circling area and at AD	FENCE	243654.0N 0735312.9E	1697 FT	NO	Fence Top
In circling area and at AD	OTHER	243653.8N 0735310.6E	1704 FT	NO	Mobile Road Traffic (Road Elev. 514.4 M + Traffic Ht. 5 M)
In circling area and at AD	OTHER	243653.4N 0735307.2E	1708 FT	NO	Mobile Road Traffic (Road Elev. 515.7 M + Traffic Ht. 5 M)
In circling area and at AD	OTHER	243653.0N 0735306.6E	1710 FT	NO	Mobile Road Traffic (Road Elev. 516.1 M + Traffic Ht. 5 M)
In circling area and at AD	FENCE	243652.9N 0735304.7E	1708 FT	NO	Fence Top
In circling area and at AD	BUILDING	243652.3N 0735304.3E	1708 FT	NO	House
In circling area and at AD	BUILDING	243651.4N 0735303.9E	1711 FT	NO	House
In circling area and at AD	TREE	243649.6N 0735304.6E	1750 FT	NO	Group Of Trees
In circling area and at AD	OTHER	243652.7N 0735302.0E	1713 FT	NO	Mobile Road Traffic (Road Elev. 517.1 M + Traffic Ht. 5 M)
In circling area and at AD	FENCE	243652.3N 0735300.1E	1713 FT	NO	Fence Top
In circling area and at AD	OTHER	243652.2N 0735300.8E	1701 FT	NO	Mobile Road Traffic (Road Elev. 513.4 M + Traffic Ht. 5 M)
In circling area and at AD	POLE	243649.9N 0735258.2E	1724 FT	NO	Electric Pole
In circling area and at AD	POLE	243651.7N 0735258.1E	1724 FT	NO	Electric Pole
In circling area and at AD	BUILDING	243650.2N 0735257.7E	1728 FT	NO	Temple Top

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
In circling area and at AD	POLE	243651.4N 0735256.0E	1723 FT	NO	Electric Pole
In circling area and at AD	FENCE	243701.5N 0735259.4E	1695 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	OTHER	243701.4N 0735259.8E	1700 FT	NO	Mobile Road Traffic (Road Elev. 513.1 M + Traffic Ht. 5 M)
In circling area and at AD	TREE	243704.9N 0735252.3E	1766 FT	NO	Group of Trees
In circling area and at AD	TREE	243704.1N 0735251.5E	1762 FT	NO	Group of Trees
In circling area and at AD	TREE	243702.5N 0735251.1E	1738 FT	NO	Group of Trees
In circling area and at AD	TREE	243701.7N 0735252.9E	1730 FT	NO	Group of Trees
In circling area and at AD	POLE	243651.0N 0735254.0E	1722 FT	NO	Electric Pole
In circling area and at AD	TREE	243702.9N 0735246.4E	1745 FT	NO	Group of Trees
In circling area and at AD	BUILDING	243702.2N 0735246.2E	1729 FT	NO	Building
In circling area and at AD	TREE	243701.8N 0735246.9E	1751 FT	NO	Group of Trees
In circling area and at AD	TREE	243702.3N 0735242.7E	1751 FT	NO	Group of Trees
In circling area and at AD	TREE	243703.2N 0735241.0E	1753 FT	NO	Group of Trees
In circling area and at AD	TREE	243701.1N 0735238.7E	1751 FT	NO	Group of Trees
In circling area and at AD	OTHER	243733.9N 0734727.0E	2712 FT	NO	Hill Top
In circling area and at AD	OTHER	243838.0N 0734618.3E	3018 FT	NO	Light On Hill Pipli Ki Dhani (Hill Top 914.4 M)
In circling area and at AD	OTHER	243714.6N 0735430.5E	1679 FT	NO	Mobile Road Traffic (Road Elev. 506.9 M + Traffic Ht. 5 M)
In circling area and at AD	TREE	243711.2N 0735409.3E	1705 FT	NO	Group of Trees
In circling area and at AD	TREE	243713.7N 0735408.0E	1725 FT	NO	Group of Trees
In circling area and at AD	OTHER	243711.7N 0735414.6E	1675 FT	NO	Security Hut
In circling area and at AD	BUILDING	243711.3N 0735415.2E	1678 FT	NO	GP Hut Top
In circling area and at AD	OTHER	243711.3N 0735415.7E	1711 FT	NO	GP Main Antenna
In circling area and at AD	OTHER	243711.1N 0735415.6E	1683 FT	NO	GP DME
In circling area and at AD	OTHER	243711.6N 0735418.7E	1683 FT	NO	GP Monitor Antenna
In circling area and at AD	OTHER	243714.2N 0735430.7E	1672 FT	NO	Security Hut

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
In circling area and at AD	TREE	243714.9N 0735431.5E	1713 FT	NO	Group of Trees
In circling area and at AD	TREE	243703.6N 0735431.0E	1739 FT	NO	Group of Trees
In circling area and at AD	OTHER	243703.4N 0735422.2E	1673 FT	NO	Security Hut
In circling area and at AD	TREE	243700.8N 0735405.6E	1717 FT	NO	Group of Trees
In circling area and at AD	TREE	243700.7N 0735409.3E	1719 FT	NO	Group of Trees
In circling area and at AD	SIGN	243708.3N 0735408.7E	1671 FT	NO	Sign Board
In circling area and at AD	FENCE	243702.4N 0735414.8E	1678 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	OTHER	243704.0N 0735419.3E	1691 FT	NO	WDI
In circling area and at AD	OTHER	243709.1N 0735415.2E	1672 FT	NO	Bird Chaser Hut
In circling area and at AD	OTHER	243711.2N 0735415.7E	1682 FT	LGTD	GP DME (LGT)
In circling area and at AD	POLE	243711.1N 0735415.5E	1684 FT	NO	Pole Top
In circling area and at AD	TREE	243711.7N 0735414.6E	1687 FT	NO	Tree
In circling area and at AD	SIGN	243711.5N 0735425.9E	1667 FT	NO	Sign Board
In circling area and at AD	SIGN	243709.9N 0735426.2E	1666 FT	NO	Sign Board
In circling area and at AD	FENCE	243704.0N 0735426.5E	1676 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	TREE	243702.2N 0735428.9E	1735 FT	NO	Group Of Trees
In circling area and at AD	TREE	243700.6N 0735427.1E	1718 FT	NO	Group Of Trees
In circling area and at AD	TREE	243701.8N 0735431.1E	1732 FT	NO	Group Of Trees
In circling area and at AD	FENCE	243704.6N 0735431.0E	1677 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	TREE	243704.4N 0735434.2E	1720 FT	NO	Group of Trees
In circling area and at AD	TREE	243703.9N 0735437.8E	1726 FT	NO	Group of Trees
In circling area and at AD	TREE	243705.1N 0735435.0E	1711 FT	NO	Tree Over Airport Boundary Wall
In circling area and at AD	FENCE	243705.2N 0735435.0E	1676 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	SIGN	243710.1N 0735428.1E	1666 FT	NO	Sign Board
In circling area and at AD	SIGN	243711.8N 0735427.7E	1667 FT	NO	Sign Board
In circling area and at AD	FENCE	243714.3N 0735430.8E	1674 FT	NO	Airport Boundary Wall With F/T

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
In circling area and at AD	TREE	243714.9N 0735433.7E	1701 FT	NO	Group of Trees
In circling area and at AD	FENCE	243714.7N 0735434.0E	1673 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	OTHER	243714.7N 0735436.1E	1677 FT	NO	Mobile Road Traffic (Road Elev. 506.0 M + Traffic Ht. 5 M)
In circling area and at AD	OTHER	243706.5N 0735335.0E	1696 FT	NO	Windsock
In circling area and at AD	OTHER	243706.1N 0735334.7E	1693 FT	NO	Met Instrument
In circling area and at AD	OTHER	243657.3N 0735337.0E	1681 FT	NO	Security Hut
In circling area and at AD	ANTENNA	243710.7N 0735324.7E	1772 FT	NO	Antenna On Terminal Building
In circling area and at AD	ANTENNA	243710.9N 0735326.2E	1772 FT	NO	Antenna On Terminal Building
In circling area and at AD	TREE	243709.3N 0735349.3E	1711 FT	NO	Group of Trees
In circling area and at AD	TREE	243713.3N 0735358.1E	1732 FT	NO	Group of Trees
In circling area and at AD	TREE	243707.7N 0735402.2E	1684 FT	NO	Tree
In circling area and at AD	FENCE	243659.3N 0735352.0E	1675 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	FENCE	243657.4N 0735339.1E	1680 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	TREE	243656.2N 0735333.8E	1727 FT	NO	Group of Trees
In circling area and at AD	BUILDING	243655.5N 0735327.9E	1692 FT	NO	School
In circling area and at AD	FENCE	243655.5N 0735324.0E	1685 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	FENCE	243704.7N 0735322.4E	1684 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	POLE	243704.6N 0735321.7E	1683 FT	NO	Light Pole On B/W
In circling area and at AD	SIGN	243703.2N 0735323.3E	1678 FT	NO	Sign Board
In circling area and at AD	SIGN	243701.0N 0735321.9E	1680 FT	NO	Sign Board
In circling area and at AD	SIGN	243701.4N 0735323.6E	1679 FT	NO	Sign Board
In circling area and at AD	OTHER	243657.3N 0735322.3E	1680 FT	NO	Bird Chaser Hut
In circling area and at AD	FENCE	243655.2N 0735321.9E	1690 FT	NO	Airport Boundary Wall With F/T
In circling area and at AD	POLE	243656.0N 0735328.7E	1695 FT	NO	Light Pole
In circling area and at AD	OTHER	243658.3N 0735326.5E	1678 FT	NO	Bird Chaser Hut

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
In circling area and at AD	SIGN	243701.7N 0735325.8E	1679 FT	NO	Sign Board
In circling area and at AD	SIGN	243703.5N 0735325.4E	1678 FT	NO	Sign Board
In circling area and at AD	SIGN	243703.7N 0735328.2E	1677 FT	NO	Sign Board
In circling area and at AD	SIGN	243702.0N 0735328.6E	1678 FT	NO	Sign Board
In circling area and at AD	SIGN	243701.7N 0735327.4E	1679 FT	NO	Sign Board
In circling area and at AD	SIGN	243701.7N 0735327.0E	1679 FT	NO	Sign Board
In circling area and at AD	SIGN	243702.3N 0735330.6E	1678 FT	NO	Sign Board
In circling area and at AD	SIGN	243702.9N 0735330.6E	1677 FT	NO	Sign Board
In circling area and at AD	SIGN	243704.0N 0735330.5E	1677 FT	NO	Sign Board
In circling area and at AD	OTHER	243704.1N 0735333.5E	1678 FT	NO	Bird Chaser Hut
In circling area and at AD	SIGN	243702.4N 0735332.3E	1678 FT	NO	Sign Board
In circling area and at AD	OTHER	243703.4N 0735334.3E	1677 FT	NO	Bird Chaser Hut
In circling area and at AD	OTHER	243659.5N 0735335.1E	1677 FT	NO	Bird Chaser Hut
In circling area and at AD	POLE	243656.9N 0735334.3E	1684 FT	NO	Light Pole On B/W
In circling area and at AD	OTHER	243657.3N 0735337.4E	1682 FT	NO	Gate Top
In circling area and at AD	SIGN	243658.4N 0735337.1E	1678 FT	NO	Sign Board
In circling area and at AD	OTHER	243659.5N 0735339.3E	1677 FT	NO	Bird Chaser Hut
In circling area and at AD	SIGN	243705.0N 0735335.8E	1678 FT	NO	Sign Board
In circling area and at AD	OTHER	243704.3N 0735340.7E	1676 FT	NO	Bird Chaser Hut
In circling area and at AD	SIGN	243705.1N 0735338.1E	1677 FT	NO	Sign Board
In circling area and at AD	OTHER	243700.6N 0735341.6E	1677 FT	NO	Bird Chaser Hut
In circling area and at AD	TREE	243656.7N 0735341.0E	1708 FT	NO	Group of Trees
In circling area and at AD	TREE	243657.0N 0735343.0E	1713 FT	NO	Group of Trees
In circling area and at AD	SIGN	243703.8N 0735342.6E	1676 FT	NO	Sign Board
In circling area and at AD	OTHER	243705.3N 0735346.9E	1675 FT	NO	Bird Chaser Hut
In circling area and at AD	TREE	243710.1N 0735349.1E	1714 FT	NO	Group of Trees

In Approach/Take-off/Circling Area and at AD					
1	**2**	**3**	**4**	**5**	**6**
RWY/Area affected	Obstacle type	Coordinates	Elevation (EGM08)	Marking/LGT	Remarks
In circling area and at AD	SIGN	243706.7N 0735357.9E	1673 FT	NO	Sign Board
In circling area and at AD	OTHER	243703.1N 0735359.6E	1673 FT	NO	Bird Chaser Hut
In circling area and at AD	OTHER	243454.7N 0734602.3E	2336 FT	NO	Hill Top
In circling area and at AD	OTHER	243302.6N 0734342.2E	2231 FT	NO	Hill Top
In circling area and at AD	OTHER	243742.7N 0734415.1E	2743 FT	NO	Hill Top
In circling area and at AD	BUILDING	243930.0N 0735231.8E	2016 FT	NO	Factory Top
In circling area and at AD	OTHER	243519.7N 0735042.4E	2123 FT	NO	Solar Light on Hill Top
In circling area and at AD	OTHER	243407.5N 0734939.8E	2296 FT	NO	Temple On Hill Top
In circling area and at AD	OTHER	243535.6N 0734847.3E	2250 FT	NO	Hill Top
In circling area and at AD	OTHER	243430.5N 0734742.8E	2297 FT	NO	Hill Top
In circling area and at AD	OTHER	243435.3N 0734636.0E	2241 FT	NO	Hill Top
In circling area and at AD	OTHER	243107.1N 0735153.1E	2266 FT	NO	Hill Top
In circling area and at AD	OTHER	243147.9N 0734939.9E	2560 FT	NO	Solar Light On Hill Top
In circling area and at AD	BUILDING	243928.0N 0735231.7E	2060 FT	NO	Cement Factory
In circling area and at AD	OTHER	243424.6N 0734935.5E	2294 FT	NO	Temple On Hill Mahadev
In circling area and at AD	OTHER	243538.3N 0734845.9E	2324 FT	NO	Pylon Mast On Hill

VAUD AD 2.11 METEOROLOGICAL INFORMATION PROVIDED

1	Name of the associated meteorological office	Udaipur
2	Hours of service and, where applicable, the designation of the responsible meteorological office outside these hours	As ATS HR
3	Office responsible for preparation of TAFs and periods of validity and interval of issuance of the forecasts	Jaipur/Delhi 9 HR
4	Availability of the trend forecast for the aerodrome and interval of issuance	As ATS HR Frequency 30 Mins
5	Information on how briefing and/or consultation is provided	Met office contact no. 0294-2655362
6	Types of flight documentation supplied and language(s) used in flight documentation	Tabular Form English
7	Charts and other information displayed or available for briefing or consultation	Nil

8	Supplementary equipment available for providing information on meteorological conditions, e.g. weather radar and receiver for satellite images;	Nil
9	The air traffic services unit(s) provided with meteorological information	Udaipur ATC and ACS
10	Additional information, e.g. concerning any limitation of service.	Documentation provided O/R.

VAUD AD 2.12 RUNWAY PHYSICAL CHARACTERISTICS

Designations	TRUE Bearings	Dimensions of RWY (M)	Strength of pavement (PCN) and associated data) and surface of runway and associated stopways	Geographical coordinates for threshold and runway end
1	2	3	4	5
08	81.56 DEG	2741 x 45 M	78/F/C/W/T Asphalt	THR: 243659.60N 0735319.64E RWY END: 243709.80N 0735434.84E
26	261.56 DEG	2741 x 45 M	78/F/C/W/T Asphalt	THR: 243708.64N 0735426.23E RWY END: 243656.72N 0735258.41E

THR elevation and highest elevation of TDZ of precision APP RWY	Slope of runway and associated stopway	Dimensions of stopway (M)	Dimensions of clearway (M)	Dimensions of strips (M)
6	7	8	9	10
THR: 1679.1FT TDZ: 1674.2FT	-0.24%	NIL	--NIL	2861 x 280 M
THR: 1665.7FT TDZ: 1669.6FT	0.24%	NIL	--NIL	2861 x 280 M

Dimensions of runway end safety areas	Location and description of arresting system (if any)	Existence of an obstacle-free zone	Remarks.
11	12	13	14
190M x 90M		---	i) PCN of Turn Pad on RWY 08 & 26 End: 61/F/C/W/T; Asphalt ii) PCN of intermediate Turn Pad on RWY08: 66/F/C/W/T; Composite iii) PCN RWY 08: From beginning of RWY 08 to 215M: 78/F/C/W/T 215M to 370M: 66/F/C/W/T Composite 370M to 459M: 78/F/C/W/T 459M to 2282M: 98/F/C/W/T 2282M to 2341M: 78/F/C/W/T 2341M to 2496M: 66/F/C/W/T Composite 2496M to 2741M: 78/F/C/W/T iv) Vertical Datum: EGM08

Dimensions of runway end safety areas	Location and description of arresting system (if any)	Existence of an obstacle-free zone	Remarks.
11	12	13	14
170M x 90M	--	---	i) PCN of Turn Pad on RWY 08 & 26 End: 61/F/C/W/T; Asphalt ii) Vertical Datum: EGM08

VAUD AD 2.13 DECLARED DISTANCES

RWY Designator	Take-off run available TORA (M)	Take-off distance available TODA (M)	Accelerate distance available ASDA (M)	Landing distance available LDA (M)	Remarks (including runway entry or start point where alternative reduced declared distances have been declared)
1	2	3	4	5	6
08	2741	2741	2741	2137	THR displaced by 604M
26	2741	2741	2741	2496	THR displaced by 245M

VAUD AD 2.14 APPROACH AND RUNWAY LIGHTING

Runway Designator	Type, length and intensity of approach lighting system	Runway threshold lights, colour and wing bars	Type of visual slope indicator system	Length of runway touchdown zone lights
1	2	3	4	5
08	SALS 420 M LIH	Green	PAPI LEFT/3.00 DEG	NIL
26	CAT I 900 M LIH	Green	PAPI LEFT/3.00 DEG	

Length, spacing, colour and intensity of runway centre line lights	Length, spacing, colour and intensity of runway edge lights	Colour of runway end lights and wing bars	Length and colour of stopway lights	Remarks
6	7	8	9	10
NIL	2741 M 60 M White LIH	Red		NIL
NIL	2741 M 60 M White LIH	Red		Distance coded centreline pattern

VAUD AD 2.15 OTHER LIGHTING, SECONDARY POWER SUPPLY

1	Location, characteristics and hours of operation of aerodrome beacon/identification beacon (if any)	ABN	At Aerodrome Control Tower Building, FLG W&G EV2SEC. As ATS HR HO
		IBN	Nil

2	Location and lighting (if any) of anemometer/ landing direction indicator;	LDI	North of RWY
		Anemometer	Available. East of Apron I
3	Taxiway edge and taxiway centre line lights;	Edge	ALL TWY
		Centre Line	NIL
4	Secondary power supply including switch-over time;	Secondary Power supply Switch-over time 14 sec	
5	Remarks	NIL	

VAUD AD 2.16 HELICOPTER LANDING AREA

1	Geographical coordinates of the geometric centre of touchdown and lift-off (TLOF) or of each threshold of final approach and take-off (FATO) area	Not Established
2	TLOF and/or FATO area elevation:	Not Established
3	TLOF and FATO area dimensions to the nearest metre or foot, surface type, bearing strength and marking;	Not Established
4	True bearings of FATO;	Not Established
5	Declared distances available	Not Established
6	Approach and FATO lighting;	Not Established
7	Remarks	Not Established

VAUD AD 2.17 AIR TRAFFIC SERVICE AIRSPACE

1	Airspace designation, geographical coordinates and lateral limits	CTR: Circular area centered on 243706N 0735334E within a 10NM radius.
2	Vertical limits	FL 85
3	Airspace classification	D
4	Call sign and language(s) of the air traffic services unit providing service;	Udaipur Tower / Udaipur Approach, English
5	Transition altitude	6000 FT
6	Hours of applicability	HO
7	Remarks	NIL

VAUD AD 2.18 AIR TRAFFIC SERVICES COMMUNICATION FACILITIES

Service Designation	Call sign	Channel(s)	SATVOICE Number(s), if available
1	**2**	**3**	**4**
APP	Udaipur Approach	120.850 MHZ	
APP	Udaipur Approach	124.075 MHZ	
TWR	Udaipur Tower	118.650 MHZ	
TWR	Udaipur Tower	124.075 MHZ	
ATIS	---	128.850 MHZ	

Logon address, as appropriate	Hours of operation	Remarks
5	**6**	**7**

Logon address, as appropriate	Hours of operation	Remarks
	HO	1. Main Frequency
	HO	1. Backup Frequency
	As ATS	Main Frequency
	HO	1. Backup Frequency
	As ATS	NIL

VAUD AD 2.19 RADIO NAVIGATION AND LANDING AIDS

Type of aids, magnetic variation and type of supported operation for ILS/ MLS, basic GNSS, SBAS and GBAS, and for VOR/ILS/MLS station used for technical lineup of the aid	Identification	Frequency(ies), Channel number(s), Service provider, and reference path identifier(s) (RPI), as appropriate	Hours of operation, as appropriate;
1	2	3	4
LOC 26 CAT I	IUDR	109.900 MHz	As ATS
GP 26	IUDR	333.800 MHz	As ATS
DME ILS 26	IUDR	CH36X	As ATS
DVOR/DME	UUD	115.900 MHz CH106X	H24

Geographical coordinates of the position of the transmitting antenna	Elevation of transmitting antenna of DME/ elevation of GBAS reference point	Service volume radius from the GBAS reference point	Remarks
5	6	7	8
243655.6N 0735250.2E			
243711.1N 0735415.1E			1. Glide Angle: 3.0 DEG
243711.2N 0735415.0E	1683 FT		1. Collocated with GP 26 2. Gravity Model: EGM-08
243653.0N 0735337.7E	1709 FT		1.Gravity Model: EGM-08 2.DME Co-located with DVOR.

VAUD AD 2.20 LOCAL AERODROME REGULATIONS

• No Aircraft shall take lock turn/ pivotal turn on the Runway to avoid pavement damage.

LOW VISIBILITY PROCEDURES,

1. DEFINITIONS: -

1.1 ILS Critical Area: An area of defined dimensions about the localizer and glide path antennas where aircraft and vehicles are excluded during all ILS operations. The critical area is protected because the presence of vehicles / or aircraft inside its boundaries will cause unacceptable disturbance to the ILS signal-in-space.

1.2 ILS Sensitive Area: An area extending beyond the ILS critical area where the parking and/or movement of vehicles, including aircraft, are controlled to prevent the possibility of unacceptable interference to the ILS signal during ILS operations. The sensitive area Airports is protected to provide protection against interferences cause by large moving objects outside the critical area but still normally within the airfield boundary.

1.3 Low Visibility Procedures (LVP): Specific procedures applied at an aerodrome for the purpose of ensuring safe operations during Categories II and III approaches and/or low visibility take-offs.

Note: as per para 5.3 of CAR on All Weather Operations, an operator shall not conduct Take-off with RVR/Visibility less than standard CAT-I conditions of 550m RVR/800m Visibility unless low visibility procedures are enforced.

1.4 Low Visibility Take-Off (LVTO): A term used in relation to flight operations referring to a take-off on a runway where the RVR is less than 400m.

1.5 Maneuvering Area: That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.

1.6 Obstacle Free Zone: The airspace above the inner approach surface, inner transitional surface and balked landing surface and that portion of the strip bounded by these surfaces, which is not penetrated by any fixed obstacle other than of low mass and frangible mounting, required for air navigation purposes.

1.7 Runway Visual Range: The range over which the pilot of an aircraft on the centerline of a runway can see the runway surface markings or the lights delineating the runway or identifying its centreline.

1.8 Safeguarding Procedures: Safeguarding Procedures (SP) are instructions for relevant airport departments and airside operators to prepare ground services and facilities for low visibility operations, in order that when LVP are implemented all SP are complete and airport is configured for Low Visibility Procedures and Low Visibility Take-offs.

1.9 Missed approach procedure: - The procedure to be followed if the approach cannot be continued.

1.10 Aerodrome Operating Minima- The limits of usability of an aerodrome for:

a) take-off, expressed in terms of runway visual range and / or visibility and, if necessary, cloud conditions;

b) landing in 2 D instrument approach operations, expressed in terms of visibility and/or runway visual range; minimum descent altitude/height (MDA/H) and, if necessary, cloud conditions; and

c) landing in 3D instrument approach operations, expressed in terms of visibility and/or runway visual range and decision altitude/height(DA/H) appropriate to the type and/or category of the operation.

1.11 Touchdown Zone- The portion of a runway, beyond the threshold, where it is intended landing aeroplanes first contact the runway.

1.12 Visibility- Visibility for aeronautical purposes is the greater of:

a) the greatest distance at which a black object of suitable dimensions, situated near the ground, can be seen and recognized when observed against a bright background;

b) The greatest distance at which lights in the vicinity of 1000 candelas can be seen and identified against an unlit background.

Note 1. — The two distances have different values in air of a given extinction coefficient, and the latter b) varies with the background illumination. The former a) is represented by the meteorological optical range (MOR).

Note 2. — The definition applies to the observations of visibility in local routine and special reports, to the observations of prevailing and minimum visibility reported in METAR and SPECI and to the observations of ground visibility.

2. ABBREVIATIONS:

ADC: Aerodrome Control
ARFF: Airport Rescue and Fire Fighting Services
ATC: Air Traffic Control
ATM: Air Traffic Management
CFT: Crash Fire Tender
ATIS: Automatic Terminal Information Service
DG: Diesel Generating Set
LVP: Low Visibility Procedures
MET: Meteorology
OPS: Operations
RWY: Runway
RVR: Runway Visual Range
SMC: Surface Movement Control
SP: Safeguarding Procedures
TDZ: Touchdown Zone
TMO: Tower Metrological Officer
TWY: Taxiway

3. LOW VISIBILITY PROCEDURES:

3.1 Regulations: CIVIL AVIATION REQUIREMENT SECTION 8 - AIRCRAFT OPERATIONS SERIES 'C' PART I ISSUE II, DATED 28TH OCTOBER 2022:

- An operator shall not conduct take-off with RVR/visibility less than standard Category I conditions of 550m RVR/800 m visibility unless low visibility procedures are enforced.
- An operator shall not conduct low visibility take-offs in less than 400 m RVR unless approved by DGCA. Operators may be authorized LVTO minima of up to 75m. Foreign operators, who are authorized by their State Regulatory Authority for LVTO, shall submit requisite documents to DGCA for approval of LVTO at Indian aerodromes.

4. GENERAL:

4.1 Low visibility procedures have been developed for Maharana Pratap Airport, Udaipur to accommodate/permit departures in visibility/RVR less than 800M/550M from RWY 26 beginning (runway served with touchdown zone RVR instruments).
4.2 The Low Visibility Procedure (LVP) incorporates safeguarding measures to mitigate runway incursions and defines operational restrictions to ensure safe Airside Operations taking into account the available Aerodrome facilities.
5. MINIMUM REQUIREMENTS:
5.1 The following Aeronautical Ground lights and RVR equipment shall be serviceable to the required standard to support Low Visibility Procedures:
a) Runway edge lights,
b) Runway end lights,
c) Runway Guard Lights (available on TWY 'A', 'B', 'E' and 'F')
d) Instrument RVR (Available for TDZ runway 26).
e) Stand by Power supply to maintain switch over time of 1 Second for Runway Edge Lights and Runway End Lights. This requirement can be met with the help of DG Set and/or UPS.
5.2 Un serviceability of Aeronautical Ground Lights/ Equipment before Implementation of LVP.
Low Visibility Procedures will not be implemented when any of the light/equipment mentioned in para 5 above is un-serviceable or is not maintained as per the required standard.

Aeronautical Ground Lighting Facility	Un-serviceability	Restrictions
Runway Edge lights	More than 5% of all lights are unserviceable	LVP operations will be suspended.
	Any two consecutive lights or more are unserviceable	
Runway End lights	More than 15% of all lights are unserviceable	LVP operations will be suspended.
	Any two consecutive lights or more are unserviceable	
Standby Generators/UPS	Any of the generator/UPS is unserviceable	LVP operations will be suspended.

Note: When any of the light/equipment mentioned in para 5 above becomes unserviceable or fails to meet the required standard during periods of LVP, Tower shall advise the aircraft accordingly and LVP shall be suspended and information to this effect shall be included in ATIS broadcast.

5.3 Due to the unavailability of runway guard lights at taxiway C and D, aircraft operations at taxiway C and D shall be suspended during the Low Visibility operations.

5.4 Runway 26 beginning (full length) only will be used for departures under LVP.

5.5 Only one aircraft movement at a time shall be permitted in the movement area when the RVR is less than 550 metres.

6. Equipment and Services

6.1 RVR Equipments

a) DCWIS (Digital Current Weather Indication System) at Runway 26.

b) FSM (Forward Scatter Meter) at RUNWAY 26.

c) RVR is reported in the following scales:

i) The maximum reportable value of RVR is 2000 m. When RVR is above 1500 m, it is reported as 2000 m.

ii) In the increments 100 m when greater than 800 m.

iii) In the increments 50 m when RVR greater than 400 m but less than 800 m.

iv) In the increments 25 m when less than 400 m. (as per Annex 3, Appendix 3, 4.3.6.1)

d) In case of unserviceability of the above mereological equipments, the LVP shall be suspended.

6.2 ILS

6.2.1 Runway 26 is equipped with CAT I ILS.

7. SAFEGUARDING PROCEDURES

7.1 Safeguarding Procedures (SP) are instructions for relevant airport, departments and airside operators to prepare ground services and facilities for low visibility operations in order that when LVP are implemented all Safeguarding procedures are complete.

7.2 Safeguarding Procedures shall be initiated when-

a) The Visibility/RVR is less than 1200m and visibility/RVR is forecast to deteriorate to 800m or less; and/or

b) The cloud ceiling is less than 400ft and forecast to fall to 200ft or less.

7.3 Safeguarding procedures include-

a) Positioning of CFTs as per visibility standby procedures.

b) Stopping of all maintenance works on the manoeuvring area, ILS sensitive and critical area as removal of all men and mobile equipment from the said area.

c) Ensuring availability of secondary power supply for change over time of maximum one second for Runway Edge and Runway End lights supported by UPS.

d) The appropriate Aeronautical ground lights must have been inspected during the hour preceding implementation of LVP, and thereafter once every two-hour period. These lighting inspections should be accorded priority and, if necessary, aircraft operations may be delayed.

e) The mandatory serviceability requirements of the Aerodrome Ground Lightings (AGLs) system shall be maintained as per CAR Section 4, Series B, Part I, Para 10.5.11, through inspection by Follow-Me with Electrical personal and reporting to ATCO prior to each departure when the RVR is less than 550 metres.

Note- Runway Edge and Runway End lights may continue to operate on main power supply during safe Guarding Procedures. Whenever, LVP is to be implemented as per para 9 below, the Runway Edge and Runway End lights shall be put on Standby Power Supply (DG set or UPS). This operation needs to be completed before LVP is implemented. In case of DG set, Main power supply shall act as stand by power. If UPS is capable of maintaining the required AGL system with one second of Switch Over time with Main Supply, the main supply can continue to be primary supply and the Generator Supply can be kept as Stand by Power supply.

f) Operations department shall ensure that all runway access roads are closed.

7.4 Process of initiation of Safeguarding Procedures-

a) When meteorological conditions meet the criteria for initiation of SP as stipulated in Para 7.2, the Tower Supervisor/Duty Officer will initiate and cocoordinate with CCR, SSO (CNS), Duty Terminal Manager and Fire Station for completion of safeguarding procedures before implementation of Low Visibility Procedures.

b) When all the CCR, SSO (CNS), Duty Terminal Manager and Fire Station have completed their necessary actions, they shall report to Tower Supervisor/Duty Officer that their Safeguarding Procedure (SP) is completed and the airport is safeguarded for LVP operations

8. LOW VISIBILITY OPERATIONS

Low Visibility Procedures are the procedures to ensure the safe operation of aircraft during periods of reduced visibility or low cloud base. LVP shall only be implemented when Safeguarding Procedure (SP) has been completed and the airport is configured for low visibility operations.

8.1 Implementation of Low Visibility Procedures-

a) Whenever Visibility/RVR reduces to 800 Meters or below and/ or cloud ceiling is at 200 ft or below the Tower Supervisor/ Duty Officer shall coordinate with CCR, SSO (CNS), Duty Terminal Manager and Fire Station to confirm whether the Safeguarding procedures have been completed or not.

b) Once, it is confirmed that Safeguarding Procedures are implemented and LVP is necessitated, the Tower Supervisor/Duty Officer will implement Low Visibility Procedures and shall inform CCR, SSO (CNS), Duty Terminal Manager and Fire Station of the imposition of low visibility procedures.

8.2 Actions by Tower Controller

a) Whenever visibility/RVR is less than 800M/550M, Tower shall confirm from pilot that the reported RVR value is within minima before issuing take-off clearance.

b) Tower shall ensure that the towing of aircraft is done under escort of “Follow Me” vehicles. “Follow Me” shall inform ATC of any deviation from the route cleared by ATC;

c) Tower shall not permit any high-power ground run on the manoeuvring area except idle power run on the stands.

d) In case high power engine run-up is in progress, the same shall be stopped whenever RVR reduces below 550m and towed back to respective stand.

e) Tower shall ensure that “Follow Me” services are provided to pilots on request;

f) The number of vehicles on the manoeuvring area shall be restricted to bare minimum and records of all operating on the manoeuvring area shall be maintained by Tower.

g) Check ATIS broadcast and include the message that “Low Visibility Procedures in Force”. If ATIS is not available inform aircrafts on VHF.

8.3 Actions by SSO

.

8.3.1 On receipt of “Initiating SP” from Tower Supervisor/Duty Officer, SSO will inform the Duty Officer, NAV AIDS and have the ILS equipment and its status indicators in ATC units checked up.
8.3.2 On receipt of “Initiating LVP” from Tower Supervisor/Duty Officer that LVP are to be made effective SSO will maintain continuous watch on the performance of ILS equipment.
8.3.3 He will inform Tower Supervisor/Duty Officer of any unserviceability in the equipment which is likely to affect Low Visibility operations.
8.4 Actions by Duty Terminal Manager (Airside)
8.4.1 On receipt of advice from Tower Supervisor/Duty Officer to implement Safeguarding procedure, the Terminal Duty Manager, will immediately inform the following:
a) Central Industrial Security Force (CISF) Control Room
b) All airlines/GHA.
c) Civil In-charge
8.4.2 Duty Terminal Manager (Airside) shall ensure that-
a) No vehicle/person enters or is present in the sensitive/critical areas of localizer and glide path.
b) All civil/electrical works in progress are to be stopped in the manoeuvring area immediately and men/material/ equipment to be removed from the sensitive/critical areas of localizer and glide path.
8.4.3 Duty Terminal Manager (Airside) would advise Tower Supervisor/Duty Officer when all actions allocated to them are completed.
8.4.4 Subsequently, Duty Terminal Manager shall remain available in apron and will maintain listening watch on Walkie-Talkie.
8.4.5 The vehicles which are not equipped with RT but has to enter the runway or taxiway for urgent operational requirement shall be escorted all the time.
8.4.6 Duty Terminal Manager (Airside) shall ensure that all the roads are closed during the Low Visibility Operations, except the Fire approach road and designated PDPs.
8.5 Actions by Shift In-Charge (Civil)
8.5.1 Shift In-Charge (Civil) to ensure that all civil works in progress in manoeuvring area, are stopped and that the work area is restored in complete serviceable condition and confirm to Tower Supervisor/Duty Officer accordingly.
8.5.2 Shift In-Charge (Civil) to ensure that during Low Visibility Operations, no equipment, manpower shall be present in sensitive areas of localizer and glide path.
8.5.3 Shift In-Charge (Civil) to ensure that none of the civil contract workers/vehicles shall enter the manoeuvring area during the Low Visibility operations.
8.6 Actions by Shift In-Charge (Electrical)
8.6.1 On receipt of advice to implement Low Visibility Procedures from Tower Supervisor/Duty Officer, will check that following visual aids are serviceable and can be operated at full intensity:
a) Approach lighting system
b) Runway edge lights
c) Runway threshold and end lights
d) Runway guard lights
e) Taxiway edge lights
(NOTE - No adjustment in light intensity shall be made without permission from ATC Tower during LVP)
8.6.2 Shift In-Charge (Electrical) shall ensure that no electrical maintenance works is carried out during LVP either in power house or on any other electrical facilities used during Low visibility operations.
8.6.3 Shift In-Charge (Electrical) will ensure that Runway switch room is manned and position themselves at halls for ground lighting facilities.
8.6.4 Shift In-Charge (Electrical) will inform the un-serviceability or any change in status of any facility/systems to Tower Supervisor/Duty Officer immediately.
8.6.5 Shift In-Charge (Electrical) shall ensure the electrical personal is available in follow me vehicle for the AGL inspections before each departure during LVP implementation.
8.7 Actions by ARFF
8.7.1 Positioning CFTs as per visibility standby procedures.
8.7.2 ARFF/ CFTs must obtain clearances from Tower prior to entry to movement area.
8.8 Actions by Tower Met Officer (Meteorological Office)
8.8.1 Tower Met Officer would issue an 'Outlook for Low Visibility Procedures' to the Tower Supervisor/Duty Officer of air traffic services whenever he expects that the RVR and/or cloud ceiling will fall below 800 m and/or 200ft or less respectively.
8.8.2 Whenever Tower Met Officer visualizes that RVR is likely to fall below 800 m and/or cloud ceiling to 200ft or less within next 2 hours, he will inform to Tower Supervisor/Duty Officer to this effect.
8.8.3 When the RVR and/or cloud ceiling are 800m and/or 200ft respectively and the trend is towards improvement in these elements of weather conditions the Duty Met Officer may, when requested by Tower Supervisor/Duty Officer, advise him about such improving weather conditions for the purpose of termination of LVP.
8.8.4 The Tower Met Officer shall be present in Tower during periods of reduced visibility and ensure that the RVR displays in ATC units in the Tower and Approach Control are serviceable.

9. TERMINATION OF LOW VISIBILITY PROCEDURES

9.1 When Visibility/RVR improves to 800M or more and cloud ceiling is 200 feet or Higher and trend is for improvement, Tower Supervisor/Duty Officer Tower would terminate operations of LVP. He may obtain advice from Tower Met Officer regarding improvement in weather conditions before the termination of LVP.

9.2 On termination of LVP, following message shall be included in two subsequent ATIS broadcasts. “LOW VISIBILITY PROCEDURES TERMINATED”. If ATIS is not available inform aircrafts on VHF.

9.3 If SP are implemented and LVP are not subsequently implemented and the visibility/RVR improves and is more than 1200 m and/or the cloud ceiling is 400ft or higher and both are forecast to remain above the required SP criteria, Tower Supervisor/ Duty Officer Tower may cancel SP.

10. OTHER ACTIONS

a) Every year before commencement of monsoon/winter season, a meeting will be held by Airport Director, to inform all airlines and agencies operating at airport about their roles/responsibilities and create awareness to ensure co-operation for safe airport operations during periods of low visibility.

b) Before issuing the Airside driving permits, the OPS Incharge shall ensure that staff and drivers are suitably trained for Low Visibility operations.

c) All agencies operating in the operational area shall ensure that only those vehicles that are absolutely essential for aircraft operations operate in the operational area during periods of low visibility. The drivers of these vehicles should keep a look out for taxiing aircraft and other vehicles to prevent accidents.

d) All the vehicles must have their obstruction lights “ON” during Low Visibility Procedures operations.

e) A refresher program for ATCO’s and personnel responsible for airside operations shall be conducted every year.

VAUD AD 2.21 NOISE ABATEMENT PROCEDURES

NIL

VAUD AD 2.22 FLIGHT PROCEDURES

NIL

VAUD AD 2.23 ADDITIONAL INFORMATION

I. All 180 degrees turn on RWY should be made only on turn pad.

II. NON- SKED operator to take positive clearance from Udaipur ATC at least 24 HRS in Advance due to shortage of parking bays.

III .Pushback and Taxi Procedure in Apron I:

1. When either or all of stands 6, 7 and 8 are occupied, stands no. 4 and 5 are to be kept vacant and when either or both stands 4 and 5 are occupied, stands no. 6, 7 and 8 are to be kept vacant.
2. Aircraft from Stand Nr 5 to pushback facing east only and to exit apron via TWY B.
3. Aircraft from Stand Nr 1 to pushback facing west only and to exit apron via TWY A.

IV. Pushback and Taxi Procedure in Apron II:

(i) Aircraft from stand 13 to pushback facing east only and to enter and exit apron only via TWY 'E'.

(ii) Stand no. 13A to 18A are suitable for code 'C' type of aircraft (maximum wing span & length 27.5 m).

(iii) Aircraft parked on stand 13A to 18A to taxi out only when at least one adjacent stand is vacant and no code C aircraft more than 27.5 m of length and 27.5 m of wing span is parked between taxi out stand and vacant stand.

V. Runway Turn Pad, capable of handling B777-300 ER type of aircraft, provided at both ends of Runway 08/26 for Special Operations with prior permission.

VI. Taxiway Intersection Departure Distance (TORA) RWY 08:

TAXIWAY	TORA(M)
E	**2289**
F	**2112**
A	**1988**
B	**1848**
C	**1415**

VII. Taxiway Intersection Departure Distance (TORA) RWY 26:

TAXIWAY	TORA(M)
B	**893**
C	**1326**
D	**2525**

VIII. Intermediate Turn Pads:

1) Intermediate turn pad RWY 26 is available, the details of this turn pad are as below:
a) LCA: 245 M from the beginning of RWY 26 .
b) LGT: Edge Light
c) TORA available for departure from intermediate turn pad RWY 26: 2496 M

2) Intermediate turn pad RWY 08 is available, the details of this turn pad are as below:
a) LCA: 215 M from beginning of RWY 08 .

b) LGT: Edge Light
c) TORA available for departure from intermediate turn pad RWY 08: 2526 M.

IX. VVIP B777-300ER parking Details:

a) On Apron II (Facing East).
b) Status of Aircraft stand: Power-in Power Out (Facing East).
c) Connecting taxiway: Entry via TWY E & Exit via TWY F.
d) When B777-300ER is parked no other aircraft can be parked on Apron II.

VAUD AD 2.24 CHARTS RELATED TO AN AERODROME

1. Aerodrome Chart(17 April 2025)
2. Aircraft Parking/Docking Chart (17 April 2025)
3. Aerodrome Obstacle Chart Type-A (Obstacle Limitations) RWY 08
4. Aerodrome Obstacle Chart Type-A (Obstacle Limitations) RWY 26
5. Instrument Approach Chart - ILS or LOC Procedure RWY 26
6. Instrument Approach Chart - VOR Procedure RWY 26
7. RNP Procedure RWY 26 (17 April 2025)
8. Coding Table - RNP Procedure RWY 26 (17 April 2025)
9. Coding Table - RNP Procedure RWY 26-FASDB (17 April 2025)

VAUD AD 2.25 VISUAL SEGMENT SURFACE (VSS) PENETRATION

Procedure	Procedure Minima	VSS Penetration
1	**2**	**3**